



[milwaukee.gov/supportforbusiness](http://milwaukee.gov/supportforbusiness)

### St. Paul Bridge Construction Update

The St. Paul Avenue vertical lift bridge is getting closer to completion. Zenith Tech has poured the west and east approach spans on either side of the lift span. The lift span steel erection has started, and is anticipated to continue for the next few weeks. Work also continues in the bridge house to address architectural, mechanical, electrical and plumbing upgrades, and also in the piers for hydraulics and counterweights for the lift span.

Much of the interior of the bridge house has been gutted. New electrical, mechanical, and control equipment is being installed, and the windows and roof are being replaced. The bridge house bell has been removed for refurbishing, and will be reinstalled on the new bridge house roof.



Prepping for the pouring of the concrete on the west approach



The bell on the bridge house is being removed for refurbishing. It will be put back into place once the bridge house is completed.



Pouring the concrete on the west approach of the bridge.



The new roof of the St. Paul Avenue bridge being lifted into place.



Support for Business Liaison • Cecilia Gilbert • (414) 286-3318 • [cecilia.gilbert@milwaukee.gov](mailto:cecilia.gilbert@milwaukee.gov)

Project Manager • Bill Frasch

A Publication of the City of Milwaukee Department of Public Works

