



APPROXIMATE DEMOLITION PROJECT LIMITS

RUBBLE/SOIL PILE

STAGING AREA (IF NEEDED)

TOTAL PARCEL AREA
2.2 ACRES

BACKFILL SUBSURFACE VOIDS TO GROUND SURFACE



- NOTES:
1. PROTECT MONITORING WELLS MW-1, MW-3, MW-6 THROUGH MW-8, AND TW-4 THROUGH TW-7 DURING DECONSTRUCTION. THESE MONITORING WELLS ARE TO REMAIN IN PLACE FOR DURATION OF DECONSTRUCTION PROJECT.
 2. MONITORING WELLS MW-2 AND MW-4 HAVE ALREADY BEEN ABANDONED AND ARE NO LONGER PRESENT.
 3. INTERIOR BASEMENT WALLS AND COLUMNS NOT SHOWN BUT TO BE REMOVED AS DESCRIBED IN TECHNICAL SPECIFICATIONS.
 4. FILL MATERIAL SLOPED FROM GROUND SURFACE DOWN TO BASEMENT FLOOR LEVEL SHALL BE KEPT AT LEAST 5 FEET FROM EASTERN BUILDING/RETAINING WALL.

