

NATIONAL AVENUE NEWS

A PUBLICATION OF THE CITY OF MILWAUKEE DEPARTMENT OF PUBLIC WORKS

www.city.milwaukee.gov/mpw/supportforbusiness/Projects.htm



PUBLIC WORKS
SUPPORT FOR BUSINESS
PROGRAM

VOLUME 1 • ISSUE 2 • DECEMBER 16, 2010

2010-2011 PROJECT SCHEDULE

- **Stage One: COMPLETE**
September—mid-November
Asphalt and concrete work
at corners. (Some parking
at corners restricted)
- **Stage Two: COMPLETE**
Mid-November - mid
December
Construct the median island
curb and walls. (Traffic re-
stricted in center travel
lane)
- **Spring 2011**
Complete any remaining
concrete work, pavement
markings, plantings, and
street lighting.

Project Contacts

Construction Supervisor
Lynn Des Jardins

Construction Inspector
Victor Buell
City of Milwaukee DPW
414-303-8691

Community Liaison
Kris Martinsek
Martinsek & Associates
414-769-0400 (office)
martinsek.national@gmail.com

STREETSCAPE WORK WRAPS UP FOR 2010

All stage one and stage two construction work planned for National Avenue between South 27th and South 39th Streets has been completed for 2010.

The completed work at the intersection corners includes curb push-outs at some locations, stamped colored concrete walk and pedestrian ramps with detectable warning fields. Adjacent to the curbs, the pavement was milled and new asphalt installed to match existing roadway.



With work completed on the intersection corners, crews moved to the medians. New median islands were installed from S. 34th to S. 36th Streets and planter walls were poured before cold weather

set in. Existing median islands at S. 28 and S. 30th Streets were improved.



The new median islands with planter walls like this one just east of 35th Street will be filled and planted in Spring of 2011

Work to realign the traffic lanes on S. 35th Street at National to improve traffic flow and safety was also completed. City crews have also begun work to install new decorative street lighting.

WHAT'S PLANNED FOR 2011

Completion of the National Avenue streetscaping will occur in Spring 2011. Stamped concrete will be placed around the median islands adjacent to the planter walls and decorative fencing will be installed. The planters will be filled with soil and planted with flowers. Several trees will also be included in the plantings. Work will continue installing new poles and streetlights.

When temperatures climb above 50°, decorative Dura-Therm™ crosswalks will be installed at select intersections. Dura-Therm is a preformed thermoplastic pavement marking that can be installed in decorative patterns.