



Department of Public Works  
 Infrastructure Services Division  
 Environmental Engineering Section

## Stormwater Management Plan As-Built Certification

As required by Chapter 120 of the City of Milwaukee Code of Ordinance, as-built certification is required after construction of the stormwater management Best Management Practices (BMPs) listed in section 14 of the City of Milwaukee Stormwater Management Plan (SWMP) Application and associated facilities have been completed. The as-built certification shall be prepared and stamped by a registered professional engineer.

### As-Built Submittal Documentation

- As-Built Certification Statement** - A certification statement provided by a Professional Engineer stating the Structural BMPs and associated facilities have been constructed per the approved Storm Water Management Plan (SWMP).
- Record Drawings** - The record drawing must include the following:
  - Structural BMP(s)** - Confirm the major contour grades and elevations in plan and cross section drawings. At a minimum, ensure all critical elevations are provided including, but not limited to, the emergency overflow, top and bottom of the BMP, and at any interface in which the storage material changes. Annotate any information that differs from the proposed design. Provide a summary table comparing the proposed and as-built storage totals.
  - Outlet Structure(s)** - Confirm the elevations and sizes for any overflow RIM, underdrain, and discharge control devices. Annotate any information that differs from the proposed design.
  - Storm Sewer Structures and Conveyance** - Confirm the location, size, inverts, and material of all proposed storm structures and pipes. Annotate any information that differs from the proposed design.
  - Additional Information** - Provide any other relevant as-built information necessary to verify stormwater function, such as manufacturer's certificates of proper installation, plumbing details/plans, testing results, etc.
- As-Built Photos (optional)** - Photos of structural BMPs.

Submit the As-Built certification documents electronically to [antjaz@milwaukee.gov](mailto:antjaz@milwaukee.gov).

The As-Built Certification submittal shall be reviewed by the City within 10 working days. Additional information and/or corrections may be requested to ensure the site is meeting all stormwater requirements including, but not limited to, the SWMP application and hydrologic/hydraulic and water quality modeling.

After the City Engineer approves the certification, the owner and preparer will be notified by email and that portion of the guarantee not utilized under s. 120-17 shall be released or returned to the owner by certified mail. If the BMPs are found to be in violation of Chapter 120 of the City of Milwaukee Code of Ordinance, the development shall be subject to the enforcement procedures and penalties set forth in s. 120-17.

For additional information, please contact Tony Jazdyk at (414) 286-2355 or at the email above.



Department of Public Works  
Infrastructure Services Division  
Environmental Engineering Section

### As-Built Certification Statement

STATE OF WISCONSIN-MILWAUKEE COUNTY

I, \_\_\_\_\_ a registered professional engineer, certify that:  
*Name*


- 1. All stormwater best management practices (BMPs), stormwater infrastructure, and land covers have been built substantially in accordance with the approved Stormwater Management Plan (SWMP) for \_\_\_\_\_ located at \_\_\_\_\_.  
*SWMP Name* *Development Address*  
Any deviations noted in the enclosed as-built plans will not prevent the system from functioning in compliance with the requirements of Chapter 120 of the Milwaukee Code of Ordinances when properly maintained and operated.
- 2. These determinations have been based upon on-site observation of construction, scheduled and conducted by me or by a project representative under my direct supervision.
- 3. A summary of the deviations from the approved SWMP is provided below (attach additional sheets as necessary):

\_\_\_\_\_  
*Signature*

\_\_\_\_\_  
*Date*

\_\_\_\_\_  
*Company Name*

\_\_\_\_\_  
*License Number*



Affix Seal