

OFFICIAL NOTICE

PUBLISHED BY THE DEPARTMENT OF NEIGHBORHOOD
SERVICES OF THE CITY OF MILWAUKEE

INVITATION FOR BIDS FOR MECHANICAL DEMOLITION PROJECT OPENING 5-19-20

THE COMMISSIONER OF THE DEPARTMENT OF NEIGHBORHOOD SERVICES OF THE CITY OF MILWAUKEE ("Commissioner"), Milwaukee, Wisconsin, acting pursuant to Sec. 7-22-3, Milwaukee City Charter, will receive sealed bids for furnishing all labor and materials and performing all work necessary for and incidental to the demolition of ten (10) primary buildings and three (3) secondary buildings located in the city of Milwaukee, Wisconsin, until **9:00 a.m.(central time) on Monday, May 18, 2020. Bids must be dropped off in the secure drop box labeled Demo Bids & Decon RFPs outside of Room 105 and 841 North Broadway. Any bids deposited in the wrong location or received after that time may be rejected and returned unopened. Bids will be opened and read on Tuesday, May 19, 2020. The bid opening will be made public by internet video conference only. Bidders wishing to observe the opening must provide their preferred email contact information legibly written or printed on the envelope of their sealed bid. Login and connection information will be emailed to participants. Others wishing to observe the bid opening may submit an email to ckraco@milwaukee.gov with "bid opening 05192020" in the subject line to receive login and connection information.**

1. Bids shall be awarded to lowest, qualified, responsive, and responsible bidder on a per parcel basis.
2. All bids shall be held open for a period of sixty (60) days subsequent to the opening of bids and no bid may be withdrawn without the written consent of the Commissioner. **IN THE EVENT THE COMMISSIONER, DURING THE SIXTY DAYS FOLLOWING BID OPENING, TAKES NO ACTION RELATIVE TO THE BID OR BIDS RECEIVED, THEN THE BID OR BIDS SHALL BECOME NULL AND VOID WITHOUT RECOURSE OF ANY KIND BY EITHER THE BIDDER OR COMMISSIONER, ACTING ON BEHALF OF THE CITY.**

As part of the bid, each bidder shall submit a full and complete list of all the proposed subcontractors and the class of work to be performed by each, which list shall not be altered without the written consent of the Commissioner.

The Commissioner reserves the right to reject any and all bids at any time, if it is in the best interests of the City, and to waive any informalities in bidding.

Attention is called to the fact that: (a) the successful bidder will not discriminate against any qualified employee or qualified applicant for employment because of sex, race, religion, color, national origin or ancestry, age, disability, lawful source of income, marital status, sexual orientation, gender identity or expression, past or present membership in the military service, familial status, or based upon affiliation with, or perceived affiliation with any of these categories as provided by Section 109-9 of the Milwaukee Code of Ordinances. This provision must be included in all subcontracts. (b) Contractor agrees that they will comply with all applicable requirements of the Americans with Disabilities Act of 1990, 42 U.S.C. 12101 et seq. (c) both parties understand that the City is bound by the Wisconsin Public Records Law, and as such all of the terms of this Agreement are subject to and conditioned on the provisions of Wis. Stat. Section 19.21, et seq. Contractor acknowledges that it is obligated to assist the City in retaining and producing records that are subject to Wisconsin Public Records Law, and that the failure to do so shall constitute a material breach of this Agreement, and that the Contractor must defend and hold the City harmless from liability under that law. Except as otherwise authorized, those records shall be maintained for a period of seven (7) years after receipt of final payment under this Agreement.

Successful bidder will be required to complete an Affidavit of Compliance/Disclosure of Participation in or Profits Derived from Slavery by Contractors before contract can be executed, if the company was established in or before 1865.

Small Business Enterprise (SBE) requirement for this project is 25% of the contract base bid.
For a complete listing of City of Milwaukee certified SBE firms please contact the Office of Small Business Development at 414-286-5534. More information can be found at www.milwaukee.gov/osbd

This bid includes a Local Business(LBE) incentive in accordance with Chapter 365 Milwaukee Code of Ordinances.

IT IS YOUR RESPONSIBILITY AS A BIDDER TO FAMILIARIZE YOURSELF WITH THIS ORDINANCE PRIOR TO SUBMITTING YOUR BID.


This bid includes Socially-Responsible Contractors (SRC) incentive in accordance with Chapter 310 Milwaukee Code of Ordinances. More information can be found at <https://city.milwaukee.gov/Purchasing/Programs/Socially-Responsible-Contractors-SRC-Program>.

COPIES OF THE CONTRACT DOCUMENTS MAY BE OBTAINED ELECTRONICALLY AT <http://city.milwaukee.gov/Demobids>

PRINTED COPIES MAY BE PURCHASED IN PERSON AT THE DEPARTMENT OF NEIGHBORHOOD SERVICES AT THE ADDRESS SHOWN BELOW. THE COST IS \$.20 PER PAGE.

Anyone who requires an auxiliary aid or service for this event should contact the City of Milwaukee ADA Coordinator @ (414) 286-3475 or ADACoordinator@milwaukee.gov as soon as possible but *no later than 72 hours before the scheduled event.*

This material is available in alternative formats for individuals with disabilities upon request. Please contact the City of Milwaukee ADA Coordinator @ (414) 286-3475 or ADACoordinator@milwaukee.gov. Provide a 72 hour advance notice for large print and 7 days for braille documents.



DEPARTMENT OF NEIGHBORHOOD SERVICES
OF THE CITY OF MILWAUKEE
841 NORTH BROADWAY RM 105
MILWAUKEE WI 53202-3650

May 4, 2020
May 6, 2020

BID DOCUMENTS
FOR
MECHANICAL DEMOLITION PROJECT

OPENING TUESDAY, MAY 19, 2020

BIDS MUST BE RECEIVED IN DROP BOX BY MONDAY, MAY 18, 2020 AT 9:00 A.M.

Milwaukee, Wisconsin

DEPARTMENT OF NEIGHBORHOOD SERVICES

CITY OF MILWAUKEE

Room 105

841 North Broadway

Milwaukee, Wisconsin 53202-3650

**WHEN SUBMITTING A BID FOR THIS PROJECT, PLEASE
USE FORMS INCLUDED IN THIS PACKET.**

5.0.0

TECHNICAL SPECIFICATIONS

(for this contract only)

5.1.0. PARCEL LOCATIONS AND DESCRIPTION OF STRUCTURES FOR MECHANICAL DEMOLITION PROJECT OPENING TUESDAY, MAY 19, 2020

Parcel numbers, street addresses, approximate sizes of main structures to be demolished under this contract are listed in Section 5.7.0.

5.2.0. WORK BY OTHERS

Certain disconnections from utilities to be made by others are noted under sec. 4.3.23., entitled "Utility Services: Protection and Disconnection."

5.3.0. WORK NOT INCLUDED IN CONTRACT

- A. Work mentioned in Technical Specifications as not being a part of this contract.
- B. Replacing of curb and walk removed in connection with demolition of street walk basements (sidewalk vaults).
- C. Trees which are not damaged and are not obstructions to demolition as interpreted by the Commissioner, or unless otherwise noted in the Technical Specifications.

5.4.0. DEMOLITION WORK WITHIN PARCELS

- A. The structures, including foundation walls, columns, piers, floors, partitions, and attached appurtenances shall be removed down to a level two feet below the present ground level unless otherwise noted in Section 5.6.0 SCHEDULE OF DETAILED WORK WITHIN PARCELS and in any case two feet below the accepted finished grade by any method allowable under the City Building Code except for the following provisions.
- B. It shall be understood that the Contractor shall take whatever precautions are necessary to protect the City sidewalk. The Contractor shall also provide protection to the electric power poles and lines.
- C. The Contractor shall remove all portions of footing and foundation walls to a depth of two feet below finish grade unless otherwise noted in Section 5.6.0 SCHEDULE OF DETAILED WORK WITHIN PARCELS. All building concrete slabs, concrete stoops and concrete stairs to the buildings are also to be removed.
- D. All material and debris which would be disallowed for use as fill by sec. 4.5.6. is to be completely removed from the site and properly disposed of in accordance with all Environmental Requirements (as defined in sec. 4.5.1. above), except with the express advance, written permission of the Commissioner.
- E. All concrete or masonry floors below existing grade shall be broken up to pieces no larger than approximately one foot in all directions to permit fill to drain.

5.5.0. SCHEDULE OF DRAWINGS

5.6.0. SCHEDULE OF DETAILED WORK WITHIN PARCELS (ALL WORK TO BE DONE IN ACCORDANCE WITH THE CITY OF MILWAUKEE DEPARTMENT OF NEIGHBORHOOD SERVICES DEMOLITION AND SITE CLEARANCE GENERAL SPECIFICATIONS (1999 REVISION))

Parcel 1 — 2564 North 11th Street – 2-story frame 2-family dwelling

Remove fire-damaged dwelling, garage slab, sidewalks, concrete steps, trees, bushes and shrubs. Contractor shall be responsible for removal of all tree stumps on this parcel as part of the demolition. Prior to demolition, the contractor must meet at the site with the Condemnation Inspector to provide a demolition plan. Contractor must also notify neighbors on the block face of the demolition that demolition activity is about to begin. This notification shall be done via a department-approved letter or door knocker.

The inspection report from Harenda Management Group is included. **BID PRICE MUST INCLUDE THE PROPER REMOVAL AND DISPOSAL OF ANY ASBESTOS-CONTAINING MATERIALS OR ANY OTHER HAZARDOUS MATERIALS LISTED IN THE REPORT FROM HMG REQUIRED TO BE ABATED BEFORE MECHANICAL DEMOLITION. NOTE THAT SOME ROOMS WERE ONLY PARTIALLY ACCESSIBLE DUE TO THE FIRE DAMAGE. ON-SITE MONITORING BY A CERTIFIED ASBESTOS SPECIALIST WILL BE REQUIRED DURING DEMOLITION. THIS COST SHOULD BE INCLUDED IN THE BID PRICE. (4 days to complete)**

Parcel 2 – 2875 North 21st Street – 1.5-story frame 1-family dwelling

Remove fire-damaged dwelling, garage slab, sidewalks, concrete steps, railings, trees, bushes and shrubs. Contractor shall be responsible for removal of all tree stumps on this parcel as part of the demolition. Prior to demolition, the contractor must meet at the site with the Condemnation Inspector to provide a demolition plan. Contractor must also notify neighbors on the block face of the demolition that demolition activity is about to begin. This notification shall be done via a department-approved letter or door knocker.

The inspection report from Harenda Management Group is included. **BID PRICE MUST INCLUDE THE PROPER REMOVAL AND DISPOSAL OF ANY ASBESTOS-CONTAINING MATERIALS OR ANY OTHER HAZARDOUS MATERIALS LISTED IN THE REPORT FROM HMG REQUIRED TO BE ABATED BEFORE MECHANICAL DEMOLITION. NOTE THAT THE INSPECTOR FROM HMG WAS UNABLE TO GAIN ACCESS TO ALL SURFACES OF THE BUILDING DUE TO THE FIRE DAMAGE. ON-SITE MONITORING BY A CERTIFIED ASBESTOS SPECIALIST WILL BE REQUIRED DURING DEMOLITION. THIS COST SHOULD BE INCLUDED IN THE BID PRICE. (8 days to complete)**

Parcel 3 – 2118A North 24th Place – 1.5-story frame 1-family REAR cottage

Remove fire-damaged rear cottage only. Prior to demolition, the contractor must meet at the site with the Condemnation Inspector to provide a demolition plan. Contractor must also notify neighbors on the block face of the demolition that demolition activity is about to begin. This notification shall be done via a department-approved letter or door knocker.

The inspection report from Harenda Management Group is included. **BID PRICE MUST INCLUDE THE PROPER REMOVAL AND DISPOSAL OF ANY ASBESTOS-CONTAINING MATERIALS OR ANY OTHER HAZARDOUS MATERIALS LISTED IN THE REPORT FROM HMG REQUIRED TO BE ABATED BEFORE MECHANICAL DEMOLITION. NOTE THAT THE INSPECTOR FROM HMG WAS UNABLE TO GAIN ACCESS TO ALL AREAS OF THE BUILDING DUE TO FIRE DAMAGE OR FLOODING. ON-SITE MONITORING BY A CERTIFIED ASBESTOS SPECIALIST WILL BE REQUIRED DURING DEMOLITION. THIS COST SHOULD BE INCLUDED IN THE BID PRICE. (5 days to complete)**

Parcel 4 – 2122 North 24th Place – 2-story frame 2-family FRONT dwelling & 2-story frame 2-family REAR dwelling

Remove front and rear dwellings, fences, patio, sidewalks, bushes and shrubs. Prior to demolition, the contractor must meet at the site with the Condemnation Inspector to provide a demolition plan. Contractor must also notify neighbors on the block face of the demolition that demolition activity is about to begin. This notification shall be done via a department-approved letter or door knocker.

The inspection reports from Harenda Management Group are included. **BID PRICE MUST INCLUDE THE PROPER REMOVAL AND DISPOSAL OF ANY ASBESTOS-CONTAINING MATERIALS OR ANY OTHER HAZARDOUS MATERIALS LISTED IN THE REPORTS FROM HMG REQUIRED TO BE ABATED BEFORE MECHANICAL DEMOLITION. (13 days to complete)**

Parcel 5–2858 North 24th Place -2.5-story frame 1-family dwelling

Remove fire-damaged dwelling, fences on the north and east sides, garage slab, sidewalks, concrete steps, railings, trees, bushes and shrubs. Contractor shall be responsible for removal of all tree stumps on this parcel as part of the demolition. Splashboards or barricades required during demolition. Prior to demolition, the contractor must meet at the site with the Condemnation Inspector to provide a demolition plan. Contractor must also notify neighbors on the block face of the demolition that demolition activity is about to begin. This notification shall be done via a department-approved letter or door knocker.

The inspection report from Harenda Management Group is included. **BID PRICE MUST INCLUDE THE PROPER REMOVAL AND DISPOSAL OF ANY ASBESTOS-CONTAINING MATERIALS OR ANY OTHER HAZARDOUS MATERIALS LISTED IN THE REPORT FROM HMG REQUIRED TO BE ABATED BEFORE MECHANICAL DEMOLITION. NOTE THAT THE INSPECTOR WAS UNABLE TO GAIN ACCESS TO ALL AREAS OF THE BUILDING AT THE TIME OF INSPECTION DUE TO THE FIRE DAMAGE. ON-SITE MONITORING BY A CERTIFIED ASBESTOS SPECIALIST WILL BE REQUIRED DURING DEMOLITION. THIS COST SHOULD BE INCLUDED IN THE BID PRICE. (4 days to complete)**

Parcel 6– 219-221 North 33rd Street – 2.5-story frame 2-family dwelling & 1-story frame garage

Remove fire-damaged dwelling and garage, garage slab, fences, sidewalks, clothes poles, concrete steps, railings, trees, bushes and shrubs. Prior to demolition, the contractor must meet at the site with the Condemnation Inspector to provide a demolition plan. Contractor must also notify neighbors on the block face of the demolition that demolition activity is about to begin. This notification shall be done via a department-approved letter or door knocker.

The inspection report from Harenda Management Group is included. **BID PRICE MUST INCLUDE THE PROPER REMOVAL AND DISPOSAL OF ANY ASBESTOS-CONTAINING MATERIALS OR ANY OTHER HAZARDOUS MATERIALS LISTED IN THE REPORT FROM HMG REQUIRED TO BE ABATED BEFORE MECHANICAL DEMOLITION. (4 days to complete)**

Parcel 7 – 223-225 North 33rd Street – 2.5-story frame 2-family dwelling & 1-story frame garage

Remove fire-damaged dwelling and garage, garage slab, fences, sidewalks, concrete steps, railings and trees. Prior to demolition, the contractor must meet at the site with the Condemnation Inspector to provide a demolition plan. Contractor must also notify neighbors on the block face of the demolition that demolition activity is about to begin. This notification shall be done via a department-approved letter or door knocker.

The inspection report from Harenda Management Group is included. **BID PRICE MUST INCLUDE THE PROPER REMOVAL AND DISPOSAL OF ANY ASBESTOS-CONTAINING MATERIALS OR ANY OTHER HAZARDOUS MATERIALS LISTED IN THE REPORT FROM HMG REQUIRED TO BE ABATED BEFORE MECHANICAL DEMOLITION. NOTE THAT THE INSPECTOR WAS UNABLE TO GAIN ACCESS TO THE INTERIOR OF THE BUILDING AT THE TIME OF INSPECTION DUE TO THE SEVERE FIRE DAMAGE. ON-SITE MONITORING BY A CERTIFIED ASBESTOS SPECIALIST WILL BE REQUIRED DURING DEMOLITION. THIS COST SHOULD BE INCLUDED IN THE BID PRICE. (4 days to complete)**

Parcel 8 – 1951-51A North 33rd Street – 2-story frame 2-family dwelling

Remove fire-damaged dwelling, fences, garage slab, concrete steps, bushes and shrubs. Prior to demolition, the contractor must meet at the site with the Condemnation Inspector to provide a demolition plan. Contractor must also notify neighbors on the block face of the demolition that demolition activity is about to begin. This notification shall be done via a department-approved letter or door knocker.

The inspection report from Harenda Management Group is included. **BID PRICE MUST INCLUDE THE PROPER REMOVAL AND DISPOSAL OF ANY ASBESTOS-CONTAINING MATERIALS OR ANY OTHER HAZARDOUS MATERIALS LISTED IN THE REPORT FROM HMG REQUIRED TO BE ABATED BEFORE MECHANICAL DEMOLITION. NOTE THAT THE INSPECTOR WAS UNABLE TO GAIN ACCESS TO ALL SURFACE AREAS OF THE BUILDING AT THE TIME OF INSPECTION DUE TO THE FIRE DAMAGE. ON-SITE MONITORING BY A CERTIFIED ASBESTOS SPECIALIST WILL BE REQUIRED DURING DEMOLITION. THIS COST SHOULD BE INCLUDED IN THE BID PRICE (8 days to complete)**

Parcel 9 – 2931 West Vliet Street – 2-story frame 2-family dwelling & 1-story frame garage

Remove fire-damaged dwelling and garage, garage slab, fences, retaining wall, sidewalks, clothes poles, concrete steps, trees, bushes and shrubs. Prior to demolition, the contractor must meet at the site with the Condemnation Inspector to provide a demolition plan. Contractor must also notify neighbors on the block face of the demolition that demolition activity is about to begin. This notification shall be done via a department-approved letter or door knocker.

The inspection report from Harenda Management Group is included. **BID PRICE MUST INCLUDE THE PROPER REMOVAL AND DISPOSAL OF ANY ASBESTOS-CONTAINING MATERIALS OR ANY OTHER HAZARDOUS MATERIALS LISTED IN THE REPORT FROM HMG REQUIRED TO BE ABATED BEFORE MECHANICAL DEMOLITION. NOTE THAT THE INSPECTOR WAS UNABLE TO GAIN ACCESS TO ALL AREAS OF THE BUILDING AT THE TIME OF INSPECTION DUE TO THE FIRE DAMAGE. ON-SITE MONITORING BY A CERTIFIED ASBESTOS SPECIALIST WILL BE REQUIRED DURING DEMOLITION. THIS COST SHOULD BE INCLUDED IN THE BID PRICE. (8 days to complete)**

Refer to Section 5.7.0 for ownership information on the parcels.

The City of Milwaukee has contacted We Energies to cut gas and electrical services. Contractor is responsible for verifying that ALL utilities have been disconnected prior to starting work.

REQUIRED EROSION CONTROL MEASURES FOR PARCELS: CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING AN EROSION CONTROL PERMIT AND INSTALLING CONTROL MEASURES PER THE REQUIREMENTS OF CHAPTER 290 OF THE MILWAUKEE CODE OF ORDINANCES. MEASURES MUST BE IN PLACE PRIOR TO DEMOLITION ACTIVITIES COMMENCING. CONTROL MEASURES MUST BE INTACT AT FINAL INSPECTION AND ARE TO REMAIN ON SITE.

FAILURE TO REQUEST OPEN BASEMENT INSPECTION WILL RESULT IN THE INSPECTOR REQUIRING COMPLETE RE-EXCAVATION OF THE PARCEL.

CONTRACTOR IS REQUIRED TO CONTACT THIS DEPARTMENT TO ARRANGE FOR AN INSPECTION IF ADDITIONAL ASBESTOS-CONTAINING MATERIALS ARE FOUND IN THE BUILDING AFTER ASBESTOS ABATEMENT OR DEMOLITION HAS COMMENCED.

IF MORE THAN 5 WASTE TIRES ARE REMOVED FROM ANY SITE, THEY MUST BE TRANSPORTED BY A LICENSED WASTE TIRE TRANSPORTER. LICENSED TRANSPORTER MUST BE LISTED IN THE LIST OF SUBCONTRACTORS SUBMITTED WITH THE BID DOCUMENTS IF OTHER THAN PRIME CONTRACTOR. FOR INFORMATION ON LICENSED

TRANSPORTERS, CONTACT CITY OF MILWAUKEE WASTE TIRE COORDINATOR AT 414-286-5028.

MANAGEMENT OF ANY MERCURY-CONTAINING PRODUCTS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF ALL APPLICABLE LOCAL, STATE AND FEDERAL REGULATIONS.

MANAGEMENT OF ANY PCB'S OR PCB-CONTAINING PRODUCTS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF ALL APPLICABLE LOCAL, STATE AND FEDERAL REGULATIONS, INCLUDING CHAPTER NR157 OF THE WISCONSIN ADMINISTRATIVE CODE.

ANY REFRIGERANTS ON SITES MUST BE RECLAIMED BY A CERTIFIED CFC RECLAIMER. CERTIFIED RECLAIMER MUST BE LISTED IN THE LIST OF SUBCONTRACTORS SUBMITTED WITH THE BID DOCUMENTS IF OTHER THAN PRIME CONTRACTOR.

IF THE DEPARTMENT OF NEIGHBORHOOD SERVICES (DNS) HAS BEEN HOLDING A CONTRACT PAYMENT FOR A YEAR AND STILL HAS NOT RECEIVED REQUIRED DOCUMENTATION FROM THE CONTRACTOR TO CLOSE OUT THE CONTRACT, DNS MAY NOTIFY THE CONTRACTOR THAT UNLESS THE DOCUMENTATION IS FORTHCOMING WITHIN THIRTY (30) DAYS, THE PAYMENT WILL BE FORFEITED.

**5.7.0. LOCATIONS AND DESCRIPTION OF BUILDINGS TO BE DEMOLISHED.
(SEE ATTACHED)**

DEPARTMENT OF NEIGHBORHOOD SERVICES DEMOLITION PROJECTS

FORMAL BIDS

The complete Bid Documents shall include Bids for Demolition form, one Noncollusion Affidavit of Prime Bidder, one Bid Bond form, one Bid Bond Form Affidavit, one Certificate as to Corporate Principal, a complete List of Subcontractors, a completed Form B (Compliance Plan for SBE participation) and the Price Breakdown Sheet.

The demolition contractor must include the plumbing contractor, asbestos abatement contractor, certified CFC reclaimer, licensed waste tire transporter and concrete contractor in the List of Subcontractors.

If any bidder has any questions as to the Bid Documents or Specifications, please contact this office by calling 414-286-2515.

BID FOR DEMOLITION

Department of Neighborhood Services
841 North Broadway
Milwaukee, Wisconsin

Gentlemen:

1. The undersigned, having familiarized _____ with the existing conditions on the Project Area affecting the cost of the work, and with the Contract Documents revised January, 1999, (which includes Invitation for Bids, Instruction to Bidders, the form of Bid, the form of the Bid Bond, Form of Contract (or agreement), form of Non-Collusion Affidavit, Addenda (if any), General Conditions, Technical Specifications, Drawings (as listed in the schedule of drawings), and Form of Surety Bond or Bonds); hereby proposes to furnish all supervision, technical personnel, labor, materials, machinery, tools, equipment and services including utility and transportation services and to perform and complete all work required for the demolition of ten (10) primary buildings and three (3) secondary buildings located in the City of Milwaukee, for mechanical Demolition Project opening May 19, 2020, all in accordance with the above-listed documents;

(a) for the lump sum of _____ Dollars
(\$ _____), in addition to and above the value of such salvage materials specified to become the property of the Bidder;

(b) in consideration of any salvaged materials which under the Contract Documents are to become the property of the Bidder and other benefits, will pay the Department of Neighborhood Services of the City of Milwaukee, the sum of

_____ Dollars
(\$ _____),

(Bidder will strike out the subparagraph (a) or (b) not used.)

2. In submitting this Bid, the Bidder understands that the right is reserved by the Commissioner of the Department of Neighborhood Services of the City of Milwaukee to reject any and all Bids as provided in sec. 2.8.2. of the Instructions To Bidders. If written notice of the acceptance of this Bid is mailed, faxed or delivered to the undersigned within sixty (60) calendar days after the opening thereof, or at any time thereafter before this Bid is withdrawn, the undersigned agrees to execute and deliver an Agreement in the prescribed form and furnish the required bond within fourteen (14) calendar days after the agreement is presented to him or her for signature.

3. A Bid Guaranty equal in amount to at least 10% of the total bid is enclosed, which certified check, bank draft or bid bond is submitted as a guaranty of the good faith of the Bidder and as a further guaranty that the Bidder will enter into the written Contract as provided, if successful in securing the award thereof. It is hereby agreed that if at any time other than as provided in the Instructions to Bidder, the Bidder should withdraw this Bid, or if this Bid is accepted and there should be a failure on the part of the Bidder to execute the Contract and furnish the required surety bond or bonds, the Department of Neighborhood Services, in either of such events, shall be entitled and is hereby given the right to retain said Bid Guaranty.

4. Attached hereto is an affidavit in proof that the undersigned has not colluded with any person in respect to this Bid or any other Bid for the Contract for which this Bid is submitted.

5. The Bidder is prepared to submit a financial and experience statement upon request.

Date _____, 20____.

Company Name

OFFICIAL ADDRESS

By _____

TITLE _____

3.2.0. NON-COLLUSION AFFIDAVIT OF PRIME BIDDER

STATE OF _____)
)SS
COUNTY OF _____)

_____, being first duly sworn, deposes and says that:

- (1) S/he is _____, (owner, partner, officer, representative or agent) of _____, the Bidder that has submitted the attached Bid.
- (2) S/he is fully informed respecting the preparation and contents of the attached Bid and of all pertinent circumstances respecting such Bid.
- (3) Such bid is genuine and is not a collusive or sham bid.
- (4) Neither the said Bidder nor any of its officers, partners, owners, agents, representatives, employees or parties in interest, including this affiant, has in any way colluded, conspired, connived or agreed, directly or indirectly, with any other Bidder, firm or person to submit a collusive or sham Bid in connection with the Contract for which the attached Bid has been submitted or to refrain from bidding in connection with such Contract, or has had or will have communication or conference with any other Bidder, firm or person to fix the price or prices in the attached Bid or of any other Bidder or to fix the overhead, profit or cost element of the bid price or the bid price of any other Bidder, or to secure through any collusion, conspiracy, connivance or unlawful agreement any advantage against the Department of Neighborhood Services of the City of Milwaukee or any person interested in the proposed Contract.
- (5) The price or prices quoted in the attached Bid are fair and proper and are not tainted by any collusion, conspiracy, connivance or unlawful agreement on the part of the Bidder or any of its agents, representatives, owners, employees, or parties in interest, including this affiant.
- (6) Attached and following this affidavit is a full and complete list of all subcontractors and the class of work to be performed by each, which the Bidder proposes to use.

Subscribed and sworn to before me
this ___ day of _____, 20____

Notary Public, Milwaukee County, WI

Title

My commission expires: _____

3.8.0.

BID BOND AFFIDAVIT

STATE OF WISCONSIN)
MILWAUKEE COUNTY)

_____ ,

being first duly sworn, on oath deposes and says that s/he is

(Attorney-in-fact or agent)

of _____

surety on the within bond executed by

Affiant further deposes and says that no Commissioner or employee of the Department of Neighborhood Services of the City of Milwaukee, and no City official or employee of the City of Milwaukee has any interest, directly or indirectly in, or is receiving any premium, commission, fee or other thing of value on account of the sale or furnishing of said bid bond.

Subscribed and sworn to before me this

_____ day of _____, 20_____

Notary Public, Milwaukee County, Wisconsin

My commission expires _____

Rev. 1/00

3.7.0. CERTIFICATE AS TO CORPORATE PRINCIPAL

I, _____, certify that I am the
_____ Secretary of the corporation
named as Principal in the within bond; that
_____, who signed the said bond on
behalf of the Principal was then _____
of said corporation; that I know his signature, and his signature thereto is genuine, and that said
bond was duly signed, sealed, and attested to for and in behalf of said corporation by authority of its
governing body.

_____(Corporate)

Title _____(Seal)

3.3.0.

COMPLETE LIST OF SUBCONTRACTORS

(Include Plumbing Contractor, Hauling Contractor, Asbestos Abatement Contractor, Certified CFC Reclaimer, Licensed Waste Tire Transporter and Licensed Concrete Contractor)

| Name of Proposed Subcontractor | Class of Work |
|---------------------------------------|----------------------|
| 1. _____ _____ Address | _____ |
| 2. _____ _____ Address | _____ |
| 3. _____ _____ Address | _____ |
| 4. _____ _____ Address | _____ |
| 5. _____ _____ Address | _____ |
| 6. _____ _____ Address | _____ |
| 7. _____ _____ Address | _____ |
| 8. _____ _____ Address | _____ |

MECHANICAL DEMOLITION PROJECT OPENING 5-19-20
LOCATION AND DESCRIPTION OF BUILDINGS TO BE DEMOLISHED

| Parcel Number | Address | Stories | Construc. | Occupancy | Residential Units | Owner | Cubic Footage |
|---------------|--|---------|-----------|----------------|-------------------|-------|---------------|
| 1 | 2564 North 11 th Street | 2 | frame | dwelling | 2 | CITY | 34,000 |
| 2 | 2875 North 21 st Street | 1.5 | frame | dwelling | 1 | CITY | 17,600 |
| 3 | 2118A North 24 th Place | 1.5 | frame | REAR cottage | 1 | PRIV | 14,500 |
| 4 | 2122 North 24 th Place | 2 | frame | FRONT dwelling | 2 | PRIV | 21,600 |
| | 2122 North 24 th Place | 2 | frame | REAR dwelling | 2 | PRIV | 26,000 |
| 5 | 2858 North 24 th Place | 2.5 | frame | dwelling | 1 | CITY | 22,800 |
| 6 | 219-221 North 33 rd Street | 2.5 | frame | dwelling | 2 | PRIV | 28,800 |
| | 219-221 North 33 rd Street | 1 | frame | garage | - | PRIV | 4,000 |
| 7 | 223-225 North 33 rd Street | 2.5 | frame | dwelling | 2 | PRIV | 28,800 |
| | 223-225 North 33 rd Street | 1 | frame | garage | - | PRIV | 6,000 |
| 8 | 1951-51A North 33 rd Street | 2 | frame | dwelling | 2 | PRIV | 30,000 |
| 9 | 2931 West Vliet Street | 2 | frame | dwelling | 2 | PRIV | 28,500 |
| | 2931 West Vliet Street | 1 | frame | garage | - | PRIV | 5,280 |

Demolition contractor has the responsibility of verifying the listed information before bid is submitted. Bid is to be based upon contractor's own inspection of the structures and sites. No guarantee is made as to the accuracy of the above listed information, and the bid/contract shall not be invalidated by any errors in the descriptions and sizes listed.

CONTRACTOR MUST SUBMIT FORM WITH ALL ORIGINAL SIGNATURES.

BID BOND FORM

KNOW ALL PERSONS BY THESE PRESENTS, That we the undersigned,

(Name of Principal)

as PRINCIPAL, and

_____, as SURETY

(Name of Surety)

are held and firmly bound unto the Department of Neighborhood Services of the City of Milwaukee hereinafter called the "Building Inspector", in the sum of 10 percent of the total bid of:

Parcel 1 _____ Dollars \$ _____

Parcel 2 _____ Dollars \$ _____

Parcel 3 _____ Dollars \$ _____

Parcel 4 _____ Dollars \$ _____

Parcel 5 _____ Dollars \$ _____

Parcel 6 _____ Dollars \$ _____

Parcel 7 _____ Dollars \$ _____

Parcel 8 _____ Dollars \$ _____

Parcel 9 _____ Dollars \$ _____

(bid price in words)

(bid price in numerals)

lawful money of the United States, in addition to and above the value of such salvage materials specified to become the property of the Bidder, for the payment of which sum well and truly to be made, we bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

THE CONDITION OF THIS OBLIGATION IS SUCH, that whereas the Principal has submitted the accompanying Bid,

dated _____, 20 ____, for DNS PROJECT OPENING 5-19-20
DEMOLITION OF 10 PRIMARY BUILDINGS AND 3 SECONDARY BUILDINGS

NOW THEREFORE, if the Principal shall be awarded the contract and if his/her Bid shall not have been previously withdrawn in accordance with the provisions of the instructions to Bidders, and if the Principal shall enter into a formal contract with the Building Inspector in accordance with the accepted Bids, said Bid shall be accompanied by good and sufficient surety or sureties for the faithful performance of the work, then this obligation is void and of no effect.

However, in the event that the Principal shall be awarded the contract, his/her Bid not being previously withdrawn in accordance with the instructions to Bidders, and if the Principal shall neglect or fail to execute such contract or to give sufficient surety or sureties within the time specified, or if no time be specified, within 14 days, then the Principal and/or surety shall forfeit to the Building Inspector as liquidated damages the amount of this bond.

Revised 1/01

IN WITNESS WHEREOF, the above-bounded parties have executed this instrument under their several seals this

_____ day of _____, 20____, the names and corporate party being hereto affixed and these presents duly signed by its undersigned representative, pursuant to authority of its governing body.

In presence of:

_____(SEAL)
(Individual Principal)

(Business Address)

_____(SEAL)
(Individual Principal)

(Business Address)

Attest:

_____(SEAL)
(Corporate Principal)

(Business Address)

By _____ affix
corporate
seal

Attest:

(Corporate Surety)

Countersigned

by _____
Attorney-in-Fact

By _____ affix
corporate
Seal

State of _____

Power of attorney for person signing for surety company must be attached to bond

FORM B (3/13)

CITY OF MILWAUKEE DEPARTMENT OF NEIGHBORHOOD SERVICES
 AFFIDAVIT OF COMPLIANCE WITH THE
 SMALL BUSINESS ENTERPRISE (SBE) PROVISIONS

BIDS DUE: 5-19-20

The bidders minimum commitment for SBE participation on this project is as follows:

| REQUIRED OVERALL PROJECT PARTICIPATION | | | |
|---|--|------------|--|
| | | | |
| SBE | | 25% | |

The Commissioner of the Department of Neighborhood Services reserves the right to reject and disqualify any bid that does not achieve the percentage requirement for this project. This also applies if the undersigned contractor fails to comply with the City's requirements as outlined in the SBE provisions.

The undersigned hereby states that s/he has not discriminated in any manner on the basis of race, sex, or national origin in any manner in the preparation of the attached bid or selection of subcontractors and/or material suppliers for such bid.

The undersigned acknowledges, understands and agrees that submission of a bid shall commit the bidder to comply with the City's SBE policy to achieve the City's stated percentage requirements for SBE participation on this contract, including submission of the information required by the proposed schedule of subcontractors and/or material suppliers.

CONTRACTOR AFFIRMS THAT THEY WILL MEET THE FOLLOWING MINIMUM SBE PROGRAM REQUIREMENTS: (BIDDER MUST WRITE IN PERCENTAGE AND SUBMIT WITH BID DOCUMENTS.)

SBE: _____ %

The undersigned also states that all the submitted SBE information is true and correct to the best of his/her knowledge.

 Authorized Signature

 Date

 Printed Name

 Title

 Company Name

STATE OF WISCONSIN)
 COUNTY OF MILWAUKEE)

Personally came before me this ____ day of _____, ____.

_____ who acknowledges that s/he executed the foregoing document for the purpose therein contained for and on behalf of said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal.

 Notary Public, Milwaukee County, WI

My Commission expires: _____

PRICE BREAKDOWN

| NO. | PARCEL ADDRESS | ASBESTOS ABATEMENT | DEMOLITION DWELLING | DEMOLITION GARAGE | TOTAL |
|-----|--|-----------------------|------------------------|----------------------|------------------------------------|
| 1 | 2564 North 11 th Street (dwelling) | | | | |
| 2 | 2875 North 21 st Street (dwelling) | | | | |
| 3 | 2118A North 24 th Place (REAR cottage) | | | | |
| 4 | 2122 North 24 th Place (FRONT dwelling) (REAR dwelling) | FRONT: REAR: | FRONT: REAR: | | Enter total for both dwellings: |
| 5 | 2858 North 24 th Place (dwelling) | | | | |
| 6 | 219-221 North 33 rd Street (dwelling & garage) | | | | |
| 7 | 223-225 North 33 rd Street (dwelling & garage) | | | | |
| 8 | 1951-51A North 33 rd Street (dwelling) | | | | |
| 9 | 2931 West Vliet Street (dwelling & garage) | | | | |

NOTE: If bidder fails to list price breakdown for garage, it will be assumed that the cost to the City of Milwaukee for demolishing the garage is \$0.



DEPARTMENT OF ADMINISTRATION
PURCHASING DIVISION

Revised December 28, 2016

LOCAL BUSINESS ENTERPRISE (LBE) PROGRAM
AFFIDAVIT OF COMPLIANCE

IMPORTANT: This form must be submitted with your bid to be considered for LBE status.

Bid/RFP #: _____

Company Name: _____

Address: _____

City, State, Zip _____

This signed and notarized affidavit of compliance will be the contractor's sworn statement that the business satisfies all of the following criteria:

- 1. Operates a business, or owns or leases property within the geographical boundaries of the City of Milwaukee.
2. A residential address may suffice to establish compliance as a Local Business Enterprise, but only if the business does not operate another business...
3. Leased property shall not suffice to establish compliance as a Local Business Enterprise unless at least half of the acreage of all the real property owned or leased by the business is located within the geographical boundaries of the City of Milwaukee.
4. Has been doing business in the City of Milwaukee for at least one (1) year.
5. The business is not delinquent in the payment of any local taxes, charges or fees, or the business has entered into an agreement to pay any delinquency and is abiding by the terms of the agreement.
6. The business will perform at least 10% of the monetary value of the work required under the contract.

IMPORTANT: Is your business certified as a Small Business Enterprise (SBE) with the City of Milwaukee?
Please Select: ___ Yes or ___ No

NOTE: If you are the primary owner of more than one business location and the other business location(s) is not located within the geographical boundaries of the City of Milwaukee, the business you are seeking to qualify as a Local Business Enterprise must serve as the primary functionally operational entity that is capable of providing the required services, commodities, or supplies for the purposes of this Bid/RFP.

SITE VISITS: Please note the contractor agrees to allow the City to verify Local Business Enterprise status by allowing City Staff to visit the operation(s) of the business that is seeking Local Business Enterprise status at any time without notice, in an effort to maintain the integrity of the City's bidding process.

I hereby declare compliance with the City of Milwaukee Code of Ordinances Chapter 365.

Authorized Signature: _____

Printed Name: _____

Date: _____

NOTARIZATION

Subscribed to before me on this _____ day of _____ in the year _____, at
_____ County, _____ State.

NOTARY PUBLIC SIGNATURE: _____

(SEAL)

PRINT NAME: _____ My commission expires: _____

PLEASE SUBMIT THIS FORM WITH YOUR BID OR PROPOSAL TO:
841 NORTH BROADWAY, ROOM 105
MILWAUKEE, WISCONSIN 53202



DEPARTMENT OF NEIGHBORHOOD SERVICES

LOCAL BUSINESS ENTERPRISE (LBE) PROGRAM
BUSINESS PROPERTY LOCATION FORM

Important Note: This form must be submitted with your bid to be considered for LBE status.

Bid / RFP # _____

Property Location 1 Check one: Own [] Lease []

Form with fields for Name, Address, and City, State, Zip for Property Location 1.

Property Location 2 Check one: Own [] Lease []

Form with fields for Name, Address, and City, State, Zip for Property Location 2.

Property Location 3 Check one: Own [] Lease []

Form with fields for Name, Address, and City, State, Zip for Property Location 3.

Property Location 4 Check one: Own [] Lease []

Form with fields for Name, Address, and City, State, Zip for Property Location 4.

PLEASE SUBMIT THIS FORM WITH YOUR BID TO:
DEPT. OF NEIGHBORHOOD SERVICES
841 NORTH BROADWAY, ROOM 105
MILWAUKEE, WISCONSIN 53202

Socially-Responsible Contractors (SRC) Application

- A. If the bids of two or more socially-responsible contractors do not exceed the lowest bid by more than 5%, the contract shall be awarded to the socially-responsible contractor that submitted a bid that exceeded the lowest bid by the smallest amount.
- B. If a bid submitted by a non-socially-responsible contractor and a bid submitted by a socially-responsible contractor are identical, the contract shall be awarded to the socially-responsible contractor, even if the bids are only identical due to the 5% award standard provided for in this chapter.
- C. If two bids submitted by two socially-responsible contractors are identical, the winner will be determined in accordance with the process for tie-breakers as established by the City Purchasing Director.
- D. If the difference between the low bidder's amount and the lowest socially-responsible contractor amount is within 5% of the low bidder and exceeds \$25,000, then the provisions in SRC Application - point A shall not apply.
- E. SRC Application – point A shall only be applied to the “base bid”.
- F. If a bidder or proposer is seeking to qualify for the SRC bid incentive, that bidder or proposer may not also seek to qualify for the City's other bid incentive programs such as the Local Business Enterprise (LBE) bid incentive (city.milwaukee.gov/Purchasing/Programs) or the Buy American bid incentive (city.milwaukee.gov/Purchasing/Programs). Should there be a conflict between multiple bidders that are seeking to qualify for these incentives, precedence shall be given to the bidder seeking to qualify for a bid incentive in the following descending order:
1. LBE bid incentive
 2. Buy American bid incentive
 3. SRC bid incentive



DEPARTMENT OF ADMINISTRATION-PURCHASING DIVISION

**SOCIALLY-RESPONSIBLE CONTRACTORS (SRC)
AFFIDAVIT OF COMPLIANCE**

NOTE: This affidavit must be completed in its entirety and submitted with your bid or proposal to be considered for SRC bid incentive.

Bid or RFP #: _____

Company Name: _____

Address, City, State, Zip: _____

A "Socially-Responsible Contractor" or "SRC" is an entity submitting a bid as part of the City's formal competitive bidding process that has acted or implemented a program to eliminate, or significantly reduce, barriers to employment for current and prospective employees of the contractor. Actions or implemented programs shall include at least three (3) of the programs listed in **Section I** below. To indicate which programs you have acted or implemented, place a checkmark in the box next to each item pertaining to the business entity as a bidder or proposer for the City of Milwaukee.

I. SRC CRITERIA

- A. Hire persons with felony convictions;
- B. Assist current or prospective employees with earning their high school diploma;
- C. Underwrite or facilitate industry-linked career-assessed pre-employment services and subsidized work experience including: internships, job shadowing, on-the-job training, and summer employment;
- D. Partner with an employment service agency to monitor and track individualized employment plans;
- E. Provide, underwrite, or facilitate industry-linked career-based instruction to current or prospective employees in areas such as the following: blueprint reading, basic math and measurement, technical math, labor history, construction culture and essential skills, health and safety awareness, manufacturing processes and production, maintenance, and budgeting and financial literacy;
- F. Provide or facilitate occupational skills training and related adult mentoring and networking;
- G. Underwrite or facilitate subsidized or unsubsidized programs which provide supportive services for current or prospective employees to obtain or fund the following:
 - A valid driver's license
 - Transportation vouchers to work and home
 - Appropriate work attire, work safety gear, and other needed equipment
 - Testing and certification fees
 - Legal aid services
 - Child care and family-related dependent care
 - Emergency housing, health care, and short-term emergency assistance
 - Career and training services
 - School supplies, books, and fees
 - Referrals for medical services and exams
 - Reasonable accommodations for persons with disabilities
- H. Partner with employment agencies to supplement subsidized wages to ensure employees receive a living wage;
- I. Provide breast feeding facilities for employees who are nursing children;
- J. Provide a minimum of 120 hours of paid sick leave;
- K. Provide a minimum of five (5) paid sick days;
- L. Provide an employer-assisted housing program providing homebuyer assistance in the form of mortgages, down payment assistance, or homebuyer education for residences within walking distance of their employer;
- M. Provide assistance to reduce fees and penalties on tardy child support payments, manage payment of child support arrears, and become current on child support obligations.

II. DISCLOSURE

The purpose of the *Socially-Responsible Contractor Program (SRC)* is to ensure contributions toward community betterment made by socially-responsible contractors are recognized and rewarded. Each bidder or proposer seeking to qualify for the SRC bid incentive shall submit, as part of its bid or proposal, this sworn affidavit describing actions taken and programs implemented to eliminate, or significantly reduce, the barriers to employment for current and prospective employees of the contractor. The outcomes of these actions and programs shall be described in verifiable detail in the section below. (Please include an attachment if additional line space is required).

This signed and notarized affidavit of compliance will be the contractor's sworn statement that the business satisfies the criteria for Socially-Responsible Contractors pursuant to Chapter 310-10 of the City of Milwaukee Code of Ordinances.

I hereby declare compliance with Chapter 310-10 of the City of Milwaukee Code of Ordinances.

Authorized Signature: _____

Printed Name: _____

Date: _____

III. NOTARIZATION

Subscribed to before me on this _____ day of _____ in the year _____, at
_____ County, _____ State.

NOTARY PUBLIC SIGNATURE: _____

(SEAL)

PRINT NAME: _____

My commission expires: _____

PLEASE SUBMIT THIS FORM WITH YOUR BID OR PROPOSAL TO:
200 E. WELLS STREET, ROOM 601
MILWAUKEE, WISCONSIN 53202
OR FAX TO 414-286-5976



PRE-DEMOLITION INSPECTION REPORT

Job Site:

**Fire Damaged
Two Family Dwelling
2564 North 11th Street
Milwaukee, Wisconsin**

For:

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613


**HMG Report No.: 20-400-020.2564
Inspector: Jazmin Spears
Contract No.: 360-20-0975**

Prepared by:

HARENDA MANAGEMENT GROUP
1237 West Bruce Street
Milwaukee, Wisconsin 53204
(414) 383-4800

March 2020

Signature Page
Pre-Demolition Inspection Report
Two Family Dwelling
2564 North 11th Street
Milwaukee, Wisconsin



Dean Jacobsen
Asbestos Inspector No. AII – 14370
Expiration Date: 12/2/20
Harenda Management Group



Jazmin Spears
Asbestos Inspector No. AII – 111055
Expiration Date: 8/10/20
Harenda Management Group

March 17, 2020

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613

RE: Pre-Demolition Inspection Report
2564 North 11th Street
Milwaukee, WI

Harenda Management Group has completed the pre-demolition inspection of the two family dwelling at 2564 North 11th Street, Milwaukee, Wisconsin, as per the referral from the City of Milwaukee Department of Neighborhood Services. The inspection and results are described in the following report. Please contact me at (414) 383-4800 if you have any questions.

Sincerely,

HARENDA MANAGEMENT GROUP



Dean Jacobsen
Asbestos Inspector No. AII – 14370

EXECUTIVE SUMMARY

Harenda Management Group was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection of the two family dwelling at 2564 North 11th Street, Milwaukee, Wisconsin, prior to demolition. HMG conducted a visual inspection for asbestos and universal wastes. HMG collected asbestos bulk samples for laboratory analysis.

Asbestos was detected above 1% in basement aircell pipe insulation sampled during the inspection. Asbestos was assumed to be in the asphalt roofing and in the floor tile and mastic in the dwelling. Results are in Section IV of this report.

TABLE OF CONTENTS
Pre-Demolition Inspection Report

| | | |
|-------|---|----|
| I. | Introduction..... | 1 |
| II. | Asbestos Inspection | 1 |
| III. | Asbestos Laboratory | 2 |
| | A. Method of Analysis | |
| IV. | Asbestos Findings and Observations | 2 |
| V. | Exclusions | 5 |
| VI. | Limitations | 5 |
| VII. | Pre-Demolition Environmental Checklist..... | 7 |
| VIII. | Asbestos Laboratory Results..... | 11 |
| IX. | Floor Plans | 12 |
| X. | HMG Certifications | 13 |

I. INTRODUCTION

Harenda Management Group (HMG) was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection for suspect asbestos containing materials in the two family dwelling at 2564 North 11th Street, Milwaukee, Wisconsin. The dwelling is a two story wood framed structure with basement and has vinyl and wood walls and asphalt roofing.

II. ASBESTOS INSPECTION

Marge Piwaron, of the City of Milwaukee Department of Neighborhood Services, authorized HMG to conduct a building inspection and to analyze samples collected during the inspection.

On March 9, 2020, HMG conducted an asbestos inspection of a two family dwelling, scheduled for mechanical demolition, located at 2564 North 11th Street, Milwaukee, Wisconsin. The inspection was conducted by Jazmin Spears, Wisconsin License No. AII – 111055, and the report was written by Dean Jacobsen, Wisconsin License No. AII – 14370..

The inspection was comprised of these elements:

1. A visual determination as to the extent of suspect asbestos containing materials within the buildings.
2. Sampling and documentation of observable suspect asbestos containing materials.
3. Quantification of observable asbestos containing materials existing within the spaces.

The results of the inspection integrated with the Polarized Light Microscopy with Dispersion Staining (PLM/DS) analysis of asbestos bulk samples collected are outlined in this document.

The following types of suspect materials were observed and inspected to determine if asbestos containing materials were present in the building as required by U.S. EPA NESHAP regulation 40 CFR 61 Subpart M, and NR 447 of the Wisconsin Administrative Code:

- Paper insulation
- Linoleum
- Drywall
- Texture
- Ceramic tile
- Blown in insulation
- Flue packing
- Aircell pipe insulation
- Plaster
- Caulk
- Ceiling tile
- Floor tile
- Asphalt roofing
- Mastics

A listing of specific homogeneous materials and homogeneous material codes are in the Findings and Observations section following the results table.

III. ASBESTOS LABORATORY

A. METHOD OF ANALYSIS

Analysis is performed by using the bulk samples for visual observation and slide preparation(s) for microscopical examination and identification. The slides are analyzed for asbestos (chrysotile, amosite, crocidolite, anthophyllite, and actinolite/tremolite), fibrous non asbestos constituents (mineral wool, paper, etc.), and nonfibrous constituents. Asbestos is identified by refractive indices (obtained by using dispersion staining), morphology, color, pleochroism, birefringence, extinction characteristics, and signs of elongation. The same characteristics are used to identify the non asbestos constituents.

The microscopist visually estimates relative amounts of each constituent using a stereoscope if necessary. The test results are based on a visual determination of relative volume of the bulk sample components. The results are valid only for the item tested. Current federal and Wisconsin regulations state asbestos containing material means material containing more than 1% asbestos as determined using the method specified in Appendix E, Subpart E, 40 CFR Part 763 Section I, Polarized Light Microscopy. Bold values below indicate that the material contains more than 1% asbestos. Refer to 29 CFR 1926.1101 (Construction) and 29 CFR 1910.1001 (General Industry) for specific OSHA requirements.

IV. ASBESTOS FINDINGS AND OBSERVATIONS

The following are the laboratory results. The laboratory report is in Appendix A.

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|---|----------|------------------|
| 1 | Exterior – west wall – under wood siding – tan paper insulation | Negative | MPIt |
| 2 | Exterior – south wall – under wood siding – tan paper insulation | Negative | MPIt |
| 3 | Exterior – east wall – under wood siding – tan paper insulation | Negative | MPIt |
| 4a | 1 st floor – front entry – white and gray linoleum | Negative | MFLwy |
| 4b | 1 st floor – front entry – under white and gray linoleum – tan mastic | Negative | MFLwy |
| 5a | 1 st floor – rear stair – on steps – gray linoleum | Negative | MFLy |
| 5b | 1 st floor – rear stair – on steps – under gray linoleum – gray mastic | Negative | MFLy |
| 6a | 2 nd floor – kitchen – south side top layer – gray and tan linoleum | Negative | MFLyt |
| 6b | 2 nd floor – kitchen – south side top layer – under gray and tan linoleum – tan mastic | Negative | MFLyt |
| 7 | 1 st floor – north bedroom – north wall – drywall | Negative | MDW |
| 8 | 1 st floor – sitting room – south wall – drywall | Negative | MDW |
| 9 | 2 nd floor – kitchen – ceiling – drywall | Negative | MDW |

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|--|------------------------------------|------------------|
| 10 | 1 st floor – sitting room – east side ceiling – texture | Negative | STX |
| 11 | 1 st floor – sitting room – west side ceiling – texture | Negative | STX |
| 12 | 2 nd floor – rear stair – ceiling – texture | Negative | STX |
| 13a | 2 nd floor – kitchen – south side on counter – gray ceramic tile | Negative | MCTMy |
| 13b | 2 nd floor – kitchen – south side on counter – under gray ceramic tile – tan mastic | Negative | MCTMy |
| 14a | 2 nd floor – kitchen – on south wall – yellow ceramic tile | Negative | MCTMI |
| 14b | 2 nd floor – kitchen – on south wall – under yellow ceramic tile – tan mastic | Negative | MCTMI |
| 15a | 2 nd floor – east bathroom floor – tan ceramic tile | Negative | MCTMt |
| 15b | 2 nd floor – east bathroom floor – under tan ceramic tile – tan mastic | Negative | MCTMt |
| 15c | 2 nd floor – east bathroom floor – grout | Negative | MCTMt |
| 16 | 1 st floor – bathroom – on north wall – white mastic | Negative | MWMw |
| 17 | 2 nd floor – west bathroom floor – tan ceramic tile | Negative | MCTMt |
| 18 | 2 nd floor – west bathroom – on north wall – tan ceramic tile | Negative | MCTMt |
| 19 | 2 nd floor – north bedroom – on floor – blown in insulation | Negative | MBI |
| 20 | 2 nd floor – living room – on floor – blown in insulation | Negative | MBI |
| 21 | 2 nd floor – sitting room – on floor – blown in insulation | Negative | MBI |
| 22 | Basement – on chimney – flue packing | Negative | TFP |
| 23 | Basement – east side - <5” diameter aircell pipe insulation | Positive 60% Chrysotile | TA5 |
| 24 | Basement – northeast - <5” diameter aircell pipe insulation | Positive 60% Chrysotile | TA5 |
| 25 | Basement – north side - <5” diameter aircell pipe insulation | Positive 60% Chrysotile | TA5 |
| 26 | 1 st floor – front entry – north wall – plaster | Negative | SPI |
| 27 | 1 st floor – living room – south wall – plaster | Negative | SPI |
| 28 | 1 st floor – bathroom – east wall – plaster | Negative | SPI |
| 29 | Basement – stair – east wall – plaster | Negative | SPI |
| 30a | 2 nd floor – kitchen – south wall – plaster | Negative | SPI |
| 30b | 2 nd floor – kitchen – south wall – joint compound layer | Negative | SPI |
| 31 | 2 nd floor – sitting room – west wall – plaster | Negative | SPI |
| 32a | 2 nd floor – dining room – north wall – plaster | Negative | SPI |
| 32b | 2 nd floor – dining room – north wall – joint compound layer | Negative | SPI |
| 33 | Exterior – on east window – white caulk | Negative | MCLKw |
| 34 | Exterior – on west window – white caulk | Negative | MCLKw |
| 35 | Exterior – on south window – white caulk | Negative | MCLKw |
| 36a | 2 nd floor – kitchen – east side top layer – gray and tan linoleum | Negative | MFLyt |
| 36b | 2 nd floor – kitchen – east side top layer – under gray and tan linoleum – tan mastic | Negative | MFLyt |
| 37a | 2 nd floor – kitchen – center top layer – gray and tan linoleum | Negative | MFLyt |
| 37b | 2 nd floor – kitchen – center top layer – under gray and tan linoleum – tan mastic | Negative | MFLyt |
| 38a | 1 st floor – kitchen – east side top layer – brown linoleum | Negative | MFLn |
| 38b | 1 st floor – kitchen – east side top layer – under brown linoleum – tan mastic | Negative | MFLn |
| 39a | 1 st floor – kitchen – west side top layer – brown linoleum | Negative | MFLn |
| 39b | 1 st floor – kitchen – west side top layer – under brown linoleum – tan mastic | Negative | MFLn |
| 40 | 1 st floor – kitchen – north side top layer – brown linoleum | Negative | MFLn |
| 42 | 1 st floor – kitchen – east side – white ceiling tile | Negative | MSCTw |

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|--|----------|------------------|
| 43 | 1 st floor – kitchen – center – white ceiling tile | Negative | MSCTw |
| 44 | 1 st floor – kitchen – west side – white ceiling tile | Negative | MSCTw |
| 45a | 1 st floor – bathroom – brown and black linoleum | Negative | MFLnk |
| 45b | 1 st floor – bathroom – under brown and black linoleum – tan mastic | Negative | MFLnk |
| 46a | Attic – east side – black linoleum | Negative | MFLk |
| 46b | Attic – east side – under black linoleum – tan mastic | Negative | MFLk |
| 47a | Attic – south side – black linoleum | Negative | MFLk |
| 47b | Attic – south side – under black linoleum – tan mastic | Negative | MFLk |
| 48a | Attic – west side – black linoleum | Negative | MFLk |
| 48b | Attic – west side – under black linoleum – tan mastic | Negative | MFLk |

One (1) of the materials sampled contains greater than 1% asbestos and is an asbestos containing material (ACM):

| Material | Homogeneous Code | Location | Approximate Quantity | Material Type |
|--------------------------------------|------------------|-------------------------------|----------------------|---------------|
| <5” Diameter Aircell Pipe Insulation | TA5 | Basement – North & East Sides | 45 SF | Friable |

Assumed Category I Non-Friable Asbestos Containing Material:

| Material | Location | Approximate Quantity | Material Type |
|-----------------------------|---|----------------------|------------------------|
| Asphalt Shingles & Flashing | House Roof | 1,400 SF | Category I Non-Friable |
| Floor Tile & Mastic | 1 st Floor Dining Room 2 nd Floor Kitchen/Sitting Room/Dining Room/ Living Room | 900 SF | Category I Non-Friable |

Note #1: The aircell is a friable asbestos containing material and meets the definition of a regulated asbestos containing material (RACM) in NR 447 NR 447.08 requires the building owner or operator to remove all RACM from a facility being demolished or renovated before any activity begins that would break up, dislodge or similarly disturb the material. DHS 159 requires that only a certified asbestos company with certified asbestos abatement personnel may remove ACMs from a building. Harenda Management Group recommends that the duct wrap be abated prior to demolition.

Note #2: The asphalt roofing and floor tile/mastic are category I non friable asbestos containing materials. Under NR 447 they do not currently meet the definition of regulated asbestos containing material (RACM) and need not be removed before demolition if the demolition debris does not become RACM and will be disposed at a Wisconsin licensed landfill.

Note#3: Category I – Non-Friable Asbestos Containing Materials may become RACM during mechanical demolition activities or maybe considered friable prior to demolition activities due to its condition at time of demolition.

Note#4: If additional materials are discovered during demolition that are not listed above they are to be assumed to be asbestos containing.

Note#5: A copy of this report should be transmitted to the demolition contractor.

Note#6: Additional aircell may be within walls and ceilings.

Homogeneous Material Codes

| | |
|-------|--------------------------------------|
| SPI | Plaster Garage |
| STX | Texture |
| MPIt | Tan Paper Insulation |
| MFLwy | White & Gray Linoleum |
| MFLy | Gray & Tan Linoleum |
| MFLyt | White & Gray Linoleum |
| MFLn | Brown Linoleum |
| MFLnk | Brown & Black Linoleum |
| MFLk | Black Linoleum |
| MDW | Drywall/Joint Compound |
| MCTMy | Gray Ceramic Tile |
| MCTMI | Yellow Ceramic Tile |
| MCTMt | Tan Ceramic Tile |
| MWMw | White Wall Panel Mastic |
| MBI | Blown in Insulation |
| MCLKw | White Caulk |
| MSCTw | White Ceiling Tile |
| TA5 | <5" Diameter Aircell Pipe Insulation |
| TFP | Flue Packing |

V. EXCLUSIONS

Dwelling is fire damaged – all rooms only partially accessible. Not all areas within walls and ceilings were accessible, and these areas may contain suspect asbestos containing materials. Only visible or accessible areas were included in the scope of work.

HMG is not and shall not represent the building owner as its agent or representative for the purpose of the US EPA/NESHAP and/or the WDNR/NR447 regulations, as owner/operator.

This report represents the condition of the building and its visible/accessible suspect asbestos containing materials at the date and the times of the onsite inspection. Hidden materials or inaccessible materials, or those materials that could be present at the point of inspection, over and above those stated in the inspection report, are the responsibility of the building owner and the demolition contractor.

VI. LIMITATIONS

The care and skill given to our procedures insures the most reliable test results possible. HMG utilizes Schneider Laboratories Global, Inc., for our asbestos testing. The findings and conclusions of HMG represent our professional opinions extrapolated from limited data. Significant limited data is gathered during the course of the preliminary asbestos specific site assessment. No other warranty is expressed or implied. Prior to any abatement or renovation activities, it is recommended that HMG be provided the opportunity to review such plans in order that the inspection and assessments contained herein are properly interpreted and implemented.

This report and the information contained herein are prepared for the sole and exclusive use and possession of the City of Milwaukee Department of Neighborhood Services. No other person or entity may rely on this report or any information contained herein. Any dissemination of the

Report or any information contained herein is strictly prohibited without prior written authorization from Harenda Management Group.

VII. PRE-DEMOLITION ENVIRONMENTAL CHECKLIST

This guide lists materials and products commonly found in buildings with examples. It is not intended as a substitute for reading the rules and statutes and making your own independent determination of their applicability to your demolition project. These examples presented here do not represent an exhaustive listing of types of materials that may be required to be removed from the building prior to demolition.

ASBESTOS

Persons conducting inspections for asbestos must hold a valid asbestos inspector certification card issued by the State of Wisconsin, Dept. of Health Services. **Please follow the Asbestos Inspection and Sampling Protocol for Buildings to be Demolished or Renovated.**

CFCs and HALONS

Equipment that may contain CFCs and Halons:

| | |
|------------|--|
| <u>N/A</u> | Air Conditioners (roof top, room, and central) |
| <u>N/A</u> | Dehumidifiers |
| <u>N/A</u> | Heat Pumps |
| <u>N/A</u> | Refrigerators, Freezers, Chillers |
| <u>N/A</u> | Vending Machines, Food Display Cases |
| <u>N/A</u> | Walk-in Coolers |
| <u>N/A</u> | Water Fountains (bubblers) |
| <u>N/A</u> | Fire Extinguishers (both portable and installed HALON suppression systems) |
| <u>N/A</u> | Water Coolers |

LEAD

Lead or Lead Based Paint (LBP) is common in many older buildings. When recycling construction and demolition debris, be aware that wood containing lead paint may not be chipped and spread for landscaping. State law also prohibits the sale or transfer of any fixture or other object containing LBP that might be placed upon any surface of a dwelling, which is ordinarily accessible to children.

MERCURY

Products that may contain mercury:

LIGHTING

| | |
|------------|--|
| <u>1</u> | Fluorescent Lights – 2 nd Floor Kitchen |
| <u>N/A</u> | High Intensity Discharge -Metal Halide -High Pressure Sodium -Mercury Vapor |
| <u>N/A</u> | Neon |
| <u>N/A</u> | Switches for lighting using mercury relays -Look for any control associated with exterior or automated lighting systems such as "Silent" wall switches. |

HVAC

Check thermostats and any control associated with air handling units for switches containing mercury.

HEATING, VENTILATING AND AIR CONDITIONING SYSTEMS

| | |
|------------|-----------------|
| <u>N/A</u> | Old Thermostats |
| <u>N/A</u> | Aquastats |
| <u>N/A</u> | Firestats |
| <u>N/A</u> | Manometers |
| <u>N/A</u> | Thermometers |

BOILERS, FURNACES, HEATERS AND TANKS

| | |
|------------|---------------------------------------|
| <u>N/A</u> | Mercury Flame Sensors by pilot lights |
| <u>N/A</u> | Manometers, Thermometers, Gauges |
| <u>N/A</u> | Pressure-trol |
| <u>N/A</u> | Float or Level Controls |
| <u>N/A</u> | Space Heaters |

ELECTRICAL SYSTEMS

| | |
|------------|-------------------------------|
| <u>N/A</u> | Load Meters and Supply Relays |
| <u>N/A</u> | Phase Splitters |
| <u>N/A</u> | Microwave Relays |
| <u>N/A</u> | Mercury Displacement Relays |

PCBs

For electrical devices manufactured prior to 1987, it is safe to assume that they contain PCBs and should be managed accordingly. Most equipment manufactured after this time will say "PCB Free". The following is a list of areas in a building were PCBs may be found:

| | |
|------------|--|
| <u>N/A</u> | Transformers |
| <u>N/A</u> | Capacitors (appliances, electronic equipment) |
| <u>N/A</u> | Heat Transfer Equipment |
| <u>N/A</u> | Ballasts |
| <u>N/A</u> | Specialty Paints (such as for swimming pools or other industrial applications) |
| <u>N/A</u> | Sumps or Oil Traps (in maintenance and industrial facilities) |

OTHER ENVIRONMENTAL ISSUES

| | |
|------------|------------------|
| <u>N/A</u> | Hazardous Waste |
| <u>N/A</u> | Oil Tanks |
| <u>N/A</u> | Well Abandonment |
| <u>N/A</u> | Junk Auto Tires |
| <u>N/A</u> | Junk Vehicles |

* 9 Gallons Paint Front Entry & 1st Floor Kitchen

VIII. ASBESTOS LABORATORY RESULTS



Customer: Harenda Management Group (5065)
Address: 1237 West Bruce Street
Milwaukee, WI 53204

| | |
|-----------------|---------------|
| Order #: | 364177 |
|-----------------|---------------|

Received 03/10/20
Analyzed 03/16/20
Reported 03/17/20

Attn:

Project:

Location: Wisconsin
Number: 20-400-020.2564

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|--|----------|-----------|-----------------|---------------------------|
| 364177-001 | 03/09/20 | 1 | Wisconsin | | |
| Layer 1: | Fibrous Material | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 364177-002 | 03/09/20 | 2 | Wisconsin | | |
| Layer 1: | Fibrous Material | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 364177-003 | 03/09/20 | 3 | Wisconsin | | |
| Layer 1: | Fibrous Material | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 364177-004 | 03/09/20 | 4 | Wisconsin | | |
| Layer 1: | Flooring | | | None Detected | 35% CELLULOSE FIBER |
| | Beige/Brown, Org.Bound/Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 50% NON FIBROUS MATERIAL |
| | Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | |
| Layer 2: | Mastic | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Soft | | | | |
| 364177-005 | 03/09/20 | 5 | Wisconsin | | |
| Layer 1: | Flooring | | | None Detected | 2% CELLULOSE FIBER |
| | Tan, Organically Bound | | | | 98% NON FIBROUS MATERIAL |
| Layer 2: | Mastic | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray, Soft | | | | |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2564

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|--------------------------|----------|-----------|-----------------|---------------------------|
| 364177-006 | 03/09/20 | 6 | Wisconsin | | |
| Layer 1: | Flooring | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Cream, Organically Bound | | | | |
| Layer 2: | Mastic | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Soft | | | | |
| 364177-007 | 03/09/20 | 7 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 4% CELLULOSE FIBER |
| | White, Powdery | | | | 96% NON FIBROUS MATERIAL |
| 364177-008 | 03/09/20 | 8 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 4% CELLULOSE FIBER |
| | White, Powdery | | | | 96% NON FIBROUS MATERIAL |
| 364177-009 | 03/09/20 | 9 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |
| 364177-010 | 03/09/20 | 10 | Wisconsin | | |
| Layer 1: | Textured Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White, Granular | | | | |
| 364177-011 | 03/09/20 | 11 | Wisconsin | | |
| Layer 1: | Textured Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White, Granular | | | | |
| 364177-012 | 03/09/20 | 12 | Wisconsin | | |
| Layer 1: | Textured Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White, Granular | | | | |
| 364177-013 | 03/09/20 | 13 | Wisconsin | | |
| Layer 1: | Ceramic Tile | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Cream, Hard | | | | |
| Layer 2: | Mastic | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Brittle | | | | |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2564

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|---|----------|-----------|-----------------|--|
| 364177-014 | 03/09/20 | 14 | Wisconsin | | |
| Layer 1: | Ceramic Tile White/Yellow/Gray/Brown, Hard | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Mastic Tan, Brittle | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364177-015 | 03/09/20 | 15 | Wisconsin | | |
| Layer 1: | Ceramic Tile Red, Hard | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Mastic Tan, Brittle | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 3: | Grout Gray, Hard | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364177-016 | 03/09/20 | 16 | Wisconsin | | |
| Layer 1: | Soft Material Light Gray, Soft | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364177-017 | 03/09/20 | 17 | Wisconsin | | |
| Layer 1: | Ceramic Tile Cream, Hard One Layer Found. | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364177-018 | 03/09/20 | 18 | Wisconsin | | |
| Layer 1: | Ceramic Tile White/Yellow/Gray/Brown, Hard One Layer Found. | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364177-019 | 03/09/20 | 19 | Wisconsin | | |
| Layer 1: | Insulation White, Fibrous | | | None Detected | 90% MINERAL/GLASS WOOL 10% NON FIBROUS MATERIAL |
| 364177-020 | 03/09/20 | 20 | Wisconsin | | |
| Layer 1: | Insulation White, Fibrous | | | None Detected | 90% MINERAL/GLASS WOOL 10% NON FIBROUS MATERIAL |
| 364177-021 | 03/09/20 | 21 | Wisconsin | | |
| Layer 1: | Insulation White, Fibrous | | | None Detected | 90% MINERAL/GLASS WOOL 10% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2564

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|-------------------|----------|-----------|-----------------|---------------------------|
| 364177-022 | 03/09/20 | 22 | Wisconsin | | |
| Layer 1: | Hard Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray, Hard | | | | |
| 364177-023 | 03/09/20 | 23 | Wisconsin | | |
| Layer 1: | Insulation | | | 60% CHRYSOTILE | 20% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 10% MINERAL/GLASS WOOL |
| | | | | | 10% NON FIBROUS MATERIAL |
| 364177-024 | 03/09/20 | 24 | Wisconsin | | |
| Layer 1: | Insulation | | | 60% CHRYSOTILE | 20% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 10% MINERAL/GLASS WOOL |
| | | | | | 10% NON FIBROUS MATERIAL |
| 364177-025 | 03/09/20 | 25 | Wisconsin | | |
| Layer 1: | Insulation | | | 60% CHRYSOTILE | 20% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 10% MINERAL/GLASS WOOL |
| | | | | | 10% NON FIBROUS MATERIAL |
| 364177-026 | 03/09/20 | 26 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 2% CELLULOSE FIBER |
| | Beige, Granular | | | | 98% NON FIBROUS MATERIAL |
| 364177-027 | 03/09/20 | 27 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 2% CELLULOSE FIBER |
| | Beige, Granular | | | | 98% NON FIBROUS MATERIAL |
| 364177-028 | 03/09/20 | 28 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 2% CELLULOSE FIBER |
| | Beige, Granular | | | | 98% NON FIBROUS MATERIAL |
| 364177-029 | 03/09/20 | 29 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 2% CELLULOSE FIBER |
| | Beige, Granular | | | | 98% NON FIBROUS MATERIAL |
| 364177-030 | 03/09/20 | 30 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 2% CELLULOSE FIBER |
| | Beige, Granular | | | | 98% NON FIBROUS MATERIAL |
| Layer 2: | Textured Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White, Granular | | | | |
| 364177-031 | 03/09/20 | 31 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 2% CELLULOSE FIBER |
| | Beige, Granular | | | | 98% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2564

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|--------------------------|----------|-----------|-----------------|---------------------------|
| 364177-032 | 03/09/20 | 32 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 2% CELLULOSE FIBER |
| | Beige, Granular | | | | 98% NON FIBROUS MATERIAL |
| Layer 2: | Textured Material | | | None Detected | 2% CELLULOSE FIBER |
| | White, Granular | | | | 98% NON FIBROUS MATERIAL |
| 364177-033 | 03/09/20 | 33 | Wisconsin | | |
| Layer 1: | Soft Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White/Gray, Soft | | | | |
| 364177-034 | 03/09/20 | 34 | Wisconsin | | |
| Layer 1: | Soft Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White/Gray, Soft | | | | |
| 364177-035 | 03/09/20 | 35 | Wisconsin | | |
| Layer 1: | Soft Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White/Gray, Soft | | | | |
| 364177-036 | 03/09/20 | 36 | Wisconsin | | |
| Layer 1: | Flooring | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Cream, Organically Bound | | | | |
| Layer 2: | Mastic | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Soft | | | | |
| 364177-037 | 03/09/20 | 37 | Wisconsin | | |
| Layer 1: | Flooring | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Cream, Organically Bound | | | | |
| Layer 2: | Mastic | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Soft | | | | |
| 364177-038 | 03/09/20 | 38 | Wisconsin | | |
| Layer 1: | Flooring | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Cream, Organically Bound | | | | |
| Layer 2: | Mastic | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Soft | | | | |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2564

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-----------|-----------|----------|----------|-----------------|-----------------|
|-----------|-----------|----------|----------|-----------------|-----------------|

| | | | | | |
|-------------------|----------|----|-----------|---------------|---|
| 364177-047 | 03/09/20 | 47 | Wisconsin | None Detected | 35% CELLULOSE FIBER 15% MINERAL/GLASS WOOL 50% NON FIBROUS MATERIAL |
|-------------------|----------|----|-----------|---------------|---|

Layer 1: Flooring
Black, Org.Bound/Fibrous

None Detected

35% CELLULOSE FIBER
15% MINERAL/GLASS WOOL
50% NON FIBROUS MATERIAL

Sample was inhomogenous, subsamples of each component were analyzed separately.

Layer 2: Mastic
Tan, Brittle

None Detected

100% NON FIBROUS MATERIAL

| | | | | | |
|-------------------|----------|----|-----------|---------------|---|
| 364177-048 | 03/09/20 | 48 | Wisconsin | None Detected | 35% CELLULOSE FIBER 15% MINERAL/GLASS WOOL 50% NON FIBROUS MATERIAL |
|-------------------|----------|----|-----------|---------------|---|

Layer 1: Flooring
Black, Org.Bound/Fibrous

None Detected

35% CELLULOSE FIBER
15% MINERAL/GLASS WOOL
50% NON FIBROUS MATERIAL

Sample was inhomogenous, subsamples of each component were analyzed separately.

Layer 2: Mastic
Tan, Brittle

None Detected

100% NON FIBROUS MATERIAL

EPA Regulatory Limit: 1%
Total layers analyzed on order: 64

364177-03/17/20 11:30 AM



Analyst Mohammed Hashim



Reviewed By: Hind Eldanaf
Microscopy Manager

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

364177

X 48



V:\364\364177

fghraizi
UPS

3/10/2020 9:53:20 AM
122E28998463323147

| | | | |
|---|-----------------|--|---|
| Submitting Co. Harenda Management Group | | State of Collection WI | Cert. Required <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct. # 5065 | Phone (414) 647-1530 |
| Milwaukee, WI 53204 | | Email dean.jacobsen@kphenvironmental.com | |
| Project Name | | PO # | |
| Project Location | Wisconsin | Special Instructions: | |
| Project Number | 20-400-020.2564 | | |
| Collected By | | | |

| Turn Around Time ** | Matrix | Tests/Analytes (Select All that Apply) Blank spaces are for additional analytes | | | |
|---|---|---|---|---|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days * not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP (w/ organics 10 Day) | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time | | Flow Rate | | Total Air ⁴ |
|----------|--------------|--------------|--|-----------|-------|------|-----------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 1 | 3/9/20 | | | | | | | | |
| 2 | | | | | | | | | |
| 3 | | | | | | | | | |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen

Signature:

Date/Time 3/9/20 1700

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

| | | | |
|--|------------------------------|---|--|
| Submitting Co. Harenda Management Group | | State of Collection WI | Cert. Required <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # 5065 | Phone (414) 647-1530 |
| Milwaukee, WI 53204 | | Email dean.jacobsen@kphenvironmental.com | |
| Project Name | | PO # | |
| Project Location Wisconsin | Special Instructions: | | |
| Project Number 20-400-020.2564 | | | |
| Collected By | | | |

| Turn Around Time** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 11 | 3/9/20 | | | | | | | | |
| 12 | | | | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | | | | | | | | |
| 16 | | | | | | | | | |
| 17 | | | | | | | | | |
| 18 | | | | | | | | | |
| 19 | | | | | | | | | |
| 20 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: Date/Time: 3/9/20 1700

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

| | | | |
|---|------------------------------|---|--|
| Submitting Co Harenda Management Group | | State of Collection WI | Cert. Required <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # 5065 | Phone (414) 647-1530 |
| Milwaukee, WI 53204 | | Email dean.jacobsen@kphenvironmental.com | |
| Project Name | | PO # | |
| Project Location Wisconsin | Special Instructions: | | |
| Project Number 20-400-020.2564 | | | |
| Collected By | | | |

| Turn Around Time** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 21 | 3/9/20 | | | | | | | | |
| 22 | | | | | | | | | |
| 23 | | | | | | | | | |
| 24 | | | | | | | | | |
| 25 | | | | | | | | | |
| 26 | | | | | | | | | |
| 27 | | | | | | | | | |
| 28 | | | | | | | | | |
| 29 | | | | | | | | | |
| 30 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen

Signature:

Date/Time 3/9/20 1700

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

| | | | | | |
|------------------------|--------------------------|-----------------------|------------------------------------|----------------|--|
| Submitting Co. | Harenda Management Group | State of Collection | WI | Cert. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmental.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.2564 | | | | |
| Collected By | | | | | |

| Turn Around Time** | Matrix | Tests/Analytes (select All that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 31 | 3/9/20 | | | | | | | | |
| 32 | | | | | | | | | |
| 33 | | | | | | | | | |
| 34 | | | | | | | | | |
| 35 | | | | | | | | | |
| 36 | | | | | | | | | |
| 37 | | | | | | | | | |
| 38 | | | | | | | | | |
| 39 | | | | | | | | | |
| 40 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen

Signature:

Date/Time 3/9/20 (RJD)

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabin.com • info@slabin.com

| | | | |
|--|------------------------------|---|--|
| Submitting Co. Harenda Management Group | | State of Collection WI | Cert. Required <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # 5065 | Phone (414) 647-1530 |
| Milwaukee, WI 53204 | | Email dean.jacobsen@kphenvironmental.com | |
| Project Name | | PO # | |
| Project Location Wisconsin | Special Instructions: | | |
| Project Number 20-400-020.2564 | | | |
| Collected By | | | |

| Turn Around Time ** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|--|--|
| | | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP (w/ organics 10 Day) | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | Gravimetric <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | Miscellaneous <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | Sub-Contract <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|--|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 41 | 3/9/20 | | | | | | | | |
| 42 | | | | | | | | | |
| 43 | | | | | | | | | |
| 44 | | | | | | | | | |
| 45 | | | | | | | | | |
| 46 | | | | | | | | | |
| 47 | | | | | | | | | |
| 48 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: [Signature] Date/Time: 3/9/20 1700


! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !

IX. FLOOR PLANS

**Two Family Dwelling
2564 North 11th Street
Milwaukee, Wisconsin**




Basement Floor Plan



**Two Family Dwelling
2564 North 11th Street
Milwaukee, Wisconsin**




1st Floor Plan



**Two Family Dwelling
2564 North 11th Street
Milwaukee, Wisconsin**




2nd Floor Plan



**Two Family Dwelling
2564 North 11th Street
Milwaukee, Wisconsin**



Attic Floor Plan



X. HMG CERTIFICATION

Company Certificate

This certifies that

HARENDA MANAGEMENT GROUP

1237 W BRUCE ST
MILWAUKEE WI 53204-1218

is certified under ch. DHS 159, Wis. Adm. Code as a

Asbestos Company -- Primary

Certificate Issue Date: 07/23/2019
Expiration Date: 08/31/2021, 12:01 a.m.
Certification #: CAP-480540

Wisconsin Department of Health Services
Division of Public Health
Bureau of Environmental and Occupational Health
Asbestos & Lead Section
PO Box 2659
Madison WI 53701-2659
Phone: (608) 261-6876



Miriam Hasan
Miriam Hasan, Unit Supervisor

ASBESTOS INSPECTOR
Issued By
STATE OF WISCONSIN
Dept. of Health Services

Jazmin K C Spears
6866 N 40th Place
Milwaukee WI 53209-2229

| | | | |
|------------|-----------------|------------|--------|
| | | 200 lbs | 5' 08" |
| All-111055 | Exp: 08/10/2020 | 10/19/1974 | |

Training due by: 08/10/2020

COPY



PRE-DEMOLITION INSPECTION REPORT

Job Site:

**Fire Damaged
One Family Dwelling
2875 North 21st Street
Milwaukee, Wisconsin**

For:

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613

**HMG Report No.: 20-400-020.2875
Inspector: Cecil Trawick
Contract No.: 360-20-0975**

Prepared by:

HARENDA MANAGEMENT GROUP
1237 West Bruce Street
Milwaukee, Wisconsin 53204
(414) 383-4800

March 2020

Signature Page
Pre-Demolition Inspection Report
One Family Dwelling
2875 North 21st Street
Milwaukee, Wisconsin



Dean Jacobsen
Asbestos Inspector No. AII – 14370
Expiration Date: 12/2/20
Harenda Management Group



Cecil Trawick
Asbestos Inspector No. AII – 104769
Expiration Date: 10/2/20
Harenda Management Group

March 20, 2020


City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613

RE: Pre-Demolition Inspection Report
2875 North 21st Street
Milwaukee, WI

Harenda Management Group has completed the pre-demolition inspection of the one family dwelling at 2875 North 21st Street, Milwaukee, Wisconsin, as per the referral from the City of Milwaukee Department of Neighborhood Services. The inspection and results are described in the following report. Please contact me at (414) 383-4800 if you have any questions.

Sincerely,

HARENDA MANAGEMENT GROUP



Dean Jacobsen
Asbestos Inspector No. AII – 14370

EXECUTIVE SUMMARY

Harenda Management Group was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection of the one family dwelling at 2875 North 21st Street, Milwaukee, Wisconsin, prior to demolition. HMG conducted a visual inspection for asbestos and universal wastes. HMG collected asbestos bulk samples for laboratory analysis.

Asbestos was detected above 1% in exterior transite siding, basement duct wrap, and basement floor tile mastic sampled during the inspection. Asbestos was not detected in any other material sampled. Asbestos was assumed to be in the asphalt roofing and in the floor tile and mastic on the 1st floor of the dwelling. Results are in Section IV of this report.

TABLE OF CONTENTS
Pre-Demolition Inspection Report

| | | |
|-------|---|----|
| I. | Introduction..... | 1 |
| II. | Asbestos Inspection | 1 |
| III. | Asbestos Laboratory | 2 |
| | A. Method of Analysis | |
| IV. | Asbestos Findings and Observations | 2 |
| V. | Exclusions | 5 |
| VI. | Limitations | 5 |
| VII. | Pre-Demolition Environmental Checklist..... | 6 |
| VIII. | Asbestos Laboratory Results..... | 10 |
| IX. | Floor Plans | 11 |
| X. | HMG Certifications | 12 |

I. INTRODUCTION

Harenda Management Group (HMG) was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection for suspect asbestos containing materials in the one family dwelling at 2875 North 21st Street, Milwaukee, Wisconsin. The dwelling is a two story wood framed structure with basement and has transite, asphalt, and wood walls and asphalt roofing.

II. ASBESTOS INSPECTION

Marge Piwaron, of the City of Milwaukee Department of Neighborhood Services, authorized HMG to conduct a building inspection and to analyze samples collected during the inspection.

On March 11, 2020, HMG conducted an asbestos inspection of a one family dwelling, scheduled for mechanical demolition, located at 2875 North 21st Street, Milwaukee, Wisconsin. The inspection was conducted by Cecil Trawick, Wisconsin License No. AII – 104769, and the report was written by Dean Jacobsen, Wisconsin License No. AII – 14370..

The inspection was comprised of these elements:

1. A visual determination as to the extent of suspect asbestos containing materials within the buildings.
2. Sampling and documentation of observable suspect asbestos containing materials.
3. Quantification of observable asbestos containing materials existing within the spaces.

The results of the inspection integrated with the Polarized Light Microscopy with Dispersion Staining (PLM/DS) analysis of asbestos bulk samples collected are outlined in this document.

The following types of suspect materials were observed and inspected to determine if asbestos containing materials were present in the building as required by U.S. EPA NESHAP regulation 40 CFR 61 Subpart M, and NR 447 of the Wisconsin Administrative Code:

- Transite siding
- Paper insulation
- Asphalt siding
- Tar paper
- Linoleum
- Duct wrap
- Flue packing
- Floor tile
- Blown in insulation
- Drywall/joint compound
- Plaster
- Window glazing compound
- Asphalt roofing
- Mastics

A listing of specific homogeneous materials and homogeneous material codes are in the Findings and Observations section following the results table.

III. ASBESTOS LABORATORY

A. METHOD OF ANALYSIS

Analysis is performed by using the bulk samples for visual observation and slide preparation(s) for microscopical examination and identification. The slides are analyzed for asbestos (chrysotile, amosite, crocidolite, anthophyllite, and actinolite/tremolite), fibrous non asbestos constituents (mineral wool, paper, etc.), and nonfibrous constituents. Asbestos is identified by refractive indices (obtained by using dispersion staining), morphology, color, pleochroism, birefringence, extinction characteristics, and signs of elongation. The same characteristics are used to identify the non asbestos constituents.

The microscopist visually estimates relative amounts of each constituent using a stereoscope if necessary. The test results are based on a visual determination of relative volume of the bulk sample components. The results are valid only for the item tested. Current federal and Wisconsin regulations state asbestos containing material means material containing more than 1% asbestos as determined using the method specified in Appendix E, Subpart E, 40 CFR Part 763 Section I, Polarized Light Microscopy. Bold values below indicate that the material contains more than 1% asbestos. Refer to 29 CFR 1926.1101 (Construction) and 29 CFR 1910.1001 (General Industry) for specific OSHA requirements.

IV. ASBESTOS FINDINGS AND OBSERVATIONS

The following are the laboratory results. The laboratory report is in Appendix A.

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|--|------------------------------------|------------------|
| 1 | Exterior – east wall – transite siding | Positive 20% Chrysotile | MTP |
| 2 | Exterior – south wall – transite siding | Positive 20% Chrysotile | MTP |
| 3 | Exterior – west wall – transite siding | Positive 20% Chrysotile | MTP |
| 4 | Exterior – east wall – under transite siding – silver paper insulation | Negative | MPIs |
| 5 | Exterior – south wall – under transite siding – silver paper insulation | Negative | MPIs |
| 6 | Exterior – west wall – under transite siding – silver paper insulation | Negative | MPIs |
| 7 | Exterior – east wall – under silver paper insulation – asphalt shingle siding | Negative | MSS |
| 8 | Exterior – south wall – under silver paper insulation – asphalt shingle siding | Negative | MSS |
| 9 | Exterior – west wall – under silver paper insulation – asphalt shingle siding | Negative | MSS |

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|---|------------------------------------|------------------|
| 10 | Exterior – east wall – under asphalt siding – tar paper | Negative | MPT |
| 11 | Exterior – south wall – under asphalt siding – tar paper | Negative | MPT |
| 12 | Exterior – west wall – under asphalt siding – tar paper | Negative | MPT |
| 13a | 1 st floor – dining room closet – brown linoleum | Negative | MFLn |
| 13b | 1 st floor – dining room closet – under brown linoleum – tan mastic | Negative | MFLn |
| 14a | 1 st floor – kitchen east side – white linoleum | Negative | MFLw |
| 14b | 1 st floor – kitchen east side – under white linoleum – tan mastic | Negative | MFLw |
| 15a | 1 st floor – kitchen north side – white linoleum | Negative | MFLw |
| 15b | 1 st floor – kitchen north side – under white linoleum – tan mastic | Negative | MFLw |
| 16a | 1 st floor – kitchen south side – white linoleum | Negative | MFLw |
| 16b | 1 st floor – kitchen south side – under white linoleum – tan mastic | Negative | MFLw |
| 17 | Basement – on duct near chimney – duct wrap | Positive 60% Chrysotile | TDW |
| 18 | Basement – on chimney – flue packing | Negative | TFP |
| 19a | Basement – east room south side – 9” cream floor tile | Negative | MF9c |
| 19b | Basement – east room south side – under 9” cream floor tile – black mastic | Positive 5% Chrysotile | MF9c |
| 20a | Basement – east room north side – 9” cream floor tile | Negative | MF9c |
| 20b | Basement – east room north side – under 9” cream floor tile – black mastic | Positive 5% Chrysotile | MF9c |
| 21a | Basement – east room east side – 9” cream floor tile | Negative | MF9c |
| 21b | Basement – east room east side – under 9” cream floor tile – black mastic | Positive 5% Chrysotile | MF9c |
| 22 | 1 st floor – kitchen – in south wall – blown in insulation | Negative | MBI |
| 23 | 2 nd floor – southwest bedroom – south side on floor – blown in insulation | Negative | MBI |
| 24 | 2 nd floor – southwest bedroom – west side on floor – blown in insulation | Negative | MBI |
| 25a | 1 st floor – kitchen – east wall – drywall | Negative | MDW |
| 25b | 1 st floor – kitchen – east wall – joint compound | Negative | MDW |
| 26 | 2 nd floor – hall – south wall – drywall | Negative | MDW |
| 27 | 2 nd floor – east bedroom – north wall – drywall | Negative | MDW |
| 28a | 1 st floor – living room – west wall – plaster | Negative | SPI |
| 28b | 1 st floor – living room – west wall – joint compound layer | Negative | SPI |
| 29a | 1 st floor – northeast bedroom – north wall – plaster | Negative | SPI |
| 29b | 1 st floor – northeast bedroom – north wall – joint compound layer | Negative | SPI |
| 30a | 1 st floor – dining room – east wall – plaster | Negative | SPI |
| 30b | 1 st floor – dining room – east wall – joint compound layer | Negative | SPI |
| 31a | 1 st floor – middle bedroom – west wall – plaster | Negative | SPI |
| 31b | 1 st floor – middle bedroom – west wall – joint compound layer | Negative | SPI |
| 32a | 1 st floor – dining room closet – west wall – plaster | Negative | SPI |
| 32b | 1 st floor – dining room closet – west wall – joint compound layer | Negative | SPI |
| 33a | 1 st floor – pantry – east wall – plaster | Negative | SPI |
| 33b | 1 st floor – pantry – east wall – joint compound layer | Negative | SPI |
| 34a | Basement – stair – south wall – plaster | Negative | SPI |
| 34b | Basement – stair – south wall – joint compound layer | Negative | SPI |

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|---|----------|------------------|
| 35 | 1 st floor – middle bedroom – on north window – glazing compound | Negative | MPG |
| 36 | 1 st floor – kitchen – on west window – glazing compound | Negative | MPG |
| 37 | 2 nd floor – east bedroom – on west window – glazing compound | Negative | MPG |

Three (3) of the materials sampled contain greater than 1% asbestos and are asbestos containing materials (ACM):

| Material | Homogeneous Code | Location | Approximate Quantity | Material Type |
|--|------------------|--------------------------------|----------------------|-------------------------|
| Transite Siding | MTP | Exterior Walls | 1,250 SF | Category II Non-Friable |
| Black Mastic Under 9” Cream Floor Tile | MF9c | Basement East Room on Concrete | 230 SF | Category II Non-Friable |
| Duct Wrap | TDW | Basement Near Chimney | 3 SF | Friable |

Assumed Category I Non-Friable Asbestos Containing Material:

| Material | Location | Approximate Quantity | Material Type |
|-----------------------------|---|----------------------|------------------------|
| Asphalt Shingles & Flashing | House Roof | 900 SF | Category I Non-Friable |
| Floor Tile & Mastic | 1 st Floor Pantry/Bathroom/Stair | 80 SF | Category I Non-Friable |

Note #1: The duct wrap is a friable asbestos containing material and meets the definition of a regulated asbestos containing material (RACM) in NR 447. The transite siding is a category II non-friable asbestos containing material and will meet the RACM definition if crumbled or reduced to powder by the demolition equipment. NR 447.08 requires the building owner or operator to remove all RACM from a facility being demolished or renovated before any activity begins that would break up, dislodge or similarly disturb the material. DHS 159 requires that only a certified asbestos company with certified asbestos abatement personnel may remove ACMs from a building. Harenda Management Group recommends that the duct wrap and transite siding be abated prior to demolition.

Note #2: The asphalt roofing and floor tile/mastic are category I non friable asbestos containing materials. Under NR 447 they do not currently meet the definition of regulated asbestos containing material (RACM) and need not be removed before demolition if the demolition debris does not become RACM and will be disposed at a Wisconsin licensed landfill. The black mastic under the 9” cream floor tile in the basement will require abatement if it will be ground, sanded, abraded, or crumbled during demolition, or if the underlying concrete will be recycled.

Note#3: Category I – Non-Friable Asbestos Containing Materials may become RACM during mechanical demolition activities or maybe considered friable prior to demolition activities due to its condition at time of demolition.

Note#4: If additional materials are discovered during demolition that are not listed above they are to be assumed to be asbestos containing.

Note#5: A copy of this report should be transmitted to the demolition contractor.

Note#6: Additional duct wrap may be within walls and ceilings.

Homogeneous Material Codes

| | |
|------|-------------------------|
| SPI | Plaster |
| MTP | Transite |
| MPIs | Silver Paper Insulation |
| MSS | Asphalt Shingle Siding |
| MPT | Tar Paper |
| MFLn | Brown Linoleum |
| MFLw | White Linoleum |
| MF9c | 9" Cream Floor Tile |
| MBI | Blown in Insulation |
| MDW | Drywall |
| MPG | Window Glazing Compound |
| TDW | Duct Wrap |
| TFP | Flue Packing |

V. EXCLUSIONS

Dwelling is fire damaged – surface in rooms only partially accessible. Not all areas within walls and ceilings were accessible, and these areas may contain suspect asbestos containing materials. Only visible or accessible areas were included in the scope of work.

HMG is not and shall not represent the building owner as its agent or representative for the purpose of the US EPA/NESHAP and/or the WDNR/NR447 regulations, as owner/operator.

This report represents the condition of the building and its visible/accessible suspect asbestos containing materials at the date and the times of the onsite inspection. Hidden materials or inaccessible materials, or those materials that could be present at the point of inspection, over and above those stated in the inspection report, are the responsibility of the building owner and the demolition contractor.

VI. LIMITATIONS

The care and skill given to our procedures insures the most reliable test results possible. HMG utilizes Schneider Laboratories Global, Inc., for our asbestos testing. The findings and conclusions of HMG represent our professional opinions extrapolated from limited data. Significant limited data is gathered during the course of the preliminary asbestos specific site assessment. No other warranty is expressed or implied. Prior to any abatement or renovation activities, it is recommended that HMG be provided the opportunity to review such plans in order that the inspection and assessments contained herein are properly interpreted and implemented.

This report and the information contained herein are prepared for the sole and exclusive use and possession of the City of Milwaukee Department of Neighborhood Services. No other person or entity may rely on this report or any information contained herein. Any dissemination of the Report or any information contained herein is strictly prohibited without prior written authorization from Harenda Management Group.

VII. PRE-DEMOLITION ENVIRONMENTAL CHECKLIST

This guide lists materials and products commonly found in buildings with examples. It is not intended as a substitute for reading the rules and statutes and making your own independent determination of their applicability to your demolition project. These examples presented here do not represent an exhaustive listing of types of materials that may be required to be removed from the building prior to demolition.

ASBESTOS

Persons conducting inspections for asbestos must hold a valid asbestos inspector certification card issued by the State of Wisconsin, Dept. of Health Services. **Please follow the Asbestos Inspection and Sampling Protocol for Buildings to be Demolished or Renovated.**

CFCs and HALONS

Equipment that may contain CFCs and Halons:

| | |
|------------|--|
| <u>N/A</u> | Air Conditioners (roof top, room, and central) |
| <u>N/A</u> | Dehumidifiers |
| <u>N/A</u> | Heat Pumps |
| <u>N/A</u> | Refrigerators, Freezers, Chillers |
| <u>N/A</u> | Vending Machines, Food Display Cases |
| <u>N/A</u> | Walk-in Coolers |
| <u>N/A</u> | Water Fountains (bubblers) |
| <u>N/A</u> | Fire Extinguishers (both portable and installed HALON suppression systems) |
| <u>N/A</u> | Water Coolers |

LEAD

Lead or Lead Based Paint (LBP) is common in many older buildings. When recycling construction and demolition debris, be aware that wood containing lead paint may not be chipped and spread for landscaping. State law also prohibits the sale or transfer of any fixture or other object containing LBP that might be placed upon any surface of a dwelling, which is ordinarily accessible to children.

MERCURY

Products that may contain mercury:

LIGHTING

| | |
|------------|--|
| <u>2</u> | Fluorescent Lights – Pantry |
| <u>N/A</u> | High Intensity Discharge -Metal Halide -High Pressure Sodium -Mercury Vapor |
| <u>N/A</u> | Neon |
| <u>N/A</u> | Switches for lighting using mercury relays -Look for any control associated with exterior or automated lighting systems such as "Silent" wall switches. |

HVAC

Check thermostats and any control associated with air handling units for switches containing mercury.

HEATING, VENTILATING AND AIR CONDITIONING SYSTEMS

| | |
|------------|-----------------|
| <u>N/A</u> | Old Thermostats |
| <u>N/A</u> | Aquastats |
| <u>N/A</u> | Firestats |
| <u>N/A</u> | Manometers |
| <u>N/A</u> | Thermometers |

BOILERS, FURNACES, HEATERS AND TANKS

| | |
|------------|---------------------------------------|
| <u>N/A</u> | Mercury Flame Sensors by pilot lights |
| <u>N/A</u> | Manometers, Thermometers, Gauges |
| <u>N/A</u> | Pressure-trol |
| <u>N/A</u> | Float or Level Controls |
| <u>N/A</u> | Space Heaters |

ELECTRICAL SYSTEMS

| | |
|------------|-------------------------------|
| <u>N/A</u> | Load Meters and Supply Relays |
| <u>N/A</u> | Phase Splitters |
| <u>N/A</u> | Microwave Relays |
| <u>N/A</u> | Mercury Displacement Relays |

PCBs

For electrical devices manufactured prior to 1987, it is safe to assume that they contain PCBs and should be managed accordingly. Most equipment manufactured after this time will say "PCB Free". The following is a list of areas in a building were PCBs may be found:

| | |
|------------|--|
| <u>N/A</u> | Transformers |
| <u>N/A</u> | Capacitors (appliances, electronic equipment) |
| <u>N/A</u> | Heat Transfer Equipment |
| <u>N/A</u> | Ballasts |
| <u>N/A</u> | Specialty Paints (such as for swimming pools or other industrial applications) |
| <u>N/A</u> | Sumps or Oil Traps (in maintenance and industrial facilities) |

OTHER ENVIRONMENTAL ISSUES

| | |
|------------|------------------------------|
| <u>N/A</u> | Hazardous Waste |
| <u>N/A</u> | Oil Tanks |
| <u>N/A</u> | Well Abandonment |
| <u>2</u> | Junk Auto Tires – Front Yard |
| <u>N/A</u> | Junk Vehicles |

* 1 Gas Meter on Exterior

VIII. ASBESTOS LABORATORY RESULTS



Customer: Harenda Management Group (5065)
Address: 1237 West Bruce Street
Milwaukee, WI 53204

| | |
|-----------------|---------------|
| Order #: | 364523 |
|-----------------|---------------|

Received 03/12/20
Analyzed 03/17/20
Reported 03/19/20

Attn:

Project:

Location: Wisconsin
Number: 20-400-020.2875

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|--|-----------|----------|-----------|-----------------|---|
| 364523-001 | 03/11/20 | 1 | Wisconsin | | |
| Layer 1: Transite Gray, Hard | | | | 20% CHRYSOTILE | 80% NON FIBROUS MATERIAL |
| 364523-002 | 03/11/20 | 2 | Wisconsin | | |
| Layer 1: Transite Gray, Hard | | | | 20% CHRYSOTILE | 80% NON FIBROUS MATERIAL |
| 364523-003 | 03/11/20 | 3 | Wisconsin | | |
| Layer 1: Transite Gray, Hard | | | | 20% CHRYSOTILE | 80% NON FIBROUS MATERIAL |
| 364523-004 | 03/11/20 | 4 | Wisconsin | | |
| Layer 1: Cover Beige/Silver, Fibrous | | | | None Detected | 65% CELLULOSE FIBER 15% MINERAL/GLASS WOOL 20% NON FIBROUS MATERIAL |
| 364523-005 | 03/11/20 | 5 | Wisconsin | | |
| Layer 1: Cover Beige/Silver, Fibrous | | | | None Detected | 65% CELLULOSE FIBER 15% MINERAL/GLASS WOOL 20% NON FIBROUS MATERIAL |
| 364523-006 | 03/11/20 | 6 | Wisconsin | | |
| Layer 1: Cover Beige/Silver, Fibrous | | | | None Detected | 65% CELLULOSE FIBER 15% MINERAL/GLASS WOOL 20% NON FIBROUS MATERIAL |
| 364523-007 | 03/11/20 | 7 | Wisconsin | | |
| Layer 1: Shingle Black, Bituminous/Granular | | | | None Detected | 5% CELLULOSE FIBER 5% MINERAL/GLASS WOOL 90% NON FIBROUS MATERIAL |

Sample was inhomogenous, subsamples of each component were analyzed separately.

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2875

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|--|----------------------------|----------|-----------|-----------------|---------------------------|
| 364523-008 | 03/11/20 | 8 | Wisconsin | | |
| Layer 1: | Shingle | | | None Detected | 5% CELLULOSE FIBER |
| | Black, Bituminous/Granular | | | | 5% MINERAL/GLASS WOOL |
| | | | | | 90% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| 364523-009 | 03/11/20 | 9 | Wisconsin | | |
| Layer 1: | Shingle | | | None Detected | 5% CELLULOSE FIBER |
| | Black, Bituminous/Granular | | | | 5% MINERAL/GLASS WOOL |
| | | | | | 90% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| 364523-010 | 03/11/20 | 10 | Wisconsin | | |
| Layer 1: | Felt | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 364523-011 | 03/11/20 | 11 | Wisconsin | | |
| Layer 1: | Felt | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 364523-012 | 03/11/20 | 12 | Wisconsin | | |
| Layer 1: | Felt | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 364523-013 | 03/11/20 | 13 | Wisconsin | | |
| Layer 1: | Tile | | | None Detected | 2% CELLULOSE FIBER |
| | Beige, Organically Bound | | | | 98% NON FIBROUS MATERIAL |
| Layer 2: | Mastic | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Soft | | | | |
| 364523-014 | 03/11/20 | 14 | Wisconsin | | |
| Layer 1: | Tile | | | None Detected | 2% CELLULOSE FIBER |
| | Beige, Organically Bound | | | | 98% NON FIBROUS MATERIAL |
| Layer 2: | Mastic | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Soft | | | | |
| 364523-015 | 03/11/20 | 15 | Wisconsin | | |
| Layer 1: | Tile | | | None Detected | 2% CELLULOSE FIBER |
| | Beige, Organically Bound | | | | 98% NON FIBROUS MATERIAL |
| Layer 2: | Mastic | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Soft | | | | |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2875

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|--------------------------|----------|-----------|-----------------|---------------------------|
| 364523-016 | 03/11/20 | 16 | Wisconsin | | |
| Layer 1: | Tile | | | None Detected | 2% CELLULOSE FIBER |
| | Beige, Organically Bound | | | | 98% NON FIBROUS MATERIAL |
| Layer 2: | Mastic | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Soft | | | | |
| 364523-017 | 03/11/20 | 17 | Wisconsin | | |
| Layer 1: | Insulation | | | 60% CHRYSOTILE | 20% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 10% MINERAL/GLASS WOOL |
| | | | | | 10% NON FIBROUS MATERIAL |
| 364523-018 | 03/11/20 | 18 | Wisconsin | | |
| Layer 1: | Hard Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray/Black, Hard | | | | |
| 364523-019 | 03/11/20 | 19 | Wisconsin | | |
| Layer 1: | Tile | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Beige, Organically Bound | | | | |
| Layer 2: | Mastic | | | 5% CHRYSOTILE | 95% NON FIBROUS MATERIAL |
| | Black, Bituminous | | | | |
| 364523-020 | 03/11/20 | 20 | Wisconsin | | |
| Layer 1: | Tile | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Beige, Organically Bound | | | | |
| Layer 2: | Mastic | | | 5% CHRYSOTILE | 95% NON FIBROUS MATERIAL |
| | Black, Bituminous | | | | |
| 364523-021 | 03/11/20 | 21 | Wisconsin | | |
| Layer 1: | Tile | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Beige, Organically Bound | | | | |
| Layer 2: | Mastic | | | 5% CHRYSOTILE | 95% NON FIBROUS MATERIAL |
| | Black, Bituminous | | | | |
| 364523-022 | 03/11/20 | 22 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2875

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|-------------------|----------|-----------|-----------------|---------------------------|
| 364523-023 | 03/11/20 | 23 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 364523-024 | 03/11/20 | 24 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 364523-025 | 03/11/20 | 25 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |
| Layer 2: | Joint Compound | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White, Granular | | | | |
| 364523-026 | 03/11/20 | 26 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |
| | One Layer Found. | | | | |
| 364523-027 | 03/11/20 | 27 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |
| | One Layer Found. | | | | |
| 364523-028 | 03/11/20 | 28 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray, Granular | | | | |
| Layer 2: | Textured Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White, Granular | | | | |
| 364523-029 | 03/11/20 | 29 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray, Granular | | | | |
| Layer 2: | Textured Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White, Granular | | | | |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2875

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|---|----------|-----------|-----------------|---------------------------|
| 364523-030 | 03/11/20 | 30 | Wisconsin | | |
| Layer 1: | Plaster Gray, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Textured Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364523-031 | 03/11/20 | 31 | Wisconsin | | |
| Layer 1: | Plaster Beige, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Textured Material Beige, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364523-032 | 03/11/20 | 32 | Wisconsin | | |
| Layer 1: | Plaster Beige, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Textured Material Beige, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364523-033 | 03/11/20 | 33 | Wisconsin | | |
| Layer 1: | Plaster Beige, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Textured Material Beige, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364523-034 | 03/11/20 | 34 | Wisconsin | | |
| Layer 1: | Plaster Beige, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Textured Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364523-035 | 03/11/20 | 35 | Wisconsin | | |
| Layer 1: | Granular Material White/Gray, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364523-036 | 03/11/20 | 36 | Wisconsin | | |
| Layer 1: | Granular Material White/Gray, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2875

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|--|-----------|----------|-----------|-----------------|---------------------------|
| 364523-037 | 03/11/20 | 37 | Wisconsin | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 1: Granular Material White/Gray, Granular | | | | | |

EPA Regulatory Limit: 1%
Total layers analyzed on order: 52

364523-03/19/20 12:20 PM



Analyst **Mohammed Hashim**



Reviewed By: **Hind Eldanaf**
Microscopy Manager

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com



V:1364\364523

fghraizi
UPS

3/12/2020 9:34:35 AM
1Z2E28998462225157

| | | | |
|--|------------------------------|---|---|
| Submitting Co Harendra Management Group | | State of Collection WI | Cert Required <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # 5065 | Phone (414) 647-1530 |
| Milwaukee, WI 53204 | | Email dean.jacobsen@kphenvironmental.com | |
| Project Name | | PO # | |
| Project Location Wisconsin | Special Instructions: | | |
| Project Number 20-400-020.2875 | | | |
| Collected By | | | |

| Turn Around Time** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|---|---|---|---|---|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days * not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP (w/ organics 10 Day) | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 1 | 3/11/20 | | | | | | | | |
| 2 | | | | | | | | | |
| 3 | | | | | | | | | |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: *[Signature]* Date/Time: 3/11/2020

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

| | | | |
|--|------------------------------|---|---|
| Submitting Co. Harenda Management Group | | State of Collection WI | Cert Required <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # 5065 | Phone (414) 647-1530 |
| Milwaukee, WI 53204 | | Email dean.jacobsen@kphenvironmental.com | |
| Project Name | | PO # | |
| Project Location Wisconsin | Special Instructions: | | |
| Project Number 20-400-020.2875 | | | |
| Collected By | | | |

| Turn Around Time** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests</small> <small>** past 3 PM the TAT will begin next business day</small> <small>Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 11 | 3/11/20 | | | | | | | | |
| 12 | | | | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | | | | | | | | |
| 16 | | | | | | | | | |
| 17 | | | | | | | | | |
| 18 | | | | | | | | | |
| 19 | | | | | | | | | |
| 20 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: *Dean Jacobsen* Date/Time 3/11/20 1700

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

| | | | | | |
|------------------------|--------------------------|-----------------------|------------------------------------|----------------|--|
| Submitting Co. | Harenda Management Group | State of Collection | WI | Cert. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmental.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.2875 | | | | |
| Collected By | | | | | |

| Turn Around Time** | Matrix | Tests/Analytes (Select All that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|---|--|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests</small> <small>** past 3 PM the TAT will begin next business day</small> <small>Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM | <input type="checkbox"/> Lead | <input type="checkbox"/> Lead | <input type="checkbox"/> BACT (MPN/PA) |
| | | <input type="checkbox"/> PLM Qualitative | <input type="checkbox"/> RCRA 8 Metals | <input type="checkbox"/> RCRA 8 Metals | <input type="checkbox"/> Mold Direct Exam |
| | | <input type="checkbox"/> 400 Point Count | <input type="checkbox"/> Chromium VI | <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> Allergens |
| | | <input type="checkbox"/> 1000 Point Count | <input type="checkbox"/> Mercury | | Sub-Contract |
| | | <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> _____ | | <input type="checkbox"/> TEM Chatfield |
| | | Asbestos in Air | Gravimetric | Miscellaneous | <input type="checkbox"/> TEM AHERA |
| | | <input type="checkbox"/> PCM | <input type="checkbox"/> Total Dust NIOSH 0500 | <input type="checkbox"/> Silica FTIR (7602) | <input type="checkbox"/> TEM 7402 |
| | | <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> _____ | <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 21 | 3/11/20 | | | | | | | | |
| 22 | | | | | | | | | |
| 23 | | | | | | | | | |
| 24 | | | | | | | | | |
| 25 | | | | | | | | | |
| 26 | | | | | | | | | |
| 27 | | | | | | | | | |
| 28 | | | | | | | | | |
| 29 | | | | | | | | | |
| 30 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis
¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: Date/Time 3/11/20 1250

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

| | | | | | |
|-------------------------|--------------------------|------------------------------|-------------------------------------|-----------------------|--|
| Submitting Co: | Harenda Management Group | State of Collection | WI | Cert. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmenmtal.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.2875 | | | | |
| Collected By | | | | | |

| Turn Around Time** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|--|---|--|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests</small> <small>** past 3 PM the TAT will begin next business day</small> <i>Please schedule rush tests in advance</i> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM | <input type="checkbox"/> Lead | <input type="checkbox"/> Lead | <input type="checkbox"/> BACT (MPN/PA) |
| | | <input type="checkbox"/> PLM Qualitative | <input type="checkbox"/> RCRA 8 Metals | <input type="checkbox"/> RCRA 8 Metals | <input type="checkbox"/> Mold Direct Exam |
| | | <input type="checkbox"/> 400 Point Count | <input type="checkbox"/> Chromium VI | <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> Allergens |
| | | <input type="checkbox"/> 1000 Point Count | <input type="checkbox"/> Mercury | | Sub-Contract |
| | | <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> _____ | | <input type="checkbox"/> TEM Chatfield |
| | | Asbestos in Air | Gravimetric | Miscellaneous | <input type="checkbox"/> TEM AHERA |
| | | <input type="checkbox"/> PCM | <input type="checkbox"/> Total Dust NIOSH 0500 | <input type="checkbox"/> Silica FTIR (7602) | <input type="checkbox"/> TEM 7402 |
| | | <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> _____ | <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification <small>(Employee, Bldg, Material, Type¹)</small> | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|--|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 31 | 3/11/20 | | | | | | | | |
| 32 | | | | | | | | | |
| 33 | | | | | | | | | |
| 34 | | | | | | | | | |
| 35 | | | | | | | | | |
| 36 | | | | | | | | | |
| 37 | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min × flow in L/min]

Relinquished By: Dean Jacobsen Signature: Date/Time: 3/11/20 1700


! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !

IX. FLOOR PLANS

**One Family Dwelling
2875 North 21st Street
Milwaukee, Wisconsin**




Basement Floor Plan



**One Family Dwelling
2875 North 21st Street
Milwaukee, Wisconsin**




1st Floor Plan



**One Family Dwelling
2875 North 21st Street
Milwaukee, Wisconsin**



2nd Floor Plan



X. HMG CERTIFICATION

Company Certificate

This certifies that

HARENDA MANAGEMENT GROUP

1237 W BRUCE ST
MILWAUKEE WI 53204-1218

is certified under ch. DHS 159, Wis.Adm.Code as a

Asbestos Company -- Primary

Certificate Issue Date: 07/23/2019
Expiration Date: 08/31/2021, 12:01 a.m.
Certification #: CAP-480540

Wisconsin Department of Health Services
Division of Public Health
Bureau of Environmental and Occupational Health
Asbestos & Lead Section
PO Box 2659
Madison WI 53701-2659
Phone: (608) 261-6876



Miriam Hasan
Miriam Hasan, Unit Supervisor





ASBESTOS INSPECTOR

Issued By

STATE OF WISCONSIN

Dept. of Health Services

Cecil James Trawick Jr

5624 N 97th Street

Milwaukee WI 53227 2502

| | | | |
|------------|-----------------|------------|--------|
| | | 222 lbs | 5' 08" |
| All-104769 | Exp: 10/02/2020 | 07/09/1971 | |

Training due by: 10/02/2020

COPY



PRE-DEMOLITION INSPECTION REPORT

Job Site:

**Fire Damaged
One Family Rear Dwelling
2118A North 24th Place
Milwaukee, Wisconsin**

For:

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613


**HMG Report No.: 20-400-020.2118A
Inspector: Jazmin Spears
Contract No.: 360-20-0975**

Prepared by:

HARENDA MANAGEMENT GROUP
1237 West Bruce Street
Milwaukee, Wisconsin 53204
(414) 383-4800

March 2020

Signature Page
Pre-Demolition Inspection Report
One Family Rear Dwelling
2118A North 24th Place
Milwaukee, Wisconsin



Dean Jacobsen
Asbestos Inspector No. AII – 14370
Expiration Date: 12/2/20
Harenda Management Group



Jazmin Spears
Asbestos Inspector No. AII – 111055
Expiration Date: 8/10/20
Harenda Management Group

March 19, 2020

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613

RE: Pre-Demolition Inspection Report
2118A North 24th Place
Milwaukee, WI

Harenda Management Group has completed the pre-demolition inspection of the one family rear dwelling at 2118A North 24th Place, Milwaukee, Wisconsin, as per the referral from the City of Milwaukee Department of Neighborhood Services. The inspection and results are described in the following report. Please contact me at (414) 383-4800 if you have any questions.

Sincerely,

HARENDA MANAGEMENT GROUP



Dean Jacobsen
Asbestos Inspector No. AII – 14370

EXECUTIVE SUMMARY

Harenda Management Group was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection of the one family rear dwelling at 2118A North 24th Place, Milwaukee, Wisconsin, prior to demolition. HMG conducted a visual inspection for asbestos and universal wastes. HMG collected asbestos bulk samples for laboratory analysis.

Asbestos was detected above 1% in exterior caulk sampled during the inspection. Asbestos was not detected in any other material sampled. Asbestos was assumed to be in the asphalt roofing and in the floor tile and mastic in the dwelling. Results are in Section IV of this report.

TABLE OF CONTENTS
Pre-Demolition Inspection Report

| | | |
|-------|---|----|
| I. | Introduction..... | 1 |
| II. | Asbestos Inspection | 1 |
| III. | Asbestos Laboratory | 2 |
| | A. Method of Analysis | |
| IV. | Asbestos Findings and Observations | 2 |
| V. | Exclusions | 4 |
| VI. | Limitations | 4 |
| VII. | Pre-Demolition Environmental Checklist..... | 7 |
| VIII. | Asbestos Laboratory Results..... | 9 |
| IX. | Floor Plans | 10 |
| X. | HMG Certifications | 11 |

I. INTRODUCTION

Harenda Management Group (HMG) was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection for suspect asbestos containing materials in the one family rear dwelling at 2118A North 24th Place, Milwaukee, Wisconsin. The dwelling is a two story wood framed structure with aluminum and wood walls and asphalt roofing.

II. ASBESTOS INSPECTION

Marge Piwaron, of the City of Milwaukee Department of Neighborhood Services, authorized HMG to conduct a building inspection and to analyze samples collected during the inspection.

On March 10, 2020, HMG conducted an asbestos inspection of a one family rear dwelling, scheduled for mechanical demolition, located at 2118A North 24th Place, Milwaukee, Wisconsin. The inspection was conducted by Jazmin Spears, Wisconsin License No. AII – 111055, and the report was written by Dean Jacobsen, Wisconsin License No. AII – 14370..

The inspection was comprised of these elements:

1. A visual determination as to the extent of suspect asbestos containing materials within the buildings.
2. Sampling and documentation of observable suspect asbestos containing materials.
3. Quantification of observable asbestos containing materials existing within the spaces.

The results of the inspection integrated with the Polarized Light Microscopy with Dispersion Staining (PLM/DS) analysis of asbestos bulk samples collected are outlined in this document.

The following types of suspect materials were observed and inspected to determine if asbestos containing materials were present in the building as required by U.S. EPA NESHAP regulation 40 CFR 61 Subpart M, and NR 447 of the Wisconsin Administrative Code:

- Paper insulation
- Caulk
- Linoleum
- Drywall/joint compound
- Plaster
- Floor tile
- Asphalt roofing
- Mastics

A listing of specific homogeneous materials and homogeneous material codes are in the Findings and Observations section following the results table.

III. ASBESTOS LABORATORY

A. METHOD OF ANALYSIS

Analysis is performed by using the bulk samples for visual observation and slide preparation(s) for microscopical examination and identification. The slides are analyzed for asbestos (chrysotile, amosite, crocidolite, anthophyllite, and actinolite/tremolite), fibrous non asbestos constituents (mineral wool, paper, etc.), and nonfibrous constituents. Asbestos is identified by refractive indices (obtained by using dispersion staining), morphology, color, pleochroism, birefringence, extinction characteristics, and signs of elongation. The same characteristics are used to identify the non asbestos constituents.

The microscopist visually estimates relative amounts of each constituent using a stereoscope if necessary. The test results are based on a visual determination of relative volume of the bulk sample components. The results are valid only for the item tested. Current federal and Wisconsin regulations state asbestos containing material means material containing more than 1% asbestos as determined using the method specified in Appendix E, Subpart E, 40 CFR Part 763 Section I, Polarized Light Microscopy. Bold values below indicate that the material contains more than 1% asbestos. Refer to 29 CFR 1926.1101 (Construction) and 29 CFR 1910.1001 (General Industry) for specific OSHA requirements.

IV. ASBESTOS FINDINGS AND OBSERVATIONS

The following are the laboratory results. The laboratory report is in Appendix A.

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|--|-------------------------------|------------------|
| 1 | Exterior – east wall – under aluminum siding – silver paper insulation | Negative | MPIs |
| 2 | Exterior – north wall – under aluminum siding – silver paper insulation | Negative | MPIs |
| 3 | Exterior – west wall – under aluminum siding – silver paper insulation | Negative | MPIs |
| 4 | Exterior – east wall – under wood siding – red paper insulation | Negative | MPIr |
| 5 | Exterior – north wall – under wood siding – red paper insulation | Negative | MPIr |
| 6 | Exterior – west wall – under wood siding – red paper insulation | Negative | MPIr |
| 7 | Exterior – on north window – gray caulk | Negative | MCLKy |
| 8 | Exterior – on west window – gray caulk | Negative | MCLKy |
| 9 | Exterior – on east window – gray caulk | Positive 4% Chrysotile | MCLKy |
| 10 | 1 st floor – living room – under carpet – gray linoleum | Negative | MFLy |
| 11 | 1 st floor – kitchen – east side – white and tan linoleum | Negative | MFLwt |
| 12 | 1 st floor – living room – east wall – drywall | Negative | MDW |
| 13a | 2 nd floor – hall – south wall – drywall | Negative | MDW |
| 13b | 2 nd floor – hall – south wall – joint compound | Negative | MDW |
| 14a | 2 nd floor – south bedroom – north wall – drywall | Negative | MDW |
| 14b | 2 nd floor – south bedroom – north wall – joint compound | Negative | MDW |
| 15 | 2 nd floor – bathroom – on east wall above tub – white mastic | Negative | MWMw |

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|--|----------|------------------|
| 16a | 1 st floor – north bedroom – north wall – plaster base coat | Negative | SPI |
| 16b | 1 st floor – north bedroom – north wall – plaster skim coat | Negative | SPI |
| 17a | 1 st floor – bathroom – west wall – plaster base coat | Negative | SPI |
| 17b | 1 st floor – bathroom – west wall – plaster skim coat | Negative | SPI |
| 18a | 2 nd floor – stair – north wall – plaster base coat | Negative | SPI |
| 18b | 2 nd floor – stair – north wall – plaster skim coat | Negative | SPI |
| 19a | 2 nd floor – bathroom – west wall – plaster base coat | Negative | SPI |
| 19b | 2 nd floor – bathroom – west wall – plaster skim coat | Negative | SPI |
| 20a | 1 st floor – kitchen – east wall – plaster base coat | Negative | SPI |
| 20b | 1 st floor – kitchen – east wall – plaster skim coat | Negative | SPI |

One (1) of the materials sampled contains greater than 1% asbestos and is an asbestos containing material (ACM):

| Material | Homogeneous Code | Location | Approximate Quantity | Material Type |
|------------|------------------|---|----------------------|-------------------------|
| Gray Caulk | MCLKy | Exterior Around Windows & Doors on Siding | 17 Windows & 2 Doors | Category II Non-Friable |

Assumed Category I Non-Friable Asbestos Containing Material:

| Material | Location | Approximate Quantity | Material Type |
|-----------------------------|---|----------------------|------------------------|
| Asphalt Shingles & Flashing | House Roof | 700 SF | Category I Non-Friable |
| Floor Tile & Mastic | 1 st Floor Kitchen/Bathroom/Stair 2 nd Floor Hall/Bathroom | 380 SF | Category I Non-Friable |

Note #1: The gray caulk is a category II non-friable asbestos containing material. It will meet the definition of a regulated asbestos containing material (RACM) in NR 447 if it becomes crumbled, pulverized or reduced to powder by the forces expected to act on the material in the course of demolition or renovation operations. NR 447.08 requires the building owner or operator to remove all RACM from a facility being demolished or renovated before any activity begins that would break up, dislodge or similarly disturb the material. DHS 159 requires that only a certified asbestos company with certified asbestos abatement personnel may remove ACMs from a building. Harenda Management Group recommends that the gray caulk be abated prior to demolition.

Note #2: The asphalt roofing and floor tile/mastic are category I non friable asbestos containing materials. Under NR 447 they do not currently meet the definition of regulated asbestos containing material (RACM) and need not be removed before demolition if the demolition debris does not become RACM and will be disposed at a Wisconsin licensed landfill.

Note#3: Category I – Non-Friable Asbestos Containing Materials may become RACM during mechanical demolition activities or maybe considered friable prior to demolition activities due to its condition at time of demolition.

Note#4: If additional materials are discovered during demolition that are not listed above they are to be assumed to be asbestos containing.

Note#5: A copy of this report should be transmitted to the demolition contractor.

Homogeneous Material Codes

| | |
|-------|-------------------------|
| SPI | Plaster |
| MPIs | Silver Paper Insulation |
| MPIr | Red Paper Insulation |
| MCLKy | Gray Caulk |
| MFLwt | White & Tan Linoleum |
| MFLy | Gray & Tan Linoleum |
| MDW | Drywall/Joint Compound |
| MWMw | White Wall Panel Mastic |

V. EXCLUSIONS

Dwelling is fire damaged – 1st and 2nd floor rooms only partially accessible. Attic not accessible. Basement flooded – no access. Not all areas within walls and ceilings were accessible, and these areas may contain suspect asbestos containing materials. Only visible or accessible areas were included in the scope of work.

HMG is not and shall not represent the building owner as its agent or representative for the purpose of the US EPA/NESHAP and/or the WDNR/NR447 regulations, as owner/operator.

This report represents the condition of the building and its visible/accessible suspect asbestos containing materials at the date and the times of the onsite inspection. Hidden materials or inaccessible materials, or those materials that could be present at the point of inspection, over and above those stated in the inspection report, are the responsibility of the building owner and the demolition contractor.

VI. LIMITATIONS

The care and skill given to our procedures insures the most reliable test results possible. HMG utilizes Schneider Laboratories Global, Inc., for our asbestos testing. The findings and conclusions of HMG represent our professional opinions extrapolated from limited data. Significant limited data is gathered during the course of the preliminary asbestos specific site assessment. No other warranty is expressed or implied. Prior to any abatement or renovation activities, it is recommended that HMG be provided the opportunity to review such plans in order that the inspection and assessments contained herein are properly interpreted and implemented.

This report and the information contained herein are prepared for the sole and exclusive use and possession of the City of Milwaukee Department of Neighborhood Services. No other person or entity may rely on this report or any information contained herein. Any dissemination of the Report or any information contained herein is strictly prohibited without prior written authorization from Harenda Management Group.

VII. PRE-DEMOLITION ENVIRONMENTAL CHECKLIST

This guide lists materials and products commonly found in buildings with examples. It is not intended as a substitute for reading the rules and statutes and making your own independent determination of their applicability to your demolition project. These examples presented here do not represent an exhaustive listing of types of materials that may be required to be removed from the building prior to demolition.

ASBESTOS

Persons conducting inspections for asbestos must hold a valid asbestos inspector certification card issued by the State of Wisconsin, Dept. of Health Services. **Please follow the Asbestos Inspection and Sampling Protocol for Buildings to be Demolished or Renovated.**

CFCs and HALONS

Equipment that may contain CFCs and Halons:

| | |
|------------|--|
| <u>N/A</u> | Air Conditioners (roof top, room, and central) |
| <u>N/A</u> | Dehumidifiers |
| <u>N/A</u> | Heat Pumps |
| <u>N/A</u> | Refrigerators, Freezers, Chillers |
| <u>N/A</u> | Vending Machines, Food Display Cases |
| <u>N/A</u> | Walk-in Coolers |
| <u>N/A</u> | Water Fountains (bubblers) |
| <u>N/A</u> | Fire Extinguishers (both portable and installed HALON suppression systems) |
| <u>N/A</u> | Water Coolers |

LEAD

Lead or Lead Based Paint (LBP) is common in many older buildings. When recycling construction and demolition debris, be aware that wood containing lead paint may not be chipped and spread for landscaping. State law also prohibits the sale or transfer of any fixture or other object containing LBP that might be placed upon any surface of a dwelling, which is ordinarily accessible to children.

MERCURY

Products that may contain mercury:

LIGHTING

| | |
|------------|--|
| <u>N/A</u> | Fluorescent Lights |
| <u>N/A</u> | High Intensity Discharge -Metal Halide -High Pressure Sodium -Mercury Vapor |
| <u>N/A</u> | Neon |
| <u>N/A</u> | Switches for lighting using mercury relays -Look for any control associated with exterior or automated lighting systems such as "Silent" wall switches. |

HVAC

Check thermostats and any control associated with air handling units for switches containing mercury.

HEATING, VENTILATING AND AIR CONDITIONING SYSTEMS

| | |
|------------|-----------------|
| <u>N/A</u> | Old Thermostats |
| <u>N/A</u> | Aquastats |
| <u>N/A</u> | Firestats |
| <u>N/A</u> | Manometers |
| <u>N/A</u> | Thermometers |

BOILERS, FURNACES, HEATERS AND TANKS

| | |
|------------|---------------------------------------|
| <u>N/A</u> | Mercury Flame Sensors by pilot lights |
| <u>N/A</u> | Manometers, Thermometers, Gauges |
| <u>N/A</u> | Pressure-trol |
| <u>N/A</u> | Float or Level Controls |
| <u>N/A</u> | Space Heaters |

ELECTRICAL SYSTEMS

| | |
|------------|-------------------------------|
| <u>N/A</u> | Load Meters and Supply Relays |
| <u>N/A</u> | Phase Splitters |
| <u>N/A</u> | Microwave Relays |
| <u>N/A</u> | Mercury Displacement Relays |

PCBs

For electrical devices manufactured prior to 1987, it is safe to assume that they contain PCBs and should be managed accordingly. Most equipment manufactured after this time will say "PCB Free". The following is a list of areas in a building were PCBs may be found:

| | |
|------------|--|
| <u>N/A</u> | Transformers |
| <u>N/A</u> | Capacitors (appliances, electronic equipment) |
| <u>N/A</u> | Heat Transfer Equipment |
| <u>N/A</u> | Ballasts |
| <u>N/A</u> | Specialty Paints (such as for swimming pools or other industrial applications) |
| <u>N/A</u> | Sumps or Oil Traps (in maintenance and industrial facilities) |

OTHER ENVIRONMENTAL ISSUES

| | |
|------------|------------------|
| <u>N/A</u> | Hazardous Waste |
| <u>N/A</u> | Oil Tanks |
| <u>N/A</u> | Well Abandonment |
| <u>N/A</u> | Junk Auto Tires |
| <u>N/A</u> | Junk Vehicles |

* 1 Gas Meter on Exterior

VIII. ASBESTOS LABORATORY RESULTS



Customer: Harenda Management Group (5065)
Address: 1237 West Bruce Street
Milwaukee, WI 53204

| | |
|-----------------|---------------|
| Order #: | 364521 |
|-----------------|---------------|

Received 03/12/20
Analyzed 03/16/20
Reported 03/19/20

Attn:

Project:

Location: Wisconsin
Number: 20-400-020.2118A

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|-----------------------|----------|-----------|-----------------|--------------------------|
| 364521-001 | 03/10/20 | 1 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 70% CELLULOSE FIBER |
| | Silver/Brown, Fibrous | | | | 20% METAL FOIL |
| | | | | | 10% NON FIBROUS MATERIAL |
| 364521-002 | 03/10/20 | 2 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 70% CELLULOSE FIBER |
| | Silver/Brown, Fibrous | | | | 20% METAL FOIL |
| | | | | | 10% NON FIBROUS MATERIAL |
| 364521-003 | 03/10/20 | 3 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 70% CELLULOSE FIBER |
| | Silver/Brown, Fibrous | | | | 20% METAL FOIL |
| | | | | | 10% NON FIBROUS MATERIAL |
| 364521-004 | 03/10/20 | 4 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 80% CELLULOSE FIBER |
| | Purple, Fibrous | | | | 20% NON FIBROUS MATERIAL |
| 364521-005 | 03/10/20 | 5 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 80% CELLULOSE FIBER |
| | Brown, Fibrous | | | | 20% NON FIBROUS MATERIAL |
| 364521-006 | 03/10/20 | 6 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 80% CELLULOSE FIBER |
| | Purple, Fibrous | | | | 20% NON FIBROUS MATERIAL |
| 364521-007 | 03/10/20 | 7 | Wisconsin | | |
| Layer 1: | Granular Material | | | None Detected | 2% CELLULOSE FIBER |
| | Gray, Granular | | | | 98% NON FIBROUS MATERIAL |
| 364521-008 | 03/10/20 | 8 | Wisconsin | | |
| Layer 1: | Granular Material | | | None Detected | 2% CELLULOSE FIBER |
| | Gray, Granular | | | | 98% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2118A

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|--|--|----------|-----------|-----------------|---|
| 364521-009 | 03/10/20 | 9 | Wisconsin | | |
| Layer 1: | Bituminous Material Black, Bituminous | | | 4% CHRYSOTILE | 96% NON FIBROUS MATERIAL |
| 364521-010 | 03/10/20 | 10 | Wisconsin | | |
| Layer 1: | Fibrous Material Black, Fibrous | | | None Detected | 40% CELLULOSE FIBER 60% NON FIBROUS MATERIAL |
| 364521-011 | 03/10/20 | 11 | Wisconsin | | |
| Layer 1: | Linoleum Beige, Org.Bound/Fibrous | | | None Detected | 30% CELLULOSE FIBER 70% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| 364521-012 | 03/10/20 | 12 | Wisconsin | | |
| Layer 1: | Drywall White, Powdery | | | None Detected | 4% CELLULOSE FIBER 96% NON FIBROUS MATERIAL |
| 364521-013 | 03/10/20 | 13 | Wisconsin | | |
| Layer 1: | Drywall White, Powdery | | | None Detected | 4% CELLULOSE FIBER 96% NON FIBROUS MATERIAL |
| Layer 2: | Joint Compound White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364521-014 | 03/10/20 | 14 | Wisconsin | | |
| Layer 1: | Drywall White, Powdery | | | None Detected | 10% CELLULOSE FIBER 90% NON FIBROUS MATERIAL |
| Layer 2: | Plaster Gray, Granular | | | None Detected | 2% CELLULOSE FIBER 98% NON FIBROUS MATERIAL |
| 364521-015 | 03/10/20 | 15 | Wisconsin | | |
| Layer 1: | Soft Material Off White, Soft | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364521-016 | 03/10/20 | 16 | Wisconsin | | |
| Layer 1: | Plaster Gray, Granular | | | None Detected | 98% NON FIBROUS MATERIAL 2% SYNTHETIC FIBER |
| Layer 2: | Skim Coat White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:


Location: Wisconsin
Number: 20-400-020.2118A

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|---------------------------------------|-----------|----------|-----------|-----------------|---|
| 364521-017 | 03/10/20 | 17 | Wisconsin | | |
| Layer 1: Plaster Gray, Granular | | | | None Detected | 2% CELLULOSE FIBER 98% NON FIBROUS MATERIAL |
| Layer 2: Skim Coat Beige, Granular | | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364521-018 | 03/10/20 | 18 | Wisconsin | | |
| Layer 1: Drywall White, Powdery | | | | None Detected | 10% CELLULOSE FIBER 90% NON FIBROUS MATERIAL |
| Layer 2: Plaster Gray, Granular | | | | None Detected | 2% CELLULOSE FIBER 98% NON FIBROUS MATERIAL |
| 364521-019 | 03/10/20 | 19 | Wisconsin | | |
| Layer 1: Plaster Gray, Granular | | | | None Detected | 2% CELLULOSE FIBER 98% NON FIBROUS MATERIAL |
| Layer 2: Skim Coat Beige, Granular | | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364521-020 | 03/10/20 | 20 | Wisconsin | | |
| Layer 1: Plaster Gray, Granular | | | | None Detected | 2% CELLULOSE FIBER 98% NON FIBROUS MATERIAL |
| Layer 2: Skim Coat Beige, Granular | | | | None Detected | 100% NON FIBROUS MATERIAL |

EPA Regulatory Limit: 1%
Total layers analyzed on order: 27



Analyst **Jada Wilson**

364521-03/19/20 12:06 PM



Reviewed By: **Hind Eldanaf**
Microscopy Manager

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

364521 O 20

 V: 13641364521
 fghraizi 3/12/2020 9:34:35 AM
 UPS 1Z2E28998462225157

| | | | |
|--|------------------------------|---|--|
| Submitting Co. Harenda Management Group | | State of Collection WI | Cert. Required <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # 5065 | Phone (414) 647-1530 |
| Milwaukee, WI 53204 | | Email dean.jacobsen@kphenvironmental.com | |
| Project Name | | PO # | |
| Project Location Wisconsin | Special Instructions: | | |
| Project Number 20-400-020.2118A | | | |
| Collected By | | | |

| Turn Around Time ** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|---|---|---|---|---|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days * not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP (w/ organics 10 Day) | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 1 | 3/10/20 | | | | | | | | |
| 2 | | | | | | | | | |
| 3 | | | | | | | | | |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: Date/Time 3/11/2020

ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

| | | | |
|---|-----------------------|---|--|
| Submitting Co: Harenda Management Group | | State of Collection: WI | Cert. Required: <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct #: 5065 | Phone: (414) 647-1530 |
| Milwaukee, WI 53204 | | Email: dean.jacobsen@kphenviromenmtal.com | |
| Project Name: | | PO #: | |
| Project Location: Wisconsin | Special Instructions: | | |
| Project Number: 20-400-020.2118A | | | |
| Collected By: | | | |

| Turn Around Time ** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 11 | 3/10/20 | | | | | | | | |
| 12 | | | | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | | | | | | | | |
| 16 | | | | | | | | | |
| 17 | | | | | | | | | |
| 18 | | | | | | | | | |
| 19 | | | | | | | | | |
| 20 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen

Signature:

Date/Time: 3/11/2020


! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !

IX. FLOOR PLANS

**One Family Rear Dwelling
2118A North 24th Place
Milwaukee, Wisconsin**




1st Floor Plan



**One Family Rear Dwelling
2118A North 24th Place
Milwaukee, Wisconsin**



2nd Floor Plan



X. HMG CERTIFICATION

Company Certificate

This certifies that

HARENDA MANAGEMENT GROUP

1237 W BRUCE ST
MILWAUKEE WI 53204-1218

is certified under ch. DHS 159, Wis.Adm.Code as a

Asbestos Company -- Primary

Certificate Issue Date: 07/23/2019
Expiration Date: 08/31/2021, 12:01 a.m.
Certification #: CAP-480540

Wisconsin Department of Health Services
Division of Public Health
Bureau of Environmental and Occupational Health
Asbestos & Lead Section
PO Box 2659
Madison WI 53701-2659
Phone: (608) 261-6876



Miriam Hasan
Miriam Hasan, Unit Supervisor



ASBESTOS INSPECTOR
Issued By
STATE OF WISCONSIN
Dept. of Health Services

Jazmin K C Spears
6866 N 40th Place
Milwaukee WI 53209-2229

| | | | |
|------------|-----------------|------------|--------|
| | | 200 lbs | 5' 08" |
| All-111055 | Exp: 08/10/2020 | 10/19/1974 | |

Training due by: 08/10/2020

COPY



PRE-DEMOLITION INSPECTION REPORT

Job Site:

**Two Family Front Dwelling
2122 North 24th Place
Milwaukee, Wisconsin**

For:

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613

**HMG Report No.: 20-400-020.2122
Inspector: Jazmin Spears
Contract No.: 360-20-0975**

Prepared by:

HARENDA MANAGEMENT GROUP
1237 West Bruce Street
Milwaukee, Wisconsin 53204
(414) 383-4800

March 2020

Signature Page
Pre-Demolition Inspection Report
Two Family Front Dwelling
2122 North 24th Place
Milwaukee, Wisconsin



Dean Jacobsen
Asbestos Inspector No. AII – 14370
Expiration Date: 12/2/20
Harenda Management Group



Jazmin Spears
Asbestos Inspector No. AII – 111055
Expiration Date: 8/10/20
Harenda Management Group

March 23, 2020

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613

RE: Pre-Demolition Inspection Report
2122 North 24th Place Front Dwelling
Milwaukee, WI

Harenda Management Group has completed the pre-demolition inspection of the two family front dwelling at 2122 North 24th Place, Milwaukee, Wisconsin, as per the referral from the City of Milwaukee Department of Neighborhood Services. The inspection and results are described in the following report. Please contact me at (414) 383-4800 if you have any questions.

Sincerely,

HARENDA MANAGEMENT GROUP



Dean Jacobsen
Asbestos Inspector No. AII – 14370

EXECUTIVE SUMMARY

Harenda Management Group was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection of the two family front dwelling at 2122 North 24th Place, Milwaukee, Wisconsin, prior to demolition. HMG conducted a visual inspection for asbestos and universal wastes. HMG collected asbestos bulk samples for laboratory analysis.

Asbestos was not detected above 1% in any material sampled during the inspection. Asbestos was detected at less than 1% in window glazing compound. Asbestos was assumed to be in the asphalt roofing and in the floor tile and mastic in the dwelling. Results are in Section IV of this report.

TABLE OF CONTENTS
Pre-Demolition Inspection Report

| | | |
|-------|---|----|
| I. | Introduction..... | 1 |
| II. | Asbestos Inspection | 1 |
| III. | Asbestos Laboratory | 2 |
| | A. Method of Analysis | |
| IV. | Asbestos Findings and Observations | 2 |
| V. | Exclusions | 4 |
| VI. | Limitations | 4 |
| VII. | Pre-Demolition Environmental Checklist..... | 6 |
| VIII. | Asbestos Laboratory Results..... | 10 |
| IX. | Floor Plans | 11 |
| X. | HMG Certifications | 12 |

I. INTRODUCTION

Harenda Management Group (HMG) was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection for suspect asbestos containing materials in the two family front dwelling at 2122 North 24th Place, Milwaukee, Wisconsin. The dwelling is a two story wood framed structure with aluminum and wood walls and asphalt roofing.

II. ASBESTOS INSPECTION

Marge Piwaron, of the City of Milwaukee Department of Neighborhood Services, authorized HMG to conduct a building inspection and to analyze samples collected during the inspection.

On March 11, 2020, HMG conducted an asbestos inspection of a two family front dwelling, scheduled for mechanical demolition, located at 2122 North 24th Place, Milwaukee, Wisconsin. The inspection was conducted by Jazmin Spears, Wisconsin License No. AII – 111055, and the report was written by Dean Jacobsen, Wisconsin License No. AII – 14370..

The inspection was comprised of these elements:

1. A visual determination as to the extent of suspect asbestos containing materials within the buildings.
2. Sampling and documentation of observable suspect asbestos containing materials.
3. Quantification of observable asbestos containing materials existing within the spaces.

The results of the inspection integrated with the Polarized Light Microscopy with Dispersion Staining (PLM/DS) analysis of asbestos bulk samples collected are outlined in this document.

The following types of suspect materials were observed and inspected to determine if asbestos containing materials were present in the building as required by U.S. EPA NESHAP regulation 40 CFR 61 Subpart M, and NR 447 of the Wisconsin Administrative Code:

- Paper insulation
- Caulk
- Window Glazing Compound
- Linoleum
- Plaster
- Drywall/joint compound
- Duct wrap
- Flue packing
- Blown in insulation
- Floor tile
- Asphalt roofing
- Mastics

A listing of specific homogeneous materials and homogeneous material codes are in the Findings and Observations section following the results table.

III. ASBESTOS LABORATORY

A. METHOD OF ANALYSIS

Analysis is performed by using the bulk samples for visual observation and slide preparation(s) for microscopical examination and identification. The slides are analyzed for asbestos (chrysotile, amosite, crocidolite, anthophyllite, and actinolite/tremolite), fibrous non asbestos constituents (mineral wool, paper, etc.), and nonfibrous constituents. Asbestos is identified by refractive indices (obtained by using dispersion staining), morphology, color, pleochroism, birefringence, extinction characteristics, and signs of elongation. The same characteristics are used to identify the non asbestos constituents.

The microscopist visually estimates relative amounts of each constituent using a stereoscope if necessary. The test results are based on a visual determination of relative volume of the bulk sample components. The results are valid only for the item tested. Current federal and Wisconsin regulations state asbestos containing material means material containing more than 1% asbestos as determined using the method specified in Appendix E, Subpart E, 40 CFR Part 763 Section I, Polarized Light Microscopy. . A point count analysis was performed for sample layers that were near 1% asbestos by the PLM method to better define the asbestos content. Bold values below indicate that the material contains more than 1% asbestos. Refer to 29 CFR 1926.1101 (Construction) and 29 CFR 1910.1001 (General Industry) for specific OSHA requirements.

IV. ASBESTOS FINDINGS AND OBSERVATIONS

The following are the laboratory results. The laboratory report is in Appendix A.

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|--|------------------------|------------------|
| 1 | Exterior – west wall – under wood siding – tan paper insulation | Negative | MPIt |
| 2 | Exterior – south wall – under wood siding – tan paper insulation | Negative | MPIt |
| 3 | Exterior – east wall – under wood siding – tan paper insulation | Negative | MPIt |
| 4 | Exterior – on west window – gray caulk | Negative | MCLKy |
| 5 | Exterior – on west door – gray caulk | Negative | MCLKy |
| 6 | Exterior – on east window – gray caulk | Negative | MCLKy |
| 7 | 1 st floor – kitchen – on north wall – white mastic | Negative | MWMw |
| 8 | 1 st floor – kitchen – on east window – glazing compound | Negative | MPG |
| 9 | 1 st floor – north bedroom – on north window – glazing compound | Negative | MPG |
| 10 | 2 nd floor – north bedroom – on north window – glazing compound | Positive 2% Chrysotile | MPG |
| 10 | Point Count Result | Trace 2% Chrysotile | MPG |
| 11 | 1 st floor – north bedroom – under carpet – beige and pink linoleum | Negative | MFLep |
| 12a | 1 st floor – kitchen – south wall – plaster base coat | Negative | SPI |

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|--|----------|------------------|
| 12b | 1 st floor – kitchen – south wall – plaster skim coat | Negative | SPI |
| 12c | 1 st floor – kitchen – south wall – joint compound layer | Negative | SPI |
| 13 | 1 st floor – dining room – south wall – plaster | Negative | SPI |
| 14a | 1 st floor – living room – west wall – plaster base coat | Negative | SPI |
| 14b | 1 st floor – living room – west wall – plaster skim coat | Negative | SPI |
| 15a | 2 nd floor – living room – west wall – plaster base coat | Negative | SPI |
| 15b | 2 nd floor – living room – west wall – plaster skim coat | Negative | SPI |
| 16 | 2 nd floor – kitchen – east wall – plaster | Negative | SPI |
| 17 | 2 nd floor – north bedroom – north wall under drywall – plaster | Negative | SPI |
| 18a | 2 nd floor – northwest bedroom – west wall – plaster base coat | Negative | SPI |
| 18b | 2 nd floor – northwest bedroom – west wall – plaster skim coat | Negative | SPI |
| 19 | 1 st floor – front entry – green and brown linoleum | Negative | MFLgn |
| 20a | 1 st floor – dining room – west wall – drywall | Negative | MDW |
| 20b | 1 st floor – dining room – west wall – joint compound | Negative | MDW |
| 21 | 1 st floor – dining room – east wall – drywall | Negative | MDW |
| 22 | 2 nd floor – north bedroom – north wall – drywall | Negative | MDW |
| 23 | Basement – on south duct – duct wrap | Negative | TDW |
| 24 | Basement – on north duct – duct wrap | Negative | TDW |
| 25 | Basement – on west duct – duct wrap | Negative | TDW |
| 26 | Basement – on chimney – flue packing | Negative | TFP |
| 27 | 2 nd floor – stair – brown and yellow linoleum | Negative | MFLnl |
| 28 | 2 nd floor – kitchen – north side – brown linoleum | Negative | MFLn |
| 29 | 2 nd floor – kitchen – east side – brown linoleum | Negative | MFLn |
| 30 | 2 nd floor – kitchen – south side – brown linoleum | Negative | MFLn |
| 31 | Attic – north side on floor – tan blown in insulation | Negative | MBI |
| 31 | Attic – north side on floor – pink blown in insulation | Negative | MBI |
| 32 | Attic – south side on floor – tan blown in insulation | Negative | MBI |
| 32 | Attic – south side on floor – pink blown in insulation | Negative | MBI |
| 33 | Attic – east side on floor – tan blown in insulation | Negative | MBI |
| 33 | Attic – east side on floor – pink blown in insulation | Negative | MBI |

None of the materials sampled contain greater than 1% asbestos.

One (1) of the materials sampled contains less than 1% asbestos as verified by point counting and is not an asbestos containing material (ACM):

| Material | Homogeneous Code | Location | Approximate Quantity | Material Type |
|-------------------------|------------------|-----------------------|----------------------|-------------------------|
| Window Glazing Compound | MPG | Windows on All Floors | 29 Windows | Category II Non-Friable |

Assumed Category I Non-Friable Asbestos Containing Material:

| Material | Location | Approximate Quantity | Material Type |
|-----------------------------|---|----------------------|------------------------|
| Asphalt Shingles & Flashing | House Roof | 800 SF | Category I Non-Friable |
| Floor Tile & Mastic | 1 st Floor Back Entry/Kitchen/Bathroom 2 nd Floor Bathroom | 280 SF | Category I Non-Friable |

Note #1: The asphalt roofing and floor tile/mastic in the house are category I non friable asbestos containing materials. Under NR 447 they do not currently meet the definition of regulated

asbestos containing material (RACM) and need not be removed before demolition if the demolition debris does not become RACM and will be disposed at a Wisconsin licensed landfill.

Note#2: Category I – Non-Friable Asbestos Containing Materials may become RACM during mechanical demolition activities or maybe considered friable prior to demolition activities due to its condition at time of demolition.

Note#3: If additional materials are discovered during demolition that are not listed above they are to be assumed to be asbestos containing.

Note#4: A copy of this report should be transmitted to the demolition contractor.

Homogeneous Material Codes

| | |
|-------|-------------------------|
| SPI | Plaster |
| MPIt | Tan Paper Insulation |
| MCLKy | Gray Caulk |
| MWMw | White Wall Panel Mastic |
| MPG | Window Glazing Compound |
| MFLep | Beige & Pink Linoleum |
| MFLgn | Green & Brown Linoleum |
| MFLnl | Brown & Yellow Linoleum |
| MFLn | Brown Linoleum |
| MDW | Drywall/Joint Compound |
| MBI | Blown in Insulation |
| TDW | Duct Wrap |
| TFP | Flue Packing |

V. EXCLUSIONS

Not all areas within walls and ceilings were accessible, and these areas may contain suspect asbestos containing materials. Only visible or accessible areas were included in the scope of work.

HMG is not and shall not represent the building owner as its agent or representative for the purpose of the US EPA/NESHAP and/or the WDNR/NR447 regulations, as owner/operator.

This report represents the condition of the building and its visible/accessible suspect asbestos containing materials at the date and the times of the onsite inspection. Hidden materials or inaccessible materials, or those materials that could be present at the point of inspection, over and above those stated in the inspection report, are the responsibility of the building owner and the demolition contractor.

VI. LIMITATIONS

The care and skill given to our procedures insures the most reliable test results possible. HMG utilizes Schneider Laboratories Global, Inc., for our asbestos testing. The findings and conclusions of HMG represent our professional opinions extrapolated from limited data. Significant limited data is gathered during the course of the preliminary asbestos specific site assessment. No other warranty is expressed or implied. Prior to any abatement or renovation activities, it is recommended that HMG be provided the opportunity to review such plans in

order that the inspection and assessments contained herein are properly interpreted and implemented.

This report and the information contained herein are prepared for the sole and exclusive use and possession of the City of Milwaukee Department of Neighborhood Services. No other person or entity may rely on this report or any information contained herein. Any dissemination of the Report or any information contained herein is strictly prohibited without prior written authorization from Harenda Management Group.

VII. PRE-DEMOLITION ENVIRONMENTAL CHECKLIST

This guide lists materials and products commonly found in buildings with examples. It is not intended as a substitute for reading the rules and statutes and making your own independent determination of their applicability to your demolition project. These examples presented here do not represent an exhaustive listing of types of materials that may be required to be removed from the building prior to demolition.

ASBESTOS

Persons conducting inspections for asbestos must hold a valid asbestos inspector certification card issued by the State of Wisconsin, Dept. of Health Services. **Please follow the Asbestos Inspection and Sampling Protocol for Buildings to be Demolished or Renovated.**

CFCs and HALONS

Equipment that may contain CFCs and Halons:

| | |
|------------|--|
| <u>N/A</u> | Air Conditioners (roof top, room, and central) |
| <u>N/A</u> | Dehumidifiers |
| <u>N/A</u> | Heat Pumps |
| <u>N/A</u> | Refrigerators, Freezers, Chillers |
| <u>N/A</u> | Vending Machines, Food Display Cases |
| <u>N/A</u> | Walk-in Coolers |
| <u>N/A</u> | Water Fountains (bubblers) |
| <u>N/A</u> | Fire Extinguishers (both portable and installed HALON suppression systems) |
| <u>N/A</u> | Water Coolers |

LEAD

Lead or Lead Based Paint (LBP) is common in many older buildings. When recycling construction and demolition debris, be aware that wood containing lead paint may not be chipped and spread for landscaping. State law also prohibits the sale or transfer of any fixture or other object containing LBP that might be placed upon any surface of a dwelling, which is ordinarily accessible to children.

MERCURY

Products that may contain mercury:

LIGHTING

| | |
|------------|--|
| <u>1</u> | Fluorescent Lights – 1 st Floor North Bedroom |
| <u>N/A</u> | High Intensity Discharge -Metal Halide -High Pressure Sodium -Mercury Vapor |
| <u>N/A</u> | Neon |
| <u>N/A</u> | Switches for lighting using mercury relays -Look for any control associated with exterior or automated lighting systems such as "Silent" wall switches. |

HVAC

Check thermostats and any control associated with air handling units for switches containing mercury.

HEATING, VENTILATING AND AIR CONDITIONING SYSTEMS

| | |
|------------|-----------------|
| <u>N/A</u> | Old Thermostats |
| <u>N/A</u> | Aquastats |
| <u>N/A</u> | Firestats |
| <u>N/A</u> | Manometers |
| <u>N/A</u> | Thermometers |

BOILERS, FURNACES, HEATERS AND TANKS – 2 Furnaces & 2 Water Heaters in Basement

| | |
|------------|---------------------------------------|
| <u>N/A</u> | Mercury Flame Sensors by pilot lights |
| <u>N/A</u> | Manometers, Thermometers, Gauges |
| <u>N/A</u> | Pressure-trol |
| <u>N/A</u> | Float or Level Controls |
| <u>N/A</u> | Space Heaters |

ELECTRICAL SYSTEMS

| | |
|------------|-------------------------------|
| <u>N/A</u> | Load Meters and Supply Relays |
| <u>N/A</u> | Phase Splitters |
| <u>N/A</u> | Microwave Relays |
| <u>N/A</u> | Mercury Displacement Relays |

PCBs

For electrical devices manufactured prior to 1987, it is safe to assume that they contain PCBs and should be managed accordingly. Most equipment manufactured after this time will say "PCB Free". The following is a list of areas in a building were PCBs may be found:

| | |
|------------|--|
| <u>N/A</u> | Transformers |
| <u>N/A</u> | Capacitors (appliances, electronic equipment) |
| <u>N/A</u> | Heat Transfer Equipment |
| <u>N/A</u> | Ballasts |
| <u>N/A</u> | Specialty Paints (such as for swimming pools or other industrial applications) |
| <u>N/A</u> | Sumps or Oil Traps (in maintenance and industrial facilities) |

OTHER ENVIRONMENTAL ISSUES

| | |
|------------|------------------|
| <u>N/A</u> | Hazardous Waste |
| <u>N/A</u> | Oil Tanks |
| <u>N/A</u> | Well Abandonment |
| <u>N/A</u> | Junk Auto Tires |
| <u>N/A</u> | Junk Vehicles |

* 1 Gas Meter on Exterior

* 3 Gallons Paint 2nd Floor Bathroom

VIII. ASBESTOS LABORATORY RESULTS



Customer: Harenda Management Group (5065)
Address: 1237 West Bruce Street
Milwaukee, WI 53204

| | |
|-----------------|---------------|
| Order #: | 364524 |
|-----------------|---------------|

Received 03/12/20
Analyzed 03/16/20
Reported 03/19/20

Attn:

Project:

Location: Wisconsin
Number: 20-400-020.2122F

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|------------------|----------|-----------|-----------------|---------------------------|
| 364524-001 | 03/11/20 | 1 | Wisconsin | | |
| Layer 1: | Fibrous Material | | | None Detected | 80% CELLULOSE FIBER |
| | Tan, Fibrous | | | | 20% NON FIBROUS MATERIAL |
| 364524-002 | 03/11/20 | 2 | Wisconsin | | |
| Layer 1: | Fibrous Material | | | None Detected | 80% CELLULOSE FIBER |
| | Tan, Fibrous | | | | 20% NON FIBROUS MATERIAL |
| 364524-003 | 03/11/20 | 3 | Wisconsin | | |
| Layer 1: | Fibrous Material | | | None Detected | 80% CELLULOSE FIBER |
| | Tan, Fibrous | | | | 20% NON FIBROUS MATERIAL |
| 364524-004 | 03/11/20 | 4 | Wisconsin | | |
| Layer 1: | Brittle Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Brittle | | | | |
| 364524-005 | 03/11/20 | 5 | Wisconsin | | |
| Layer 1: | Brittle Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Brittle | | | | |
| 364524-006 | 03/11/20 | 6 | Wisconsin | | |
| Layer 1: | Soft Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White, Soft | | | | |
| 364524-007 | 03/11/20 | 7 | Wisconsin | | |
| Layer 1: | Soft Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Soft | | | | |
| 364524-008 | 03/11/20 | 8 | Wisconsin | | |
| Layer 1: | Brittle Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Beige, Brittle | | | | |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2122F

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|--|--|----------|-----------|-----------------|--|
| 364524-009 | 03/11/20 | 9 | Wisconsin | | |
| Layer 1: | Brittle Material Beige, Brittle | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364524-010 | 03/11/20 | 10 | Wisconsin | | |
| Layer 1: | Brittle Material Gray, Brittle | | | 2% CHRYSOTILE | 98% NON FIBROUS MATERIAL |
| 364524-011 | 03/11/20 | 11 | Wisconsin | | |
| Layer 1: | Linoleum Multi-Colored, Org.Bound/Fibrous | | | None Detected | 20% CELLULOSE FIBER 60% NON FIBROUS MATERIAL 20% SYNTHETIC FIBER |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| 364524-012 | 03/11/20 | 12 | Wisconsin | | |
| Layer 1: | Plaster Gray, Hard/Granular | | | None Detected | 3% ANIMAL HAIR 97% NON FIBROUS MATERIAL |
| Layer 2: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 3: | Granular Material Beige, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364524-013 | 03/11/20 | 13 | Wisconsin | | |
| Layer 1: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364524-014 | 03/11/20 | 14 | Wisconsin | | |
| Layer 1: | Plaster Gray, Hard/Granular | | | None Detected | 3% ANIMAL HAIR 97% NON FIBROUS MATERIAL |
| Layer 2: | Granular Material White, Hard | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364524-015 | 03/11/20 | 15 | Wisconsin | | |
| Layer 1: | Plaster Gray, Hard/Granular | | | None Detected | 3% ANIMAL HAIR 97% NON FIBROUS MATERIAL |
| Layer 2: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2122F

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|--|--|----------|-----------|-----------------|--|
| 364524-016 | 03/11/20 | 16 | Wisconsin | | |
| Layer 1: | Granular Material Gray, Hard/Granular | | | None Detected | 3% ANIMAL HAIR 97% NON FIBROUS MATERIAL |
| 364524-017 | 03/11/20 | 17 | Wisconsin | | |
| Layer 1: | Granular Material Gray, Hard/Granular | | | None Detected | 3% ANIMAL HAIR 3% CELLULOSE FIBER 94% NON FIBROUS MATERIAL |
| 364524-018 | 03/11/20 | 18 | Wisconsin | | |
| Layer 1: | Plaster Gray, Hard/Granular | | | None Detected | 3% ANIMAL HAIR 97% NON FIBROUS MATERIAL |
| Layer 2: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364524-019 | 03/11/20 | 19 | Wisconsin | | |
| Layer 1: | Linoleum Tan/Green, Org.Bound/Fibrous | | | None Detected | 20% CELLULOSE FIBER 60% NON FIBROUS MATERIAL 20% SYNTHETIC FIBER |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| 364524-020 | 03/11/20 | 20 | Wisconsin | | |
| Layer 1: | Gypsum Board White, Powdery | | | None Detected | 10% CELLULOSE FIBER 90% NON FIBROUS MATERIAL |
| Layer 2: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 364524-021 | 03/11/20 | 21 | Wisconsin | | |
| Layer 1: | Gypsum Board White, Powdery One layer found. | | | None Detected | 10% CELLULOSE FIBER 90% NON FIBROUS MATERIAL |
| 364524-022 | 03/11/20 | 22 | Wisconsin | | |
| Layer 1: | Gypsum Board White, Powdery One layer found. | | | None Detected | 10% CELLULOSE FIBER 90% NON FIBROUS MATERIAL |
| 364524-023 | 03/11/20 | 23 | Wisconsin | | |
| Layer 1: | Fibrous Material Brown, Fibrous | | | None Detected | 80% CELLULOSE FIBER 20% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2122F

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|--|-------------------------------|----------|-----------|-----------------|---------------------------|
| 364524-024 | 03/11/20 | 24 | Wisconsin | | |
| Layer 1: | Fibrous Material | | | None Detected | 80% CELLULOSE FIBER |
| | Brown, Fibrous | | | | 20% NON FIBROUS MATERIAL |
| 364524-025 | 03/11/20 | 25 | Wisconsin | | |
| Layer 1: | Fibrous Material | | | None Detected | 80% CELLULOSE FIBER |
| | Brown, Fibrous | | | | 20% NON FIBROUS MATERIAL |
| 364524-026 | 03/11/20 | 26 | Wisconsin | | |
| Layer 1: | Granular Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray, Hard/Granular | | | | |
| 364524-027 | 03/11/20 | 27 | Wisconsin | | |
| Layer 1: | Linoleum | | | None Detected | 20% CELLULOSE FIBER |
| | Brown, Org.Bound/Fibrous | | | | 60% NON FIBROUS MATERIAL |
| | | | | | 20% SYNTHETIC FIBER |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| 364524-028 | 03/11/20 | 28 | Wisconsin | | |
| Layer 1: | Linoleum | | | None Detected | 15% MINERAL/GLASS WOOL |
| | Dark Brown, Organically Bound | | | | 85% NON FIBROUS MATERIAL |
| 364524-029 | 03/11/20 | 29 | Wisconsin | | |
| Layer 1: | Linoleum | | | None Detected | 15% MINERAL/GLASS WOOL |
| | Dark Brown, Organically Bound | | | | 85% NON FIBROUS MATERIAL |
| 364524-030 | 03/11/20 | 30 | Wisconsin | | |
| Layer 1: | Linoleum | | | None Detected | 15% MINERAL/GLASS WOOL |
| | Dark Brown, Organically Bound | | | | 85% NON FIBROUS MATERIAL |
| 364524-031 | 03/11/20 | 31 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 95% CELLULOSE FIBER |
| | Tan, Fibrous | | | | 5% NON FIBROUS MATERIAL |
| Layer 2: | Insulation | | | None Detected | 90% MINERAL/GLASS WOOL |
| | Pink, Fibrous | | | | 10% NON FIBROUS MATERIAL |
| 364524-032 | 03/11/20 | 32 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 95% CELLULOSE FIBER |
| | Tan, Fibrous | | | | 5% NON FIBROUS MATERIAL |
| Layer 2: | Insulation | | | None Detected | 90% MINERAL/GLASS WOOL |
| | Pink, Fibrous | | | | 10% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2122F

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|------------|---------------|----------|-----------|-----------------|--------------------------|
| 364524-033 | 03/11/20 | 33 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 95% CELLULOSE FIBER |
| | Tan, Fibrous | | | | 5% NON FIBROUS MATERIAL |
| Layer 2: | Insulation | | | None Detected | 90% MINERAL/GLASS WOOL |
| | Pink, Fibrous | | | | 10% NON FIBROUS MATERIAL |

EPA Regulatory Limit: 1%
Total layers analyzed on order: 42

364524-03/19/20 12:10 PM



Analyst **Senhory Abdellatif**



Reviewed By: **Hind Eldanaf**
Microscopy Manager

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.



364524 X 33

 V:13641364524
 fghraizi 3/12/2020 9:34:35 AM
 UPS 1Z2E28998462225157

| | | | | | |
|------------------------|--------------------------|-----------------------|------------------------------------|----------------|--|
| Submitting Co | Harenda Management Group | State of Collection | WI | Cert. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmental.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.2122F | | | | |
| Collected By | | | | | |

| Turn Around Time ** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|--|--|---|--|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | Metals Total <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | TCLP <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | Microbiology <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | Gravimetric <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | Miscellaneous <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | Sub-Contract <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 1 | 3/11/20 | | | | | | | | |
| 2 | | | | | | | | | |
| 3 | | | | | | | | | |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: [Signature] Date/Time 3/11/20 1700

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabin.com • info@slabin.com

| | | | | | |
|-------------------------|--------------------------|------------------------------|------------------------------------|----------------------|--|
| Submitting Co. | Harenda Management Group | State of Collection | WI | Cert Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmental.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.2122F | | | | |
| Collected By | | | | | |

| Turn Around Time ** | Matrix | Tests/Analytes (Select ALL that Apply) - Blank spaces are for additional analytes | | | |
|--|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days. * not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 11 | 3/11/20 | | | | | | | | |
| 12 | | | | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | | | | | | | | |
| 16 | | | | | | | | | |
| 17 | | | | | | | | | |
| 18 | | | | | | | | | |
| 19 | | | | | | | | | |
| 20 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: [Signature] Date/Time 3/11/20 1700

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabin.com • info@slabin.com

| | | | | | |
|------------------------|--------------------------|-----------------------|------------------------------------|----------------|--|
| Submitting Co | Harenda Management Group | State of Collection | WI | Cert. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmental.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.2122F | | | | |
| Collected By | | | | | |

| Turn Around Time ** | Matrix | Tests/Analytes (Select All that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 21 | 3/11/20 | | | | | | | | |
| 22 | | | | | | | | | |
| 23 | | | | | | | | | |
| 24 | | | | | | | | | |
| 25 | | | | | | | | | |
| 26 | | | | | | | | | |
| 27 | | | | | | | | | |
| 28 | | | | | | | | | |
| 29 | | | | | | | | | |
| 30 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min × flow in L/min]

Relinquished By: Dean Jacobsen

Signature:

Date/Time: 3/11/20 1700

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

| | | | |
|--|------------------------------|---|---|
| Submitting Co. Harenda Management Group | | State of Collection WI | Cert Required <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # 5065 | Phone (414) 647-1530 |
| Milwaukee, WI 53204 | | Email dean.jacobsen@kphenvironmental.com | |
| Project Name | | PO # | |
| Project Location Wisconsin | Special Instructions: | | |
| Project Number 20-400-020.2122F | | | |
| Collected By | | | |

| Turn Around Time** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 31 | 3/11/20 | | | | | | | | |
| 32 | ↓ | | | | | | | | |
| 33 | ↓ | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: Date/Time: 3/11/20 1700

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



Analysis Report

Schneider Laboratories Global, Inc

2512 W. Cary Street • Richmond, Virginia • 23220-5117
804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475

Customer: Harenda Management Group (5065)
Address: 1237 West Bruce Street
Milwaukee, WI 53204

Order #: 365626

Received 03/12/20
Analyzed 03/23/20
Reported 03/23/20

Attn:

Project:

Location: Wisconsin
Number: 20-400-020.2122F

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763 with Point Count **PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|--|-----------|----------|-----------|------------------|-----------------------------|
| 365626-001 | 03/11/20 | 10 | Wisconsin | 0.50% CHRYSOTILE | 99.50% NON FIBROUS MATERIAL |
| Layer 1: Brittle Material Gray, Brittle, Homogenous | | | | | |

EPA Regulatory Limit: 1%
Total layers analyzed on order: 1

365626-03/23/20 01:40 PM

Analyst **Senhory Abdellatif**

Reviewed By: **Hind Eldanaf**
Microscopy Manager

Reporting limit: 0.25% Samples analyzed by the EPA Point Count test method. The EPA recommends that any vermiculite sample with a trace (<1) or greater amount of asbestos is a concern and should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the lab, and must not be used to claim NVLAP or other government agency endorsement. The test results reported relate only to the samples submitted.



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

365626

X 1



V:\365\365626

abruner

3/19/2020 4:54:03 PM

UPS

| | | | | | |
|------------------------|--------------------------|-----------------------|------------------------------------|----------------|--|
| Submitting Co. | Harenda Management Group | State of Collection | WI | Cert. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmental.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.2122F | | | | |
| Collected By | | | | | |

| Turn Around Time ** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|---|---|---|---|---|--|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input checked="" type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input type="checkbox"/> 5 business days * not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input type="checkbox"/> PLM | <input type="checkbox"/> Lead | <input type="checkbox"/> Lead | <input type="checkbox"/> BACT (MPN/PA) |
| | | <input type="checkbox"/> PLM Qualitative | <input type="checkbox"/> RCRA 8 Metals | <input type="checkbox"/> RCRA 8 Metals | <input type="checkbox"/> Mold Direct Exam |
| | | <input checked="" type="checkbox"/> 400 Point Count | <input type="checkbox"/> Chromium VI | <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> Allergens |
| | | <input type="checkbox"/> 1000 Point Count | <input type="checkbox"/> Mercury | | Sub-Contract |
| | | <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> _____ | | <input type="checkbox"/> TEM Chatfield |
| | | Asbestos in Air | Gravimetric | Miscellaneous | <input type="checkbox"/> TEM AHERA |
| | | <input type="checkbox"/> PCM | <input type="checkbox"/> Total Dust NIOSH 0500 | <input type="checkbox"/> Silica FTIR (7602) | <input type="checkbox"/> TEM 7402 |
| | | <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> _____ | <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification <small>(Employee, Bldg, Material, Type)</small> | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|--|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 10 | 3/11/20 | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis
¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [Time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: *[Signature]* Date/Time: 3/19/20 1430


! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !

IX. FLOOR PLANS

**Two Family Front Dwelling
2122 North 24th Place
Milwaukee, Wisconsin**




Basement Floor Plan



**Two Family Front Dwelling
2122 North 24th Place
Milwaukee, Wisconsin**




1st Floor Plan



**Two Family Front Dwelling
2122 North 24th Place
Milwaukee, Wisconsin**




2nd Floor Plan



**Two Family Front Dwelling
2122 North 24th Place
Milwaukee, Wisconsin**



Attic Floor Plan



X. HMG CERTIFICATION

Company Certificate

This certifies that

HARENDA MANAGEMENT GROUP

1237 W BRUCE ST
MILWAUKEE WI 53204-1218

is certified under ch. DHS 159, Wis.Adm.Code as a

Asbestos Company -- Primary

Certificate Issue Date: 07/23/2019
Expiration Date: 08/31/2021, 12:01 a.m.
Certification #: CAP-480540

Wisconsin Department of Health Services
Division of Public Health
Bureau of Environmental and Occupational Health
Asbestos & Lead Section
PO Box 2659
Madison WI 53701-2659
Phone: (608) 261-6876



Miriam Hasan
Miriam Hasan, Unit Supervisor

ASBESTOS INSPECTOR
Issued By
STATE OF WISCONSIN
Dept. of Health Services

Jazmin K C Spears
6866 N 40th Place
Milwaukee WI 53209-2229

| | | | |
|------------|-----------------|------------|--------|
| | | 200 lbs | 5' 08" |
| All-111055 | Exp: 08/10/2020 | 10/19/1974 | |

Training due by: 08/10/2020

COPY



PRE-DEMOLITION INSPECTION REPORT

Job Site:

**Two Family Rear Dwelling
2122 North 24th Place
Milwaukee, Wisconsin**

For:

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613

**HMG Report No.: 20-400-020.2122R
Inspector: Jazmin Spears
Contract No.: 360-20-0975**

Prepared by:


HARENDA MANAGEMENT GROUP
1237 West Bruce Street
Milwaukee, Wisconsin 53204
(414) 383-4800

March 2020

Signature Page
Pre-Demolition Inspection Report
Two Family Rear Dwelling
2122 North 24th Place
Milwaukee, Wisconsin



Dean Jacobsen
Asbestos Inspector No. AII – 14370
Expiration Date: 12/2/20
Harenda Management Group



Jazmin Spears
Asbestos Inspector No. AII – 111055
Expiration Date: 8/10/20
Harenda Management Group

March 24, 2020

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613

RE: Pre-Demolition Inspection Report
2122 North 24th Place Rear Dwelling
Milwaukee, WI

Harenda Management Group has completed the pre-demolition inspection of the two family rear dwelling at 2122 North 24th Place, Milwaukee, Wisconsin, as per the referral from the City of Milwaukee Department of Neighborhood Services. The inspection and results are described in the following report. Please contact me at (414) 383-4800 if you have any questions.

Sincerely,

HARENDA MANAGEMENT GROUP



Dean Jacobsen
Asbestos Inspector No. AII – 14370

EXECUTIVE SUMMARY

Harenda Management Group was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection of the two family rear dwelling at 2122 North 24th Place, Milwaukee, Wisconsin, prior to demolition. HMG conducted a visual inspection for asbestos and universal wastes. HMG collected asbestos bulk samples for laboratory analysis.

Asbestos was not detected in any material sampled during the inspection. Asbestos was assumed to be in the asphalt roofing and in the floor tile and mastic in the dwelling. Results are in Section IV of this report.

TABLE OF CONTENTS
Pre-Demolition Inspection Report

| | | |
|-------|---|----|
| I. | Introduction..... | 1 |
| II. | Asbestos Inspection | 1 |
| III. | Asbestos Laboratory | 2 |
| | A. Method of Analysis | |
| IV. | Asbestos Findings and Observations | 2 |
| V. | Exclusions | 4 |
| VI. | Limitations | 4 |
| VII. | Pre-Demolition Environmental Checklist..... | 5 |
| VIII. | Asbestos Laboratory Results..... | 9 |
| IX. | Floor Plans | 10 |
| X. | HMG Certifications | 11 |

I. INTRODUCTION

Harenda Management Group (HMG) was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection for suspect asbestos containing materials in the two family rear dwelling at 2122 North 24th Place, Milwaukee, Wisconsin. The dwelling is a two story wood framed structure with aluminum and wood walls and asphalt roofing.

II. ASBESTOS INSPECTION

Marge Piwaron, of the City of Milwaukee Department of Neighborhood Services, authorized HMG to conduct a building inspection and to analyze samples collected during the inspection.

On March 12, 2020, HMG conducted an asbestos inspection of a two family rear dwelling, scheduled for mechanical demolition, located at 2122 North 24th Place, Milwaukee, Wisconsin. The inspection was conducted by Jazmin Spears, Wisconsin License No. AII – 111055, and the report was written by Dean Jacobsen, Wisconsin License No. AII – 14370..

The inspection was comprised of these elements:

1. A visual determination as to the extent of suspect asbestos containing materials within the buildings.
2. Sampling and documentation of observable suspect asbestos containing materials.
3. Quantification of observable asbestos containing materials existing within the spaces.

The results of the inspection integrated with the Polarized Light Microscopy with Dispersion Staining (PLM/DS) analysis of asbestos bulk samples collected are outlined in this document.

The following types of suspect materials were observed and inspected to determine if asbestos containing materials were present in the building as required by U.S. EPA NESHAP regulation 40 CFR 61 Subpart M, and NR 447 of the Wisconsin Administrative Code:

- Paper insulation
- Blown in insulation
- Caulk
- Window Glazing Compound
- Plaster
- Ceramic tile
- Linoleum
- Flue packing
- Floor tile
- Asphalt roofing
- Mastics

A listing of specific homogeneous materials and homogeneous material codes are in the Findings and Observations section following the results table.

III. ASBESTOS LABORATORY

A. METHOD OF ANALYSIS

Analysis is performed by using the bulk samples for visual observation and slide preparation(s) for microscopical examination and identification. The slides are analyzed for asbestos (chrysotile, amosite, crocidolite, anthophyllite, and actinolite/tremolite), fibrous non asbestos constituents (mineral wool, paper, etc.), and nonfibrous constituents. Asbestos is identified by refractive indices (obtained by using dispersion staining), morphology, color, pleochroism, birefringence, extinction characteristics, and signs of elongation. The same characteristics are used to identify the non asbestos constituents.

The microscopist visually estimates relative amounts of each constituent using a stereoscope if necessary. The test results are based on a visual determination of relative volume of the bulk sample components. The results are valid only for the item tested. Current federal and Wisconsin regulations state asbestos containing material means material containing more than 1% asbestos as determined using the method specified in Appendix E, Subpart E, 40 CFR Part 763 Section I, Polarized Light Microscopy. Bold values below indicate that the material contains more than 1% asbestos. Refer to 29 CFR 1926.1101 (Construction) and 29 CFR 1910.1001 (General Industry) for specific OSHA requirements.

IV. ASBESTOS FINDINGS AND OBSERVATIONS

The following are the laboratory results. The laboratory report is in Appendix A.

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|---|----------|------------------|
| 1 | Exterior – west wall – under wood siding – tan paper insulation | Negative | MPIt |
| 2 | Exterior – south wall – under wood siding – tan paper insulation | Negative | MPIt |
| 3 | Exterior – east wall – under wood siding – tan paper insulation | Negative | MPIt |
| 4 | Exterior – in west wall – blown in insulation | Negative | MBI |
| 5 | 2 nd floor – kitchen – on floor – blown in insulation | Negative | MBI |
| 6 | Attic – on floor – blown in insulation | Negative | MBI |
| 7 | Exterior – on west window – white caulk | Negative | MCLKw |
| 8 | Exterior – on south window – white caulk | Negative | MCLKw |
| 9 | Exterior – on east window – white caulk | Negative | MCLKw |
| 10 | 1 st floor – living room – on south window – glazing compound | Negative | MPG |
| 11 | 1 st floor – east bedroom – on north window – glazing compound | Negative | MPG |
| 12 | 2 nd floor – north bedroom – on west window – glazing compound | Negative | MPG |
| 13 | 1 st floor – living room – east wall – plaster | Negative | SPI |
| 14 | 1 st floor – bathroom – south wall – plaster | Negative | SPI |
| 15 | 1 st floor – east bedroom – north wall – plaster | Negative | SPI |
| 16 | 1 st floor – middle bedroom – north wall – plaster | Negative | SPI |
| 17 | 2 nd floor – kitchen – east wall – plaster | Negative | SPI |
| 18 | 2 nd floor – middle bedroom – north wall – plaster | Negative | SPI |

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|---|----------|------------------|
| 19 | 2 nd floor – north bedroom – west wall – plaster | Negative | SPI |
| 20a | 1 st floor – bathroom floor – cream ceramic tile | Negative | MCTMc |
| 20b | 1 st floor – bathroom floor – grout | Negative | MCTMc |
| 20c | 1 st floor – bathroom floor – under cream ceramic tile – mortar | Negative | MCTMc |
| 21a | 1 st floor – rear stair – on landing – black linoleum | Negative | MFLk |
| 21b | 1 st floor – rear stair – on landing – under black linoleum – tan mastic | Negative | MFLk |
| 22a | 1 st floor – rear stair – on steps – black linoleum | Negative | MFLk |
| 22b | 1 st floor – rear stair – on steps – under black linoleum – tan mastic | Negative | MFLk |
| 23a | 2 nd floor – rear stair – on landing – black linoleum | Negative | MFLk |
| 23b | 2 nd floor – rear stair – on landing – under black linoleum – tan mastic | Negative | MFLk |
| 24 | Basement – on chimney – flue packing | Negative | TFP |

None of the materials sampled contain greater than 1% asbestos.

Assumed Category I Non-Friable Asbestos Containing Material:

| Material | Location | Approximate Quantity | Material Type |
|-----------------------------|--|----------------------|------------------------|
| Asphalt Shingles & Flashing | House Roof | 900 SF | Category I Non-Friable |
| Floor Tile & Mastic | 1 st & 2 nd Floor Kitchens | 300 SF | Category I Non-Friable |

Note #1: The asphalt roofing and floor tile/mastic in the house are category I non friable asbestos containing materials. Under NR 447 they do not currently meet the definition of regulated asbestos containing material (RACM) and need not be removed before demolition if the demolition debris does not become RACM and will be disposed at a Wisconsin licensed landfill.

Note#2: Category I – Non-Friable Asbestos Containing Materials may become RACM during mechanical demolition activities or maybe considered friable prior to demolition activities due to its condition at time of demolition.

Note#3: If additional materials are discovered during demolition that are not listed above they are to be assumed to be asbestos containing.

Note#4: A copy of this report should be transmitted to the demolition contractor.

Homogeneous Material Codes

| | |
|-------|-------------------------|
| SPI | Plaster |
| MPIt | Tan Paper Insulation |
| MBI | Blown in Insulation |
| MCLKw | White Caulk |
| MPG | Window Glazing Compound |
| MCTMc | Cream Ceramic Tile |
| MFLk | Black Linoleum |
| TFP | Flue Packing |

V. EXCLUSIONS

Not all areas within walls and ceilings were accessible, and these areas may contain suspect asbestos containing materials. Only visible or accessible areas were included in the scope of work.

HMG is not and shall not represent the building owner as its agent or representative for the purpose of the US EPA/NESHAP and/or the WDNR/NR447 regulations, as owner/operator.

This report represents the condition of the building and its visible/accessible suspect asbestos containing materials at the date and the times of the onsite inspection. Hidden materials or inaccessible materials, or those materials that could be present at the point of inspection, over and above those stated in the inspection report, are the responsibility of the building owner and the demolition contractor.

VI. LIMITATIONS

The care and skill given to our procedures insures the most reliable test results possible. HMG utilizes Schneider Laboratories Global, Inc., for our asbestos testing. The findings and conclusions of HMG represent our professional opinions extrapolated from limited data. Significant limited data is gathered during the course of the preliminary asbestos specific site assessment. No other warranty is expressed or implied. Prior to any abatement or renovation activities, it is recommended that HMG be provided the opportunity to review such plans in order that the inspection and assessments contained herein are properly interpreted and implemented.

This report and the information contained herein are prepared for the sole and exclusive use and possession of the City of Milwaukee Department of Neighborhood Services. No other person or entity may rely on this report or any information contained herein. Any dissemination of the Report or any information contained herein is strictly prohibited without prior written authorization from Harenda Management Group.

VII. PRE-DEMOLITION ENVIRONMENTAL CHECKLIST

This guide lists materials and products commonly found in buildings with examples. It is not intended as a substitute for reading the rules and statutes and making your own independent determination of their applicability to your demolition project. These examples presented here do not represent an exhaustive listing of types of materials that may be required to be removed from the building prior to demolition.

ASBESTOS

Persons conducting inspections for asbestos must hold a valid asbestos inspector certification card issued by the State of Wisconsin, Dept. of Health Services. **Please follow the Asbestos Inspection and Sampling Protocol for Buildings to be Demolished or Renovated.**

CFCs and HALONS

Equipment that may contain CFCs and Halons:

| | |
|------------|--|
| <u>N/A</u> | Air Conditioners (roof top, room, and central) |
| <u>N/A</u> | Dehumidifiers |
| <u>N/A</u> | Heat Pumps |
| <u>N/A</u> | Refrigerators, Freezers, Chillers |
| <u>N/A</u> | Vending Machines, Food Display Cases |
| <u>N/A</u> | Walk-in Coolers |
| <u>N/A</u> | Water Fountains (bubblers) |
| <u>N/A</u> | Fire Extinguishers (both portable and installed HALON suppression systems) |
| <u>N/A</u> | Water Coolers |

LEAD

Lead or Lead Based Paint (LBP) is common in many older buildings. When recycling construction and demolition debris, be aware that wood containing lead paint may not be chipped and spread for landscaping. State law also prohibits the sale or transfer of any fixture or other object containing LBP that might be placed upon any surface of a dwelling, which is ordinarily accessible to children.

MERCURY

Products that may contain mercury:

LIGHTING

| | |
|------------|--|
| <u>2</u> | Fluorescent Lights – 1 st Floor East Bedroom, 2 nd Floor Middle Bedroom |
| <u>N/A</u> | High Intensity Discharge -Metal Halide -High Pressure Sodium -Mercury Vapor |
| <u>N/A</u> | Neon |
| <u>N/A</u> | Switches for lighting using mercury relays -Look for any control associated with exterior or automated lighting systems such as "Silent" wall switches. |

HVAC

Check thermostats and any control associated with air handling units for switches containing mercury.

HEATING, VENTILATING AND AIR CONDITIONING SYSTEMS

| | |
|------------|---|
| <u>1</u> | Old Thermostats – 1 st Floor Living Room |
| <u>N/A</u> | Aquastats |
| <u>N/A</u> | Firestats |
| <u>N/A</u> | Manometers |
| <u>N/A</u> | Thermometers |

BOILERS, FURNACES, HEATERS AND TANKS – 2 Furnaces & 1 Water Heater in Basement

| | |
|------------|---------------------------------------|
| <u>N/A</u> | Mercury Flame Sensors by pilot lights |
| <u>N/A</u> | Manometers, Thermometers, Gauges |
| <u>N/A</u> | Pressure-trol |
| <u>N/A</u> | Float or Level Controls |
| <u>N/A</u> | Space Heaters |

ELECTRICAL SYSTEMS

| | |
|------------|-------------------------------|
| <u>N/A</u> | Load Meters and Supply Relays |
| <u>N/A</u> | Phase Splitters |
| <u>N/A</u> | Microwave Relays |
| <u>N/A</u> | Mercury Displacement Relays |

PCBs

For electrical devices manufactured prior to 1987, it is safe to assume that they contain PCBs and should be managed accordingly. Most equipment manufactured after this time will say "PCB Free". The following is a list of areas in a building were PCBs may be found:

| | |
|------------|--|
| <u>N/A</u> | Transformers |
| <u>N/A</u> | Capacitors (appliances, electronic equipment) |
| <u>N/A</u> | Heat Transfer Equipment |
| <u>N/A</u> | Ballasts |
| <u>N/A</u> | Specialty Paints (such as for swimming pools or other industrial applications) |
| <u>N/A</u> | Sumps or Oil Traps (in maintenance and industrial facilities) |

OTHER ENVIRONMENTAL ISSUES

| | |
|------------|------------------------------|
| <u>N/A</u> | Hazardous Waste |
| <u>N/A</u> | Oil Tanks |
| <u>N/A</u> | Well Abandonment |
| <u>2</u> | Junk Auto Tires – Rear Stair |
| <u>N/A</u> | Junk Vehicles |

- * 1 Gas Meter on Exterior
- * 1 Small Propane Tank in 1st Floor Kitchen
- * 1 Gallon Gasoline in Basement

VIII. ASBESTOS LABORATORY RESULTS



Customer: Harenda Management Group (5065)
Address: 1237 West Bruce Street
Milwaukee, WI 53204

| | |
|-----------------|--------|
| Order #: | 365032 |
|-----------------|--------|

Received 03/16/20
Analyzed 03/19/20
Reported 03/23/20

Attn:

Project:

Location: Wisconsin
Number: 20-400-020.2122R

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|-------------------|----------|-----------|-----------------|---------------------------|
| 365032-001 | 03/11/20 | 1 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365032-002 | 03/11/20 | 2 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365032-003 | 03/11/20 | 3 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365032-004 | 03/11/20 | 4 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365032-005 | 03/11/20 | 5 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365032-006 | 03/11/20 | 6 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365032-007 | 03/11/20 | 7 | Wisconsin | | |
| Layer 1: | Granular Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Green, Granular | | | | |
| 365032-008 | 03/11/20 | 8 | Wisconsin | | |
| Layer 1: | Granular Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Green, Granular | | | | |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2122R

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|--------------------------------------|----------|-----------|-----------------|---------------------------|
| 365032-009 | 03/11/20 | 9 | Wisconsin | | |
| Layer 1: | Granular Material Green, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365032-010 | 03/11/20 | 10 | Wisconsin | | |
| Layer 1: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365032-011 | 03/11/20 | 11 | Wisconsin | | |
| Layer 1: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365032-012 | 03/11/20 | 12 | Wisconsin | | |
| Layer 1: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365032-013 | 03/11/20 | 13 | Wisconsin | | |
| Layer 1: | Plaster Beige, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365032-014 | 03/11/20 | 14 | Wisconsin | | |
| Layer 1: | Plaster Beige, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365032-015 | 03/11/20 | 15 | Wisconsin | | |
| Layer 1: | Plaster Beige, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365032-016 | 03/11/20 | 16 | Wisconsin | | |
| Layer 1: | Plaster Beige, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365032-017 | 03/11/20 | 17 | Wisconsin | | |
| Layer 1: | Plaster Beige, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365032-018 | 03/11/20 | 18 | Wisconsin | | |
| Layer 1: | Plaster Beige, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2122R

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-----------|-----------|----------|----------|-----------------|-----------------|
|-----------|-----------|----------|----------|-----------------|-----------------|

EPA Regulatory Limit: 1%

Total layers analyzed on order: 29

365032-03/23/20 10:47 AM



Analyst **Mohammed Hashim**



Reviewed By: **Hind Eldanaf**

Microscopy Manager

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.



365032 X 24

 V:13651365032
 fgbraizi 3/16/2020 9:47:56 AM
 UPS 1Z2E28998462845568

| | | | |
|--|------------------------------|--|--|
| Submitting Co. Harenda Management Group | | State of Collection WI | Cert. Required <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # 5065 | Phone (414) 647-1530 |
| Milwaukee, WI 53204 | | Email dean.jacobsen@kphenvironmenmtal.com | |
| Project Name | | PO # | |
| Project Location Wisconsin | Special Instructions: | | |
| Project Number 20-400-020.2122R | | | |
| Collected By | | | |

| Turn Around Time ** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|---|---|---|--|--|--|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days * not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM | <input type="checkbox"/> Lead | <input type="checkbox"/> Lead | <input type="checkbox"/> BACT (MPN/PA) |
| | | <input type="checkbox"/> PLM Qualitative | <input type="checkbox"/> RCRA 8 Metals | <input type="checkbox"/> RCRA 8 Metals | <input type="checkbox"/> Mold Direct Exam |
| | | <input type="checkbox"/> 400 Point Count | <input type="checkbox"/> Chromium VI | <input type="checkbox"/> Full TCLP (w/ organics 10 Day) | <input type="checkbox"/> Allergens |
| | | <input type="checkbox"/> 1000 Point Count | <input type="checkbox"/> Mercury | | Sub-Contract |
| | | <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> _____ | | <input type="checkbox"/> TEM Chatfield |
| | | Asbestos in Air | Gravimetric | Miscellaneous | <input type="checkbox"/> TEM AHERA |
| | | <input type="checkbox"/> PCM | <input type="checkbox"/> Total Dust NIOSH 0500 | <input type="checkbox"/> Silica FTIR (7602) | <input type="checkbox"/> TEM 7402 |
| | | <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> _____ | <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 1 | 3/11/20 | | | | | | | | |
| 2 | | | | | | | | | |
| 3 | | | | | | | | | |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: Date/Time: 3/13/2020

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com


| | | | | | |
|------------------------|--------------------------|-----------------------|-------------------------------------|----------------|--|
| Submitting Co. | Harenda Management Group | State of Collection | WI | Cert. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmenmtal.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.2122R | | | | |
| Collected By | | | | | |

| Turn Around Time ** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|--|---|--|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests</small> <small>** past 3 PM the TAT will begin next business day</small> <small>Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM | <input type="checkbox"/> Lead | <input type="checkbox"/> Lead | <input type="checkbox"/> BACT (MPN/PA) |
| | | <input type="checkbox"/> PLM Qualitative | <input type="checkbox"/> RCRA 8 Metals | <input type="checkbox"/> RCRA 8 Metals | <input type="checkbox"/> Mold Direct Exam |
| | | <input type="checkbox"/> 400 Point Count | <input type="checkbox"/> Chromium VI | <input type="checkbox"/> Full TCLP | <input type="checkbox"/> Allergens |
| | | <input type="checkbox"/> 1000 Point Count | <input type="checkbox"/> Mercury | (w/ organics 10 Day) | |
| | | <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> _____ | | |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM | <input type="checkbox"/> Total Dust NIOSH 0500 | <input type="checkbox"/> Silica FTIR (7602) | <input type="checkbox"/> TEM Chatfield |
| | | <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> _____ | <input type="checkbox"/> TEM AHERA |
| | | | | | <input type="checkbox"/> TEM 7402 |
| | | | | | <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 11 | 3/11/20 | | | | | | | | |
| 12 | | | | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | | | | | | | | |
| 16 | | | | | | | | | |
| 17 | | | | | | | | | |
| 18 | | | | | | | | | |
| 19 | | | | | | | | | |
| 20 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature:  Date/Time: 3/13/20 (20)

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabin.com • info@slabin.com

| | | | | | |
|------------------------|--------------------------|-----------------------|-------------------------------------|----------------|--|
| Submitting Co. | Harenda Management Group | State of Collection | WI | Cert. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmenmtal.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.2122R | | | | |
| Collected By | | | | | |

| Turn Around Time** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests</small> <small>** past 3 PM the TAT will begin next business day</small> <small>Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 21 | 3/11/20 | | | | | | | | |
| 22 | ↓ | | | | | | | | |
| 23 | ↓ | | | | | | | | |
| 24 | ↓ | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: Date/Time: 3/13/2020


! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !

IX. FLOOR PLANS

**Two Family Rear Dwelling
2122 North 24th Place
Milwaukee, Wisconsin**




Basement Floor Plan



**Two Family Rear Dwelling
2122 North 24th Place
Milwaukee, Wisconsin**




1st Floor Plan



**Two Family Rear Dwelling
2122 North 24th Place
Milwaukee, Wisconsin**




2nd Floor Plan



**Two Family Rear Dwelling
2122 North 24th Place
Milwaukee, Wisconsin**



Attic Floor Plan



X. HMG CERTIFICATION

Company Certificate

This certifies that

HARENDA MANAGEMENT GROUP

1237 W BRUCE ST
MILWAUKEE WI 53204-1218

is certified under ch. DHS 159, Wis.Adm.Code as a

Asbestos Company -- Primary

Certificate Issue Date: 07/23/2019
Expiration Date: 08/31/2021, 12:01 a.m.
Certification #: CAP-480540

Wisconsin Department of Health Services
Division of Public Health
Bureau of Environmental and Occupational Health
Asbestos & Lead Section
PO Box 2659
Madison WI 53701-2659
Phone: (608) 261-6876



Miriam Hasan
Miriam Hasan, Unit Supervisor

ASBESTOS INSPECTOR
Issued By
STATE OF WISCONSIN
Dept. of Health Services

Jazmin K C Spears
6866 N 40th Place
Milwaukee WI 53209-2229

| | | | |
|------------|-----------------|------------|--------|
| | | 200 lbs | 5' 08" |
| All-111055 | Exp: 08/10/2020 | 10/19/1974 | |

Training due by: 08/10/2020

COPY



PRE-DEMOLITION INSPECTION REPORT

Job Site:

**Fire Damaged
One Family Dwelling
2858 North 24th Place
Milwaukee, Wisconsin**

For:

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613

**HMG Report No.: 20-400-020.2858
Inspector: Cecil Trawick
Contract No.: 360-20-0975**

Prepared by:

HARENDA MANAGEMENT GROUP
1237 West Bruce Street
Milwaukee, Wisconsin 53204
(414) 383-4800

March 2020

Signature Page
Pre-Demolition Inspection Report
One Family Dwelling
2858 North 24th Place
Milwaukee, Wisconsin



Dean Jacobsen
Asbestos Inspector No. AII – 14370
Expiration Date: 12/2/20
Harenda Management Group



Cecil Trawick
Asbestos Inspector No. AII – 104769
Expiration Date: 10/2/20
Harenda Management Group

March 24, 2020

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613

RE: Pre-Demolition Inspection Report
2858 North 24th Place
Milwaukee, WI

Harenda Management Group has completed the pre-demolition inspection of the one family dwelling at 2858 North 24th Place, Milwaukee, Wisconsin, as per the referral from the City of Milwaukee Department of Neighborhood Services. The inspection and results are described in the following report. Please contact me at (414) 383-4800 if you have any questions.

Sincerely,

HARENDA MANAGEMENT GROUP



Dean Jacobsen
Asbestos Inspector No. AII – 14370

EXECUTIVE SUMMARY

Harenda Management Group was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection of the one family dwelling at 2858 North 24th Place, Milwaukee, Wisconsin, prior to demolition. HMG conducted a visual inspection for asbestos and universal wastes. HMG collected asbestos bulk samples for laboratory analysis.

Asbestos was not detected in any material sampled during the inspection. Asbestos was assumed to be in the asphalt roofing and in the floor tile and mastic in the dwelling. Results are in Section IV of this report.

TABLE OF CONTENTS
Pre-Demolition Inspection Report

| | | |
|-------|---|----|
| I. | Introduction..... | 1 |
| II. | Asbestos Inspection | 1 |
| III. | Asbestos Laboratory | 2 |
| | A. Method of Analysis | |
| IV. | Asbestos Findings and Observations | 2 |
| V. | Exclusions | 3 |
| VI. | Limitations | 4 |
| VII. | Pre-Demolition Environmental Checklist..... | 5 |
| VIII. | Asbestos Laboratory Results..... | 9 |
| IX. | Floor Plans | 10 |
| X. | HMG Certifications | 11 |

I. INTRODUCTION

Harenda Management Group (HMG) was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection for suspect asbestos containing materials in the one family dwelling at 2858 North 24th Place, Milwaukee, Wisconsin. The dwelling is a two story wood framed structure with basement and has vinyl and wood walls and asphalt roofing.

II. ASBESTOS INSPECTION

Marge Piwaron, of the City of Milwaukee Department of Neighborhood Services, authorized HMG to conduct a building inspection and to analyze samples collected during the inspection.

On March 11, 2020, HMG conducted an asbestos inspection of a one family dwelling, scheduled for mechanical demolition, located at 2858 North 24th Place, Milwaukee, Wisconsin. The inspection was conducted by Cecil Trawick, Wisconsin License No. AII – 104769, and the report was written by Dean Jacobsen, Wisconsin License No. AII – 14370..

The inspection was comprised of these elements:

1. A visual determination as to the extent of suspect asbestos containing materials within the building.
2. Sampling and documentation of observable suspect asbestos containing materials.
3. Quantification of observable asbestos containing materials existing within the spaces.

The results of the inspection integrated with the Polarized Light Microscopy with Dispersion Staining (PLM/DS) analysis of asbestos bulk samples collected are outlined in this document.

The following types of suspect materials were observed and inspected to determine if asbestos containing materials were present in the building as required by U.S. EPA NESHAP regulation 40 CFR 61 Subpart M, and NR 447 of the Wisconsin Administrative Code:

- Paper insulation
- Plaster
- Blown in insulation
- Drywall
- Ceramic tile
- Floor tile
- Asphalt roofing
- Mastics

A listing of specific homogeneous materials and homogeneous material codes are in the Findings and Observations section following the results table.

III. ASBESTOS LABORATORY

A. METHOD OF ANALYSIS

Analysis is performed by using the bulk samples for visual observation and slide preparation(s) for microscopical examination and identification. The slides are analyzed for asbestos (chrysotile, amosite, crocidolite, anthophyllite, and actinolite/tremolite), fibrous non asbestos constituents (mineral wool, paper, etc.), and nonfibrous constituents. Asbestos is identified by refractive indices (obtained by using dispersion staining), morphology, color, pleochroism, birefringence, extinction characteristics, and signs of elongation. The same characteristics are used to identify the non asbestos constituents.

The microscopist visually estimates relative amounts of each constituent using a stereoscope if necessary. The test results are based on a visual determination of relative volume of the bulk sample components. The results are valid only for the item tested. Current federal and Wisconsin regulations state asbestos containing material means material containing more than 1% asbestos as determined using the method specified in Appendix E, Subpart E, 40 CFR Part 763 Section I, Polarized Light Microscopy. Bold values below indicate that the material contains more than 1% asbestos. Refer to 29 CFR 1926.1101 (Construction) and 29 CFR 1910.1001 (General Industry) for specific OSHA requirements.

IV. ASBESTOS FINDINGS AND OBSERVATIONS

The following are the laboratory results. The laboratory report is in Appendix A.

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|--|----------|------------------|
| 1 | 1 st floor – living room – on floor – blown in insulation | Negative | MBI |
| 2 | 1 st floor – dining room – in south wall – blown in insulation | Negative | MBI |
| 3 | 1 st floor – kitchen – in north wall – blown in insulation | Negative | MBI |
| 4 | 1 st floor – kitchen – southwest wall – drywall | Negative | MDW |
| 5 | 1 st floor – kitchen – southeast wall – drywall | Negative | MDW |
| 6 | 1 st floor – kitchen – ceiling – drywall | Negative | MDW |
| 7a | 1 st floor – kitchen – east side floor – white ceramic tile | Negative | MCTMw |
| 7b | 1 st floor – kitchen – east side floor – under white ceramic tile – mortar | Negative | MCTMw |
| 8a | 1 st floor – kitchen – south side floor – white ceramic tile | Negative | MCTMw |
| 8b | 1 st floor – kitchen – south side floor – under white ceramic tile – mortar | Negative | MCTMw |
| 9a | 1 st floor – kitchen – west side floor – white ceramic tile | Negative | MCTMw |
| 9b | 1 st floor – kitchen – west side floor – under white ceramic tile – mortar | Negative | MCTMw |
| 10 | Exterior – west wall – under wood siding – black paper insulation | Negative | MPIk |
| 11 | Exterior – north wall – under wood siding – black paper insulation | Negative | MPIk |
| 12 | Exterior – east wall – under wood siding – black paper insulation | Negative | MPIk |
| 13 | 1 st floor – front entry – south wall – plaster | Negative | SPI |
| 14 | 1 st floor – foyer – south wall – plaster | Negative | SPI |
| 15 | 1 st floor – living room – south wall – plaster | Negative | SPI |

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|--|----------|------------------|
| 16 | 1 st floor – hall – north wall – plaster | Negative | SPI |
| 17 | 1 st floor – kitchen – north wall – plaster | Negative | SPI |

None of the materials sampled contain asbestos.

Assumed Category I Non-Friable Asbestos Containing Material:

| Material | Location | Approximate Quantity | Material Type |
|-----------------------------|--|----------------------|------------------------|
| Asphalt Shingles & Flashing | House Roof | 950 SF | Category I Non-Friable |
| Floor Tile & Mastic | 1 st Floor Front Entry/Hall | 70 SF | Category I Non-Friable |

Note #1: The asphalt roofing and floor tile/mastic are category I non friable asbestos containing materials. Under NR 447 they do not currently meet the definition of regulated asbestos containing material (RACM) and need not be removed before demolition if the demolition debris does not become RACM and will be disposed at a Wisconsin licensed landfill.

Note#2: Category I – Non-Friable Asbestos Containing Materials may become RACM during mechanical demolition activities or maybe considered friable prior to demolition activities due to its condition at time of demolition.

Note#3: If additional materials are discovered during demolition that are not listed above they are to be assumed to be asbestos containing.

Note#4: A copy of this report should be transmitted to the demolition contractor.

Homogeneous Material Codes

| | |
|-------|------------------------|
| SPI | Plaster |
| MPIk | Black Paper Insulation |
| MBI | Blown in Insulation |
| MDW | Drywall |
| MCTMw | White Ceramic Tile |

V. EXCLUSIONS

Dwelling is fire damaged – surfaces in rooms only partially accessible. No access to 2nd floor or attic. Not all areas within walls and ceilings were accessible, and these areas may contain suspect asbestos containing materials. Only visible or accessible areas were included in the scope of work.

HMG is not and shall not represent the building owner as its agent or representative for the purpose of the US EPA/NESHAP and/or the WDNR/NR447 regulations, as owner/operator.

This report represents the condition of the building and its visible/accessible suspect asbestos containing materials at the date and the times of the onsite inspection. Hidden materials or inaccessible materials, or those materials that could be present at the point of inspection, over and above those stated in the inspection report, are the responsibility of the building owner and the demolition contractor.

VI. LIMITATIONS

The care and skill given to our procedures insures the most reliable test results possible. HMG utilizes Schneider Laboratories Global, Inc., for our asbestos testing. The findings and conclusions of HMG represent our professional opinions extrapolated from limited data. Significant limited data is gathered during the course of the preliminary asbestos specific site assessment. No other warranty is expressed or implied. Prior to any abatement or renovation activities, it is recommended that HMG be provided the opportunity to review such plans in order that the inspection and assessments contained herein are properly interpreted and implemented.

This report and the information contained herein are prepared for the sole and exclusive use and possession of the City of Milwaukee Department of Neighborhood Services. No other person or entity may rely on this report or any information contained herein. Any dissemination of the Report or any information contained herein is strictly prohibited without prior written authorization from Harenda Management Group.

VII. PRE-DEMOLITION ENVIRONMENTAL CHECKLIST

This guide lists materials and products commonly found in buildings with examples. It is not intended as a substitute for reading the rules and statutes and making your own independent determination of their applicability to your demolition project. These examples presented here do not represent an exhaustive listing of types of materials that may be required to be removed from the building prior to demolition.

ASBESTOS

Persons conducting inspections for asbestos must hold a valid asbestos inspector certification card issued by the State of Wisconsin, Dept. of Health Services. **Please follow the Asbestos Inspection and Sampling Protocol for Buildings to be Demolished or Renovated.**

CFCs and HALONS

Equipment that may contain CFCs and Halons:

| | |
|------------|--|
| <u>N/A</u> | Air Conditioners (roof top, room, and central) |
| <u>N/A</u> | Dehumidifiers |
| <u>N/A</u> | Heat Pumps |
| <u>N/A</u> | Refrigerators, Freezers, Chillers |
| <u>N/A</u> | Vending Machines, Food Display Cases |
| <u>N/A</u> | Walk-in Coolers |
| <u>N/A</u> | Water Fountains (bubblers) |
| <u>N/A</u> | Fire Extinguishers (both portable and installed HALON suppression systems) |
| <u>N/A</u> | Water Coolers |

LEAD

Lead or Lead Based Paint (LBP) is common in many older buildings. When recycling construction and demolition debris, be aware that wood containing lead paint may not be chipped and spread for landscaping. State law also prohibits the sale or transfer of any fixture or other object containing LBP that might be placed upon any surface of a dwelling, which is ordinarily accessible to children.

MERCURY

Products that may contain mercury:

LIGHTING

| | |
|------------|--|
| <u>N/A</u> | Fluorescent Lights |
| <u>N/A</u> | High Intensity Discharge -Metal Halide -High Pressure Sodium -Mercury Vapor |
| <u>N/A</u> | Neon |
| <u>N/A</u> | Switches for lighting using mercury relays -Look for any control associated with exterior or automated lighting systems such as "Silent" wall switches. |

HVAC

Check thermostats and any control associated with air handling units for switches containing mercury.

HEATING, VENTILATING AND AIR CONDITIONING SYSTEMS

| | |
|------------|-----------------|
| <u>N/A</u> | Old Thermostats |
| <u>N/A</u> | Aquastats |
| <u>N/A</u> | Firestats |
| <u>N/A</u> | Manometers |
| <u>N/A</u> | Thermometers |

BOILERS, FURNACES, HEATERS AND TANKS

| | |
|------------|---------------------------------------|
| <u>N/A</u> | Mercury Flame Sensors by pilot lights |
| <u>N/A</u> | Manometers, Thermometers, Gauges |
| <u>N/A</u> | Pressure-trol |
| <u>N/A</u> | Float or Level Controls |
| <u>N/A</u> | Space Heaters |

ELECTRICAL SYSTEMS

| | |
|------------|-------------------------------|
| <u>N/A</u> | Load Meters and Supply Relays |
| <u>N/A</u> | Phase Splitters |
| <u>N/A</u> | Microwave Relays |
| <u>N/A</u> | Mercury Displacement Relays |

PCBs

For electrical devices manufactured prior to 1987, it is safe to assume that they contain PCBs and should be managed accordingly. Most equipment manufactured after this time will say "PCB Free". The following is a list of areas in a building were PCBs may be found:

| | |
|------------|--|
| <u>N/A</u> | Transformers |
| <u>N/A</u> | Capacitors (appliances, electronic equipment) |
| <u>N/A</u> | Heat Transfer Equipment |
| <u>N/A</u> | Ballasts |
| <u>N/A</u> | Specialty Paints (such as for swimming pools or other industrial applications) |
| <u>N/A</u> | Sumps or Oil Traps (in maintenance and industrial facilities) |

OTHER ENVIRONMENTAL ISSUES

| | |
|------------|------------------|
| <u>N/A</u> | Hazardous Waste |
| <u>N/A</u> | Oil Tanks |
| <u>N/A</u> | Well Abandonment |
| <u>N/A</u> | Junk Auto Tires |
| <u>N/A</u> | Junk Vehicles |

* 1 Gas Meter on Exterior

VIII. ASBESTOS LABORATORY RESULTS



Customer: Harenda Management Group (5065)
Address: 1237 West Bruce Street
Milwaukee, WI 53204

| | |
|-----------------|--------|
| Order #: | 365031 |
|-----------------|--------|

Received 03/16/20
Analyzed 03/20/20
Reported 03/23/20

Attn:

Project:

Location: Wisconsin
Number: 20-400-020.2858

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|----------------|----------|-----------|-----------------|---------------------------|
| 365031-001 | 03/11/20 | 1 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365031-002 | 03/11/20 | 2 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365031-003 | 03/11/20 | 3 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365031-004 | 03/11/20 | 4 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |
| 365031-005 | 03/11/20 | 5 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |
| 365031-006 | 03/11/20 | 6 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |
| 365031-007 | 03/11/20 | 7 | Wisconsin | | |
| Layer 1: | Tile | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Brown, Hard | | | | |
| Layer 2: | Hard Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray, Hard | | | | |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2858

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|----------------------|----------|-----------|-----------------|---------------------------|
| 365031-008 | 03/11/20 | 8 | Wisconsin | | |
| Layer 1: | Tile | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Brown, Hard | | | | |
| Layer 2: | Hard Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Brown, Hard | | | | |
| 365031-009 | 03/11/20 | 9 | Wisconsin | | |
| Layer 1: | Tile | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Brown, Hard | | | | |
| Layer 2: | Hard Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray, Hard | | | | |
| 365031-010 | 03/11/20 | 10 | Wisconsin | | |
| Layer 1: | Felt | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365031-011 | 03/11/20 | 11 | Wisconsin | | |
| Layer 1: | Felt | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365031-012 | 03/11/20 | 12 | Wisconsin | | |
| Layer 1: | Felt | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365031-013 | 03/11/20 | 13 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray/Black, Granular | | | | |
| 365031-014 | 03/11/20 | 14 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray, Granular | | | | |
| 365031-015 | 03/11/20 | 15 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray, Granular | | | | |
| 365031-016 | 03/11/20 | 16 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray, Granular | | | | |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.2858

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|------------------------------------|-----------|----------|-----------|-----------------|---------------------------|
| 365031-017 | 03/11/20 | 17 | Wisconsin | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 1: Plaster Gray, Granular | | | | | |

EPA Regulatory Limit: 1%
Total layers analyzed on order: 20

365031-03/23/20 10:20 AM



Reviewed By: **Hind Eldanaf**
Microscopy Manager


Analyst **Mohammed Hashim**

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabin.com • info@slabin.com

365031

X 17



V:\365\365031

fghraizi
UPS

3/16/2020 9:47:56 AM
1Z2E28998462845568

| | | | |
|--|-----------------|--|--|
| Submitting Co. Harendra Management Group | | State of Collection WI | Cell Required <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct.# 5065 | Phone (414) 647-1530 |
| Milwaukee, WI 53204 | | Email dean.jacobsen@kphenvironmental.com | |
| Project Name | | PO # | |
| Project Location | Wisconsin | Special Instructions: | |
| Project Number | 20-400-020.2858 | | |
| Collected By | | | |

| Turn Around Time ** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|--|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 1 | 3/11/20 | | | | | | | | |
| 2 | | | | | | | | | |
| 3 | | | | | | | | | |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: Date/Time: 3/13/2020

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabin.com • info@slabin.com

| | | | | | |
|-------------------------|--------------------------|------------------------------|------------------------------------|-----------------------|--|
| Submitting Co. | Harenda Management Group | State of Collection | WI | Cert. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmental.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.2858 | | | | |
| Collected By | | | | | |

| Turn Around Time ** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|--|---|--|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests</small> <small>** past 3 PM the TAT will begin next business day</small> <small>Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM | <input type="checkbox"/> Lead | <input type="checkbox"/> Lead | <input type="checkbox"/> BACT (MPN/PA) |
| | | <input type="checkbox"/> PLM Qualitative | <input type="checkbox"/> RCRA 8 Metals | <input type="checkbox"/> RCRA 8 Metals | <input type="checkbox"/> Mold Direct Exam |
| | | <input type="checkbox"/> 400 Point Count | <input type="checkbox"/> Chromium VI | <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> Allergens |
| | | <input type="checkbox"/> 1000 Point Count | <input type="checkbox"/> Mercury | | Sub-Contract |
| | | <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> _____ | | <input type="checkbox"/> TEM Chatfield |
| | | Asbestos in Air | Gravimetric | Miscellaneous | <input type="checkbox"/> TEM AHERA |
| | | <input type="checkbox"/> PCM | <input type="checkbox"/> Total Dust NIOSH 0500 | <input type="checkbox"/> Silica FTIR (7602) | <input type="checkbox"/> TEM 7402 |
| | | <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> _____ | <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 11 | 3/11/20 | | | | | | | | |
| 12 | | | | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | | | | | | | | |
| 16 | | | | | | | | | |
| 17 | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: Date/Time: 3/13/2017


! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !

IX. FLOOR PLANS

**One Family Dwelling
2858 North 24th Place
Milwaukee, Wisconsin**



1st Floor Plan



X. HMG CERTIFICATION

Company Certificate

This certifies that

HARENDA MANAGEMENT GROUP

1237 W BRUCE ST
MILWAUKEE WI 53204-1218

is certified under ch. DHS 159, Wis.Adm.Code as a

Asbestos Company -- Primary

Certificate Issue Date: 07/23/2019
Expiration Date: 08/31/2021, 12:01 a.m.
Certification #: CAP-480540

Wisconsin Department of Health Services
Division of Public Health
Bureau of Environmental and Occupational Health
Asbestos & Lead Section
PO Box 2659
Madison WI 53701-2659
Phone: (608) 261-6876



Miriam Hasan
Miriam Hasan, Unit Supervisor





ASBESTOS INSPECTOR

Issued By

STATE OF WISCONSIN

Dept. of Health Services

Cecil James Trawick Jr

5624 N 97th Street

Milwaukee WI 53227 2502

| | | | |
|------------|-----------------|------------|--------|
| | | 222 lbs | 5' 08" |
| All-104769 | Exp: 10/02/2020 | 07/09/1971 | |

Training due by: 10/02/2020

COPY



PRE-DEMOLITION INSPECTION REPORT

Job Site:

**Fire Damaged
Two Family Dwelling
219-221 North 33rd Street
Milwaukee, Wisconsin**

For:

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613


**HMG Report No.: 20-400-020.219-21
Inspector: Cecil Trawick
Contract No.: 360-20-0975**

Prepared by:

HARENDA MANAGEMENT GROUP
1237 West Bruce Street
Milwaukee, Wisconsin 53204
(414) 383-4800

March 2020

Signature Page
Pre-Demolition Inspection Report
Two Family Dwelling
219-221 North 33rd Street
Milwaukee, Wisconsin



Dean Jacobsen
Asbestos Inspector No. AII – 14370
Expiration Date: 12/2/20
Harenda Management Group



Cecil Trawick
Asbestos Inspector No. AII – 104769
Expiration Date: 10/2/20
Harenda Management Group

March 25, 2020

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613

RE: Pre-Demolition Inspection Report
219-221 North 33rd Street
Milwaukee, WI

Harenda Management Group has completed the pre-demolition inspection of the two family dwelling and garage at 219-221 North 33rd Street, Milwaukee, Wisconsin, as per the referral from the City of Milwaukee Department of Neighborhood Services. The inspection and results are described in the following report. Please contact me at (414) 383-4800 if you have any questions.

Sincerely,

HARENDA MANAGEMENT GROUP



Dean Jacobsen
Asbestos Inspector No. AII – 14370

EXECUTIVE SUMMARY

Harenda Management Group was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection of the two family dwelling and garage at 219-221 North 33rd Street, Milwaukee, Wisconsin, prior to demolition. HMG conducted a visual inspection for asbestos and universal wastes. HMG collected asbestos bulk samples for laboratory analysis.

Asbestos was not detected in any material sampled during the inspection. Asbestos was assumed to be in the asphalt roofing on the dwelling and garage. Results are in Section IV of this report.

TABLE OF CONTENTS
Pre-Demolition Inspection Report

| | | |
|-------|---|----|
| I. | Introduction..... | 1 |
| II. | Asbestos Inspection | 1 |
| III. | Asbestos Laboratory | 2 |
| | A. Method of Analysis | |
| IV. | Asbestos Findings and Observations | 2 |
| V. | Exclusions | 4 |
| VI. | Limitations | 4 |
| VII. | Pre-Demolition Environmental Checklist..... | 6 |
| VIII. | Asbestos Laboratory Results..... | 10 |
| IX. | Floor Plans | 11 |
| X. | HMG Certifications | 12 |

I. INTRODUCTION

Harenda Management Group (HMG) was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection for suspect asbestos containing materials in the two family dwelling and garage at 219-221 North 33rd Street, Milwaukee, Wisconsin. The dwelling is a two story wood framed structure with basement and has vinyl, asphalt, and wood walls with asphalt roofing.

II. ASBESTOS INSPECTION

Marge Piwaron, of the City of Milwaukee Department of Neighborhood Services, authorized HMG to conduct a building inspection and to analyze samples collected during the inspection.

On March 12, 2020, HMG conducted an asbestos inspection of a two family dwelling and garage, scheduled for mechanical demolition, located at 219-221 North 33rd Street, Milwaukee, Wisconsin. The inspection was conducted by Cecil Trawick, Wisconsin License No. AII – 104769, and the report was written by Dean Jacobsen, Wisconsin License No. AII – 14370.

The inspection was comprised of these elements:

1. A visual determination as to the extent of suspect asbestos containing materials within the buildings.
2. Sampling and documentation of observable suspect asbestos containing materials.
3. Quantification of observable asbestos containing materials existing within the spaces.

The results of the inspection integrated with the Polarized Light Microscopy with Dispersion Staining (PLM/DS) analysis of asbestos bulk samples collected are outlined in this document.

The following types of suspect materials were observed and inspected to determine if asbestos containing materials were present in the building as required by U.S. EPA NESHAP regulation 40 CFR 61 Subpart M, and NR 447 of the Wisconsin Administrative Code:

- Asphalt shingle siding
- Tar paper
- Paper insulation
- Fiberboard
- Linoleum
- Drywall
- Ceramic tile
- Ceiling tile
- Blown in insulation
- Asphalt roofing
- Mastics

A listing of specific homogeneous materials and homogeneous material codes are in the Findings and Observations section following the results table.

III. ASBESTOS LABORATORY

A. METHOD OF ANALYSIS

Analysis is performed by using the bulk samples for visual observation and slide preparation(s) for microscopical examination and identification. The slides are analyzed for asbestos (chrysotile, amosite, crocidolite, anthophyllite, and actinolite/tremolite), fibrous non asbestos constituents (mineral wool, paper, etc.), and nonfibrous constituents. Asbestos is identified by refractive indices (obtained by using dispersion staining), morphology, color, pleochroism, birefringence, extinction characteristics, and signs of elongation. The same characteristics are used to identify the non asbestos constituents.

The microscopist visually estimates relative amounts of each constituent using a stereoscope if necessary. The test results are based on a visual determination of relative volume of the bulk sample components. The results are valid only for the item tested. Current federal and Wisconsin regulations state asbestos containing material means material containing more than 1% asbestos as determined using the method specified in Appendix E, Subpart E, 40 CFR Part 763 Section I, Polarized Light Microscopy. Bold values below indicate that the material contains more than 1% asbestos. Refer to 29 CFR 1926.1101 (Construction) and 29 CFR 1910.1001 (General Industry) for specific OSHA requirements.

IV. ASBESTOS FINDINGS AND OBSERVATIONS

The following are the laboratory results. The laboratory report is in Section VIII.

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|---|----------|------------------|
| 1a | Exterior – east wall under vinyl siding – asphalt shingle siding | Negative | MSS |
| 1b | Exterior – east wall under asphalt shingle siding – tar paper | Negative | MPT |
| 1c | Exterior – east wall under tar paper – fiberboard | Negative | MFB |
| 2a | Exterior – south wall under vinyl siding – asphalt shingle siding | Negative | MSS |
| 2b | Exterior – south wall under asphalt shingle siding – tar paper | Negative | MPT |
| 2c | Exterior – south wall under tar paper – fiberboard | Negative | MFB |
| 3a | Exterior – west wall under tar paper – fiberboard | Negative | MSS |
| 3b | Exterior – west wall under asphalt shingle siding – tar paper | Negative | MPT |
| 3c | Exterior – west wall under tar paper – fiberboard | Negative | MFB |
| 4 | Exterior – east wall under wood siding – brown paper insulation | Negative | MPIIn |
| 5 | Exterior – south wall under wood siding – brown paper insulation | Negative | MPIIn |
| 6 | Exterior – west wall under wood siding – brown paper insulation | Negative | MPIIn |
| 7 | 1 st floor – front entry – tan linoleum | Negative | MFLt |
| 8 | 1 st floor – front entry – north wall – drywall | Negative | MDW |

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|--|----------|------------------|
| 9 | 1 st floor – living room – south wall – drywall | Negative | MDW |
| 10 | 2 nd floor – hall – north wall – drywall | Negative | MDW |
| 11a | 1 st floor – kitchen – west side – brown linoleum | Negative | MFLn |
| 11b | 1 st floor – kitchen – west side – under brown linoleum – tan mastic | Negative | MFLn |
| 12a | 1 st floor – kitchen – east side – brown linoleum | Negative | MFLn |
| 12b | 1 st floor – kitchen – east side – under brown linoleum – tan mastic | Negative | MFLn |
| 13a | 1 st floor – bathroom – brown linoleum | Negative | MFLn |
| 13b | 1 st floor – bathroom – under brown linoleum – tan mastic | Negative | MFLn |
| 14a | 1 st floor – bathroom – on north wall – white ceramic tile | Negative | MCTMw |
| 14b | 1 st floor – bathroom – on north wall – under white ceramic tile – white mastic | Negative | MCTMw |
| 15 | Basement – center – 1' x 1' ceiling tile | Negative | MSCT11 |
| 16 | Basement – southeast – 1' x 1' ceiling tile | Negative | MSCT11 |
| 17 | Basement – northeast – 1' x 1' ceiling tile | Negative | MSCT11 |
| 18a | 2 nd floor – kitchen – on west wall – tan ceramic tile | Negative | MCTMt |
| 18b | 2 nd floor – kitchen – on west wall – under tan ceramic tile – white mastic | Negative | MCTMt |
| 19a | 2 nd floor – kitchen floor – west side – brown ceramic tile | Negative | MCTMn |
| 19b | 2 nd floor – kitchen floor – west side – grout | Negative | MCTMn |
| 20a | 2 nd floor – kitchen floor – east side – brown ceramic tile | Negative | MCTMn |
| 20b | 2 nd floor – kitchen floor – east side – grout | Negative | MCTMn |
| 21a | 2 nd floor – hall floor – brown ceramic tile | Negative | MCTMn |
| 21b | 2 nd floor – hall floor – grout | Negative | MCTMn |
| 21c | 2 nd floor – hall floor – under brown ceramic tile – tan mastic | Negative | MCTMn |
| 22a | 2 nd floor – bathroom – on east wall – gray ceramic tile | Negative | MCTMy |
| 22b | 2 nd floor – bathroom – on east wall – grout | Negative | MCTMy |
| 22c | 2 nd floor – bathroom – on east wall – under gray ceramic tile – tan mastic | Negative | MCTMy |
| 23a | 2 nd floor – bathroom – on west wall – gray ceramic tile | Negative | MCTMy |
| 23b | 2 nd floor – bathroom – on west wall – grout | Negative | MCTMy |
| 23c | 2 nd floor – bathroom – on west wall – under gray ceramic tile – tan mastic | Negative | MCTMy |
| 24 | 2 nd floor – bathroom – on north wall – gray ceramic tile | Negative | MCTMy |
| 25 | 2 nd floor – kitchen – in ceiling – blown in insulation | Negative | MBI |
| 26 | 2 nd floor – living room – in ceiling – blown in insulation | Negative | MBI |
| 27 | 2 nd floor – east bedroom – in ceiling – blown in insulation | Negative | MBI |
| 28a | 2 nd floor – front stair – on steps – cream linoleum | Negative | MFLc |
| 28b | 2 nd floor – front stair – on steps – under cream linoleum – tan mastic | Negative | MFLc |

None of the materials sampled contains asbestos.

Assumed Category I Non-Friable Asbestos Containing Material:

| Material | Location | Approximate Quantity | Material Type |
|-----------------------------|----------------------|----------------------|------------------------|
| Asphalt Shingles & Flashing | House & Garage Roofs | 1,800 SF | Category I Non-Friable |

Note #1: The asphalt roofing is a category I non friable asbestos containing material. Under NR 447 it does not currently meet the definition of regulated asbestos containing material (RACM) and

need not be removed before demolition if the demolition debris does not become RACM and will be disposed at a Wisconsin licensed landfill.

Note#2: Category I – Non-Friable Asbestos Containing Materials may become RACM during mechanical demolition activities or maybe considered friable prior to demolition activities due to its condition at time of demolition.

Note#3: If additional materials are discovered during demolition that are not listed above they are to be assumed to be asbestos containing.

Note#4: A copy of this report should be transmitted to the demolition contractor.

Homogeneous Material Codes

| | |
|--------|------------------------|
| MSS | Asphalt Shingle Siding |
| MPT | Tar Paper |
| MFB | Fiberboard |
| MPIIn | Brown Paper Insulation |
| MFLt | Tan Linoleum |
| MFLn | Brown Linoleum |
| MFLc | Cream Linoleum |
| MDW | Drywall |
| MCTMw | White Ceramic Tile |
| MCTMt | Tan Ceramic Tile |
| MCTMn | Brown Ceramic Tile |
| MCTMy | Gray Ceramic Tile |
| MSCT11 | 1' x 1' Ceiling Tile |
| MBI | Blown in Insulation |

V. EXCLUSIONS

Dwelling is fire damaged – surfaces in rooms only partially accessible. Not all areas within walls and ceilings were accessible, and these areas may contain suspect asbestos containing materials. Only visible or accessible areas were included in the scope of work.

HMG is not and shall not represent the building owner as its agent or representative for the purpose of the US EPA/NESHAP and/or the WDNR/NR447 regulations, as owner/operator.

This report represents the condition of the building and its visible/accessible suspect asbestos containing materials at the date and the times of the onsite inspection. Hidden materials or inaccessible materials, or those materials that could be present at the point of inspection, over and above those stated in the inspection report, are the responsibility of the building owner and the demolition contractor.

VI. LIMITATIONS

The care and skill given to our procedures insures the most reliable test results possible. HMG utilizes Schneider Laboratories Global, Inc., for our asbestos testing. The findings and conclusions of HMG represent our professional opinions extrapolated from limited data. Significant limited data is gathered during the course of the preliminary asbestos specific site assessment. No other warranty is expressed or implied. Prior to any abatement or renovation activities, it is recommended that HMG be provided the opportunity to review such plans in

order that the inspection and assessments contained herein are properly interpreted and implemented.

This report and the information contained herein are prepared for the sole and exclusive use and possession of the City of Milwaukee Department of Neighborhood Services. No other person or entity may rely on this report or any information contained herein. Any dissemination of the Report or any information contained herein is strictly prohibited without prior written authorization from Harenda Management Group.

VII. PRE-DEMOLITION ENVIRONMENTAL CHECKLIST

This guide lists materials and products commonly found in buildings with examples. It is not intended as a substitute for reading the rules and statutes and making your own independent determination of their applicability to your demolition project. These examples presented here do not represent an exhaustive listing of types of materials that may be required to be removed from the building prior to demolition.

ASBESTOS

Persons conducting inspections for asbestos must hold a valid asbestos inspector certification card issued by the State of Wisconsin, Dept. of Health Services. **Please follow the Asbestos Inspection and Sampling Protocol for Buildings to be Demolished or Renovated.**

CFCs and HALONS

Equipment that may contain CFCs and Halons:

| | |
|------------|--|
| <u>N/A</u> | Air Conditioners (roof top, room, and central) |
| <u>N/A</u> | Dehumidifiers |
| <u>N/A</u> | Heat Pumps |
| <u>1</u> | Refrigerators , Freezers, Chillers – 2 nd Floor Kitchen |
| <u>N/A</u> | Vending Machines, Food Display Cases |
| <u>N/A</u> | Walk-in Coolers |
| <u>N/A</u> | Water Fountains (bubblers) |
| <u>N/A</u> | Fire Extinguishers (both portable and installed HALON suppression systems) |
| <u>N/A</u> | Water Coolers |

LEAD

Lead or Lead Based Paint (LBP) is common in many older buildings. When recycling construction and demolition debris, be aware that wood containing lead paint may not be chipped and spread for landscaping. State law also prohibits the sale or transfer of any fixture or other object containing LBP that might be placed upon any surface of a dwelling, which is ordinarily accessible to children.

MERCURY

Products that may contain mercury:

LIGHTING

| | |
|------------|--|
| <u>N/A</u> | Fluorescent Lights |
| <u>N/A</u> | High Intensity Discharge -Metal Halide -High Pressure Sodium -Mercury Vapor |
| <u>N/A</u> | Neon |
| <u>N/A</u> | Switches for lighting using mercury relays -Look for any control associated with exterior or automated lighting systems such as "Silent" wall switches. |

HVAC

Check thermostats and any control associated with air handling units for switches containing mercury.

HEATING, VENTILATING AND AIR CONDITIONING SYSTEMS

| | |
|------------|-----------------|
| <u>N/A</u> | Old Thermostats |
| <u>N/A</u> | Aquastats |
| <u>N/A</u> | Firestats |
| <u>N/A</u> | Manometers |
| <u>N/A</u> | Thermometers |

BOILERS, FURNACES, HEATERS AND TANKS – 2 Water Heaters in Basement

| | |
|------------|---------------------------------------|
| <u>N/A</u> | Mercury Flame Sensors by pilot lights |
| <u>N/A</u> | Manometers, Thermometers, Gauges |
| <u>N/A</u> | Pressure-trol |
| <u>N/A</u> | Float or Level Controls |
| <u>N/A</u> | Space Heaters |

ELECTRICAL SYSTEMS – 2 Electrical Boxes in Basement

| | |
|------------|-------------------------------|
| <u>N/A</u> | Load Meters and Supply Relays |
| <u>N/A</u> | Phase Splitters |
| <u>N/A</u> | Microwave Relays |
| <u>N/A</u> | Mercury Displacement Relays |

PCBs

For electrical devices manufactured prior to 1987, it is safe to assume that they contain PCBs and should be managed accordingly. Most equipment manufactured after this time will say "PCB Free". The following is a list of areas in a building were PCBs may be found:

| | |
|------------|--|
| <u>N/A</u> | Transformers |
| <u>N/A</u> | Capacitors (appliances, electronic equipment) |
| <u>N/A</u> | Heat Transfer Equipment |
| <u>N/A</u> | Ballasts |
| <u>N/A</u> | Specialty Paints (such as for swimming pools or other industrial applications) |
| <u>N/A</u> | Sumps or Oil Traps (in maintenance and industrial facilities) |

OTHER ENVIRONMENTAL ISSUES

| | |
|------------|------------------|
| <u>N/A</u> | Hazardous Waste |
| <u>N/A</u> | Oil Tanks |
| <u>N/A</u> | Well Abandonment |
| <u>N/A</u> | Junk Auto Tires |
| <u>N/A</u> | Junk Vehicles |

VIII. ASBESTOS LABORATORY RESULTS



Customer: Harenda Management Group (5065)
Address: 1237 West Bruce Street
Milwaukee, WI 53204

| | |
|-----------------|--------|
| Order #: | 365030 |
|-----------------|--------|

Received 03/16/20
Analyzed 03/20/20
Reported 03/23/20

Attn:

Project:

Location: Wisconsin
Number: 20-400-020.219-21

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|--|----------------------------|----------|-----------|-----------------|--------------------------|
| 365030-001 | 03/11/20 | 1 | Wisconsin | | |
| Layer 1: | Shingle | | | None Detected | 5% CELLULOSE FIBER |
| | Black, Bituminous/Granular | | | | 5% MINERAL/GLASS WOOL |
| | | | | | 90% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| Layer 2: | Felt | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| Layer 3: | Fibrous Material | | | None Detected | 70% CELLULOSE FIBER |
| | Tan, Fibrous | | | | 30% NON FIBROUS MATERIAL |
| 365030-002 | 03/11/20 | 2 | Wisconsin | | |
| Layer 1: | Shingle | | | None Detected | 5% CELLULOSE FIBER |
| | Black, Bituminous/Granular | | | | 5% MINERAL/GLASS WOOL |
| | | | | | 90% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| Layer 2: | Felt | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| Layer 3: | Fibrous Material | | | None Detected | 70% CELLULOSE FIBER |
| | Tan, Fibrous | | | | 30% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wiconsin
Number: 20-400-020.219-21

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|--|----------------------------|----------|----------|-----------------|--------------------------|
| 365030-003 | 03/11/20 | 3 | Wiconsin | | |
| Layer 1: | Shingle | | | None Detected | 5% CELLULOSE FIBER |
| | Black, Bituminous/Granular | | | | 5% MINERAL/GLASS WOOL |
| | | | | | 90% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| Layer 2: | Felt | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| Layer 3: | Fibrous Material | | | None Detected | 70% CELLULOSE FIBER |
| | Tan, Fibrous | | | | 30% NON FIBROUS MATERIAL |
| 365030-004 | 03/11/20 | 4 | Wiconsin | | |
| Layer 1: | Paper | | | None Detected | 65% CELLULOSE FIBER |
| | Brown, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365030-005 | 03/11/20 | 5 | Wiconsin | | |
| Layer 1: | Paper | | | None Detected | 65% CELLULOSE FIBER |
| | Brown, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365030-006 | 03/11/20 | 6 | Wiconsin | | |
| Layer 1: | Paper | | | None Detected | 65% CELLULOSE FIBER |
| | Brown, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365030-007 | 03/11/20 | 7 | Wiconsin | | |
| Layer 1: | Tile | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Org.Bound/Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| 365030-008 | 03/11/20 | 8 | Wiconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |
| 365030-009 | 03/11/20 | 9 | Wiconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |
| 365030-010 | 03/11/20 | 10 | Wiconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wiconsin
Number: 20-400-020.219-21

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|--|-----------|----------|----------|-----------------|---|
| 365030-011 | 03/11/20 | 11 | Wiconsin | | |
| Layer 1: Tile Beige, Org.Bound/Fibrous | | | | None Detected | 35% CELLULOSE FIBER 15% MINERAL/GLASS WOOL 50% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| Layer 2: Mastic Tan, Soft | | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365030-012 | 03/11/20 | 12 | Wiconsin | | |
| Layer 1: Tile Beige, Org.Bound/Fibrous | | | | None Detected | 35% CELLULOSE FIBER 15% MINERAL/GLASS WOOL 50% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| Layer 2: Mastic Tan, Soft | | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365030-013 | 03/11/20 | 13 | Wiconsin | | |
| Layer 1: Tile Beige, Org.Bound/Fibrous | | | | None Detected | 35% CELLULOSE FIBER 15% MINERAL/GLASS WOOL 50% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| Layer 2: Mastic Tan, Soft | | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365030-014 | 03/11/20 | 14 | Wiconsin | | |
| Layer 1: Tile White, Hard | | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: Mastic White, Soft | | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365030-015 | 03/11/20 | 15 | Wiconsin | | |
| Layer 1: Acoustical Tile Beige, Fibrous | | | | None Detected | 40% CELLULOSE FIBER 40% MINERAL/GLASS WOOL 20% NON FIBROUS MATERIAL |
| 365030-016 | 03/11/20 | 16 | Wiconsin | | |
| Layer 1: Acoustical Tile Beige, Fibrous | | | | None Detected | 40% CELLULOSE FIBER 40% MINERAL/GLASS WOOL 20% NON FIBROUS MATERIAL |
| 365030-017 | 03/11/20 | 17 | Wiconsin | | |
| Layer 1: Acoustical Tile Beige, Fibrous | | | | None Detected | 40% CELLULOSE FIBER 40% MINERAL/GLASS WOOL 20% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wiconsin
Number: 20-400-020.219-21

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|------------------|----------|----------|-----------------|---------------------------|
| 365030-018 | 03/11/20 | 18 | Wiconsin | | |
| Layer 1: | Tile | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Beige/Gray, Hard | | | | |
| Layer 2: | Mastic | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Cream, Soft | | | | |
| 365030-019 | 03/11/20 | 19 | Wiconsin | | |
| Layer 1: | Tile | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Brown, Hard | | | | |
| Layer 2: | Hard Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Beige, Hard | | | | |
| 365030-020 | 03/11/20 | 20 | Wiconsin | | |
| Layer 1: | Tile | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Brown, Hard | | | | |
| Layer 2: | Hard Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Beige, Hard | | | | |
| 365030-021 | 03/11/20 | 21 | Wiconsin | | |
| Layer 1: | Tile | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Brown, Hard | | | | |
| Layer 2: | Hard Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Beige, Hard | | | | |
| Layer 3: | Mastic | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Brittle | | | | |
| 365030-022 | 03/11/20 | 22 | Wiconsin | | |
| Layer 1: | Tile | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray, Hard | | | | |
| Layer 2: | Hard Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Beige, Hard | | | | |
| Layer 3: | Mastic | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Brittle | | | | |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
www.slabinc.com • info@slabinc.com

365030 O 28

V:1365\365030

fghraizi 3/16/2020 9:47:56 AM
UPS 1Z2E28998462845568

| | | | | | |
|-------------------------|--------------------------|------------------------------|------------------------------------|----------------------|--|
| Submitting Co. | Harenda Management Group | State of Collection | WI | Gen. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmental.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.219-21 | | | | |
| Collected By | | | | | |

| Turn Around Time** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 1 | 3/11/20 | | | | | | | | |
| 2 | | | | | | | | | |
| 3 | | | | | | | | | |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: Date/Time 3/13/20 1700

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

| | | | | | |
|-------------------------|--------------------------|------------------------------|------------------------------------|-----------------------|--|
| Submitting Co. | Harenda Management Group | State of Collection | WI | Cert. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmental.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.219-21 | | | | |
| Collected By | | | | | |

| Turn Around Time** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input type="checkbox"/> 5 business days * not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 11 | 3/11/20 | | | | | | | | |
| 12 | | | | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | | | | | | | | |
| 16 | | | | | | | | | |
| 17 | | | | | | | | | |
| 18 | | | | | | | | | |
| 19 | | | | | | | | | |
| 20 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen

Signature:

Date/Time 3/13/2020

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabin.com • info@slabin.com

| | | | | | |
|-------------------------|--------------------------|------------------------------|------------------------------------|-----------------------|--|
| Submitting Co. | Harenda Management Group | State of Collection | WI | Cert. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmental.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.219-21 | | | | |
| Collected By | | | | | |

| Turn Around Time** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 21 | 3/11/20 | | | | | | | | |
| 22 | | | | | | | | | |
| 23 | | | | | | | | | |
| 24 | | | | | | | | | |
| 25 | | | | | | | | | |
| 26 | | | | | | | | | |
| 27 | | | | | | | | | |
| 28 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters (time in min x flow in L/min)

Relinquished By: Dean Jacobsen

Signature:

Date/Time 3/13/2020


! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !

IX. FLOOR PLANS

**Two Family Dwelling
219-221 North 33rd Street
Milwaukee, Wisconsin**




Basement Floor Plan



**Two Family Dwelling
219-221 North 33rd Street
Milwaukee, Wisconsin**




1st Floor Plan



**Two Family Dwelling
219-221 North 33rd Street
Milwaukee, Wisconsin**



2nd Floor Plan



X. HMG CERTIFICATION

Company Certificate

This certifies that

HARENDA MANAGEMENT GROUP

1237 W BRUCE ST
MILWAUKEE WI 53204-1218

is certified under ch. DHS 159, Wis.Adm.Code as a

Asbestos Company -- Primary

Certificate Issue Date: 07/23/2019
Expiration Date: 08/31/2021, 12:01 a.m.
Certification #: CAP-480540

Wisconsin Department of Health Services
Division of Public Health
Bureau of Environmental and Occupational Health
Asbestos & Lead Section
PO Box 2659
Madison WI 53701-2659
Phone: (608) 261-6876



Miriam Hasan
Miriam Hasan, Unit Supervisor



ASBESTOS INSPECTOR

Issued By

STATE OF WISCONSIN

Dept. of Health Services

Cecil James Trawick Jr

5624 N 97th Street

Milwaukee WI 53222 2502

| | | | |
|------------|-----------------|------------|--------|
| | | 222 lbs | 5' 08" |
| All-104769 | Exp: 10/02/2020 | 07/09/1971 | |

Training due by: 10/02/2020

COPY



PRE-DEMOLITION INSPECTION REPORT

Job Site:

**Fire Damaged
Two Family Dwelling
223-225 North 33rd Street
Milwaukee, Wisconsin**

For:

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613


**HMG Report No.: 20-400-020. 223-25
Inspector: Cecil Trawick
Contract No.: 360-20-0975**

Prepared by:

HARENDA MANAGEMENT GROUP
1237 West Bruce Street
Milwaukee, Wisconsin 53204
(414) 383-4800

April 2020

Signature Page
Pre-Demolition Inspection Report
Two Family Dwelling
223-225 North 33rd Street
Milwaukee, Wisconsin



Dean Jacobsen
Asbestos Inspector No. AII – 14370
Expiration Date: 12/2/20
Harenda Management Group



Cecil Trawick
Asbestos Inspector No. AII – 104769
Expiration Date: 10/2/20
Harenda Management Group

April 21, 2020

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613

RE: Pre-Demolition Inspection Report
223-225 North 33rd Street
Milwaukee, WI

Harenda Management Group has completed the pre-demolition inspection of the two family dwelling and garage at 223-225 North 33rd Street, Milwaukee, Wisconsin, as per the referral from the City of Milwaukee Department of Neighborhood Services. The inspection and results are described in the following report. Please contact me at (414) 383-4800 if you have any questions.

Sincerely,

HARENDA MANAGEMENT GROUP



Dean Jacobsen
Asbestos Inspector No. AII – 14370

EXECUTIVE SUMMARY

Harenda Management Group was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection of the two family dwelling and garage at 223-225 North 33rd Street, Milwaukee, Wisconsin, prior to demolition. HMG conducted a visual inspection for asbestos and universal wastes.

The dwelling was severely fire damaged and unsafe to enter. No samples were collected for laboratory analysis. Asbestos was assumed to be in the asphalt roofing in the dwelling debris and on the garage. Results are in Section III of this report.

TABLE OF CONTENTS
Pre-Demolition Inspection Report

| | | |
|-------|---|---|
| I. | Introduction..... | 1 |
| II. | Asbestos Inspection | 1 |
| III. | Asbestos Findings and Observations | 1 |
| IV. | Exclusions | 2 |
| V. | Limitations | 2 |
| VI. | Pre-Demolition Environmental Checklist..... | 3 |
| VII. | Floor Plans | 7 |
| VIII. | HMG Certifications | 8 |

I. INTRODUCTION

Harenda Management Group (HMG) was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection for suspect asbestos containing materials in the two family dwelling and garage at 223-225 North 33rd Street, Milwaukee, Wisconsin. The dwelling is a two story wood framed structure with basement. The garage has vinyl and wood walls with asphalt roofing.

II. ASBESTOS INSPECTION

Marge Piwaron, of the City of Milwaukee Department of Neighborhood Services, authorized HMG to conduct a building inspection and to analyze samples collected during the inspection.

On March 13, 2020, HMG conducted an asbestos inspection of a two family dwelling and garage, scheduled for mechanical demolition, located at 223-225 North 33rd Street, Milwaukee, Wisconsin. The inspection was conducted by Cecil Trawick, Wisconsin License No. AII – 104769, and the report was written by Dean Jacobsen, Wisconsin License No. AII – 14370.

The inspection was comprised of these elements:

1. A visual determination as to the extent of suspect asbestos containing materials within the buildings.
2. Documentation of observable suspect asbestos containing materials.
3. Quantification of observable asbestos containing materials existing within the spaces.

The results of the inspection are outlined in this document.

The following types of suspect materials were observed and inspected to determine if asbestos containing materials were present in the buildings as required by U.S. EPA NESHAP regulation 40 CFR 61 Subpart M, and NR 447 of the Wisconsin Administrative Code:

- Asphalt roofing

A listing of specific homogeneous materials is in the Findings and Observations section.

III. ASBESTOS FINDINGS AND OBSERVATIONS

No suspect friable or category II non-friable asbestos containing materials were observed in the dwelling debris or in the garage.

Assumed Category I Non-Friable Asbestos Containing Material:

| Material | Location | Approximate Quantity | Material Type |
|-----------------------------|-------------------------|----------------------|------------------------|
| Asphalt Shingles & Flashing | In Dwelling Fire Debris | 1,500 SF | Category I Non-Friable |
| Asphalt Shingles & Flashing | Garage Roof | 700 SF | Category I Non-Friable |

Note #1: The asphalt roofing is a category I non friable asbestos containing material. Under NR 447 it does not currently meet the definition of regulated asbestos containing material (RACM) and need not be removed before demolition if the demolition debris does not become RACM and will be disposed at a Wisconsin licensed landfill.

Note#2: Category I – Non-Friable Asbestos Containing Materials may become RACM during mechanical demolition activities or maybe considered friable prior to demolition activities due to its condition at time of demolition.

Note#3: If additional materials are discovered during demolition that are not listed above they are to be assumed to be asbestos containing.

Note#4: A copy of this report should be transmitted to the demolition contractor.

IV. EXCLUSIONS

Dwelling is severely fire damaged and was unsafe to enter – all dwelling surfaces inaccessible. Only visible or accessible areas were included in the scope of work.

HMG is not and shall not represent the building owner as its agent or representative for the purpose of the US EPA/NESHAP and/or the WDNR/NR447 regulations, as owner/operator.

This report represents the condition of the buildings and the visible/accessible suspect asbestos containing materials at the date and the times of the onsite inspection. Hidden materials or inaccessible materials, or those materials that could be present at the point of inspection, over and above those stated in the inspection report, are the responsibility of the building owner and the demolition contractor.

V. LIMITATIONS

The care and skill given to our procedures insures the most reliable test results possible. HMG utilizes Schneider Laboratories Global, Inc., for our asbestos testing. The findings and conclusions of HMG represent our professional opinions extrapolated from limited data. Significant limited data is gathered during the course of the preliminary asbestos specific site assessment. No other warranty is expressed or implied. Prior to any abatement or renovation activities, it is recommended that HMG be provided the opportunity to review such plans in order that the inspection and assessments contained herein are properly interpreted and implemented.

This report and the information contained herein are prepared for the sole and exclusive use and possession of the City of Milwaukee Department of Neighborhood Services. No other person or entity may rely on this report or any information contained herein. Any dissemination of the Report or any information contained herein is strictly prohibited without prior written authorization from Harenda Management Group.

VI. PRE-DEMOLITION ENVIRONMENTAL CHECKLIST

This guide lists materials and products commonly found in buildings with examples. It is not intended as a substitute for reading the rules and statutes and making your own independent determination of their applicability to your demolition project. These examples presented here do not represent an exhaustive listing of types of materials that may be required to be removed from the building prior to demolition.

ASBESTOS

Persons conducting inspections for asbestos must hold a valid asbestos inspector certification card issued by the State of Wisconsin, Dept. of Health Services. **Please follow the Asbestos Inspection and Sampling Protocol for Buildings to be Demolished or Renovated.**

CFCs and HALONS

Equipment that may contain CFCs and Halons:

| | |
|------------|--|
| <u>N/A</u> | Air Conditioners (roof top, room, and central) |
| <u>N/A</u> | Dehumidifiers |
| <u>N/A</u> | Heat Pumps |
| <u>N/A</u> | Refrigerators, Freezers, Chillers |
| <u>N/A</u> | Vending Machines, Food Display Cases |
| <u>N/A</u> | Walk-in Coolers |
| <u>N/A</u> | Water Fountains (bubblers) |
| <u>N/A</u> | Fire Extinguishers (both portable and installed HALON suppression systems) |
| <u>N/A</u> | Water Coolers |

LEAD

Lead or Lead Based Paint (LBP) is common in many older buildings. When recycling construction and demolition debris, be aware that wood containing lead paint may not be chipped and spread for landscaping. State law also prohibits the sale or transfer of any fixture or other object containing LBP that might be placed upon any surface of a dwelling, which is ordinarily accessible to children.

MERCURY

Products that may contain mercury:

LIGHTING

| | |
|------------|--|
| <u>N/A</u> | Fluorescent Lights |
| <u>N/A</u> | High Intensity Discharge -Metal Halide -High Pressure Sodium -Mercury Vapor |
| <u>N/A</u> | Neon |
| <u>N/A</u> | Switches for lighting using mercury relays -Look for any control associated with exterior or automated lighting systems such as "Silent" wall switches. |

HVAC

Check thermostats and any control associated with air handling units for switches containing mercury.

HEATING, VENTILATING AND AIR CONDITIONING SYSTEMS

| | |
|------------|-----------------|
| <u>N/A</u> | Old Thermostats |
| <u>N/A</u> | Aquastats |
| <u>N/A</u> | Firestats |
| <u>N/A</u> | Manometers |
| <u>N/A</u> | Thermometers |

BOILERS, FURNACES, HEATERS AND TANKS

| | |
|------------|---------------------------------------|
| <u>N/A</u> | Mercury Flame Sensors by pilot lights |
| <u>N/A</u> | Manometers, Thermometers, Gauges |
| <u>N/A</u> | Pressure-trol |
| <u>N/A</u> | Float or Level Controls |
| <u>N/A</u> | Space Heaters |

ELECTRICAL SYSTEMS

| | |
|------------|-------------------------------|
| <u>N/A</u> | Load Meters and Supply Relays |
| <u>N/A</u> | Phase Splitters |
| <u>N/A</u> | Microwave Relays |
| <u>N/A</u> | Mercury Displacement Relays |

PCBs

For electrical devices manufactured prior to 1987, it is safe to assume that they contain PCBs and should be managed accordingly. Most equipment manufactured after this time will say "PCB Free". The following is a list of areas in a building where PCBs may be found:

| | |
|------------|--|
| <u>N/A</u> | Transformers |
| <u>N/A</u> | Capacitors (appliances, electronic equipment) |
| <u>N/A</u> | Heat Transfer Equipment |
| <u>N/A</u> | Ballasts |
| <u>N/A</u> | Specialty Paints (such as for swimming pools or other industrial applications) |
| <u>N/A</u> | Sumps or Oil Traps (in maintenance and industrial facilities) |



OTHER ENVIRONMENTAL ISSUES

| | |
|------------|------------------|
| <u>N/A</u> | Hazardous Waste |
| <u>N/A</u> | Oil Tanks |
| <u>N/A</u> | Well Abandonment |
| <u>N/A</u> | Junk Auto Tires |
| <u>N/A</u> | Junk Vehicles |

VII. FLOOR PLANS

**Two Family Dwelling
223-225 North 33rd Street
Milwaukee, Wisconsin**

1st Floor Plan



VIII. HMG CERTIFICATION

Company Certificate

This certifies that

HARENDA MANAGEMENT GROUP

1237 W BRUCE ST
MILWAUKEE WI 53204-1218

is certified under ch. DHS 159, Wis. Adm. Code as a

Asbestos Company -- Primary

Certificate Issue Date: 07/23/2019
Expiration Date: 08/31/2021, 12:01 a.m.
Certification #: CAP-480540

Wisconsin Department of Health Services
Division of Public Health
Bureau of Environmental and Occupational Health
Asbestos & Lead Section
PO Box 2659
Madison WI 53701-2659
Phone: (608) 261-6876



Miriam Hasan
Miriam Hasan, Unit Supervisor



ASBESTOS INSPECTOR

Issued By

STATE OF WISCONSIN

Dept. of Health Services

Cecil James Trawick Jr

5624 N 97th Street

Milwaukee WI 53227 2502

| | | | |
|------------|-----------------|------------|--------|
| | | 222 lbs | 5' 08" |
| All-104769 | Exp: 10/02/2020 | 07/09/1971 | |

Training due by: 10/02/2020

COPY



PRE-DEMOLITION INSPECTION REPORT

Job Site:

**Fire Damaged
Two Family Dwelling
1951-51A North 33rd Street
Milwaukee, Wisconsin**

For:

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613


**HMG Report No.: 20-400-020.1951
Inspector: Cecil Trawick
Contract No.: 360-20-0975**

Prepared by:

HARENDA MANAGEMENT GROUP
1237 West Bruce Street
Milwaukee, Wisconsin 53204
(414) 383-4800

April 2020

Signature Page
Pre-Demolition Inspection Report
Two Family Dwelling
1951-51A North 33rd Street
Milwaukee, Wisconsin



Dean Jacobsen
Asbestos Inspector No. AII – 14370
Expiration Date: 12/2/20
Harenda Management Group



Cecil Trawick
Asbestos Inspector No. AII – 104769
Expiration Date: 10/2/20
Harenda Management Group

April 21, 2020

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613

RE: Pre-Demolition Inspection Report
1951-51A North 33rd Street
Milwaukee, WI

Harenda Management Group has completed the pre-demolition inspection of the two family dwelling at 1951-51A North 33rd Street, Milwaukee, Wisconsin, as per the referral from the City of Milwaukee Department of Neighborhood Services. The inspection and results are described in the following report. Please contact me at (414) 383-4800 if you have any questions.

Sincerely,

HARENDA MANAGEMENT GROUP



Dean Jacobsen
Asbestos Inspector No. AII – 14370

EXECUTIVE SUMMARY

Harenda Management Group was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection of the two family dwelling at 1951-51A North 33rd Street, Milwaukee, Wisconsin, prior to demolition. HMG conducted a visual inspection for asbestos and universal wastes. HMG collected asbestos bulk samples for laboratory analysis.

Asbestos was not detected in any material sampled during the inspection. Asbestos was assumed to be in the asphalt roofing and in the floor tile and mastic in the dwelling. Results are in Section IV of this report.

TABLE OF CONTENTS
Pre-Demolition Inspection Report

| | | |
|-------|---|----|
| I. | Introduction..... | 1 |
| II. | Asbestos Inspection | 1 |
| III. | Asbestos Laboratory | 2 |
| | A. Method of Analysis | |
| IV. | Asbestos Findings and Observations | 2 |
| V. | Exclusions | 4 |
| VI. | Limitations | 4 |
| VII. | Pre-Demolition Environmental Checklist..... | 6 |
| VIII. | Asbestos Laboratory Results..... | 10 |
| IX. | Floor Plans | 11 |
| X. | HMG Certifications | 12 |

I. INTRODUCTION

Harenda Management Group (HMG) was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection for suspect asbestos containing materials in the two family dwelling at 1951-51A North 33rd Street, Milwaukee, Wisconsin. The dwelling is a two story wood framed structure with basement and has vinyl, asphalt, and wood walls with asphalt roofing.

II. ASBESTOS INSPECTION

Marge Piwaron, of the City of Milwaukee Department of Neighborhood Services, authorized HMG to conduct a building inspection and to analyze samples collected during the inspection.

On March 13, 2020, HMG conducted an asbestos inspection of a two family dwelling, scheduled for mechanical demolition, located at 1951-51A North 33rd Street, Milwaukee, Wisconsin. The inspection was conducted by Cecil Trawick, Wisconsin License No. AII – 104769, and the report was written by Dean Jacobsen, Wisconsin License No. AII – 14370..

The inspection was comprised of these elements:

1. A visual determination as to the extent of suspect asbestos containing materials within the building.
2. Sampling and documentation of observable suspect asbestos containing materials.
3. Quantification of observable asbestos containing materials existing within the spaces.

The results of the inspection integrated with the Polarized Light Microscopy with Dispersion Staining (PLM/DS) analysis of asbestos bulk samples collected are outlined in this document.

The following types of suspect materials were observed and inspected to determine if asbestos containing materials were present in the building as required by U.S. EPA NESHAP regulation 40 CFR 61 Subpart M, and NR 447 of the Wisconsin Administrative Code:

- Asphalt shingle siding
- Paper insulation
- Ceramic tile
- Drywall
- Plaster
- Flue packing
- Blown in insulation
- Floor tile
- Asphalt roofing
- Mastics

A listing of specific homogeneous materials and homogeneous material codes are in the Findings and Observations section following the results table.

III. ASBESTOS LABORATORY

A. METHOD OF ANALYSIS

Analysis is performed by using the bulk samples for visual observation and slide preparation(s) for microscopical examination and identification. The slides are analyzed for asbestos (chrysotile, amosite, crocidolite, anthophyllite, and actinolite/tremolite), fibrous non asbestos constituents (mineral wool, paper, etc.), and nonfibrous constituents. Asbestos is identified by refractive indices (obtained by using dispersion staining), morphology, color, pleochroism, birefringence, extinction characteristics, and signs of elongation. The same characteristics are used to identify the non asbestos constituents.

The microscopist visually estimates relative amounts of each constituent using a stereoscope if necessary. The test results are based on a visual determination of relative volume of the bulk sample components. The results are valid only for the item tested. Current federal and Wisconsin regulations state asbestos containing material means material containing more than 1% asbestos as determined using the method specified in Appendix E, Subpart E, 40 CFR Part 763 Section I, Polarized Light Microscopy. Bold values below indicate that the material contains more than 1% asbestos. Refer to 29 CFR 1926.1101 (Construction) and 29 CFR 1910.1001 (General Industry) for specific OSHA requirements.

IV. ASBESTOS FINDINGS AND OBSERVATIONS

The following are the laboratory results. The laboratory report is in Section VIII.

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|---|----------|------------------|
| 1a | Exterior – east wall under vinyl siding – asphalt shingle siding | Negative | MSS |
| 1b | Exterior – east wall under asphalt shingle siding – tar paper | Negative | MPT |
| 1c | Exterior – east wall under tar paper – fiberboard | Negative | MFB |
| 2a | Exterior – south wall under vinyl siding – asphalt shingle siding | Negative | MSS |
| 2b | Exterior – south wall under asphalt shingle siding – tar paper | Negative | MSS |
| 2c | Exterior – south wall under tar paper – fiberboard | Negative | MSS |
| 3a | Exterior – north wall under tar paper – fiberboard | Negative | MSS |
| 3b | Exterior – north wall under asphalt shingle siding – tar paper | Negative | MSS |
| 3c | Exterior – north wall under tar paper – fiberboard | Negative | MSS |
| 4 | Exterior – south wall under wood siding – tan paper insulation | Negative | MPIt |
| 5 | Exterior – north wall under wood siding – tan paper insulation | Negative | MPIt |
| 6 | Exterior – east wall under wood siding – tan paper insulation | Negative | MPIt |
| 7a | 1 st floor – front entry floor – brown ceramic tile | Negative | MCTMn |
| 7b | 1 st floor – front entry floor – under brown ceramic tile – mortar | Negative | MCTMn |
| 8 | 1 st floor – living room – south wall – drywall | Negative | MDW |
| 9 | 1 st floor – dining room – north wall – drywall | Negative | MDW |
| 10 | 1 st floor – kitchen – west wall – drywall | Negative | MDW |

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|--|----------|------------------|
| 11a | 1 st floor – front entry – ceiling – plaster base coat | Negative | SPI |
| 11b | 1 st floor – front entry – ceiling – plaster skim coat | Negative | SPI |
| 12a | 1 st floor – living room – north wall – plaster base coat | Negative | SPI |
| 12b | 1 st floor – living room – north wall – plaster skim coat | Negative | SPI |
| 13a | 1 st floor – dining room – north wall – plaster base coat | Negative | SPI |
| 13b | 1 st floor – dining room – north wall – plaster skim coat | Negative | SPI |
| 14a | 1 st floor – north bedroom – ceiling – plaster base coat | Negative | SPI |
| 14b | 1 st floor – north bedroom – ceiling – plaster skim coat | Negative | SPI |
| 15a | 2 nd floor – kitchen – north wall – plaster base coat | Negative | SPI |
| 15b | 2 nd floor – kitchen – north wall – plaster skim coat | Negative | SPI |
| 16a | 2 nd floor – front stair – north wall – plaster base coat | Negative | SPI |
| 16b | 2 nd floor – front stair – north wall – plaster skim coat | Negative | SPI |
| 17a | 2 nd floor – northwest bedroom – west wall – plaster base coat | Negative | SPI |
| 17b | 2 nd floor – northwest bedroom – west wall – plaster skim coat | Negative | SPI |
| 18a | 1 st floor – bathroom floor – yellow ceramic tile | Negative | MCTMI |
| 18b | 1 st floor – bathroom floor – under yellow ceramic tile – mortar | Negative | MCTMI |
| 19a | 1 st floor – bathroom – on north wall– white ceramic tile | Negative | MCTMw |
| 19b | 1 st floor – bathroom – on north wall – under white ceramic tile – clear mastic | Negative | MCTMw |
| 20a | 1 st floor – kitchen – on north wall– cream ceramic tile | Negative | MCTMw |
| 20b | 1 st floor – kitchen – on north wall – under cream ceramic tile – mortar | Negative | MCTMw |
| 21a | 1 st floor – kitchen floor– cream ceramic tile | Negative | MCTMw |
| 21b | 1 st floor – kitchen floor – under cream ceramic tile – mortar | Negative | MCTMw |
| 22a | 1 st floor – kitchen – on south wall– cream ceramic tile | Negative | MCTMw |
| 22b | 1 st floor – kitchen – on south wall – under cream ceramic tile – mortar | Negative | MCTMw |
| 23 | Basement – on chimney – flue packing | Negative | TFP |
| 24 | 2 nd floor – kitchen – in ceiling – blown in insulation | Negative | MBI |
| 25 | 2 nd floor – dining room – in ceiling – blown in insulation | Negative | MBI |
| 26 | 2 nd floor – northwest bedroom – in ceiling – blown in insulation | Negative | MBI |

None of the materials sampled contain asbestos.

Assumed Category I Non-Friable Asbestos Containing Material:

| Material | Location | Approximate Quantity | Material Type |
|-----------------------------|-----------------------------------|----------------------|------------------------|
| Asphalt Shingles & Flashing | House Roof | 1,100 SF | Category I Non-Friable |
| Floor Tile & Mastic | 2 nd Floor Living Room | 50 SF | Category I Non-Friable |

Note #1: The asphalt roofing and floor tile/mastic are category I non friable asbestos containing materials. Under NR 447 they do not currently meet the definition of regulated asbestos containing material (RACM) and need not be removed before demolition if the demolition debris does not become RACM and will be disposed at a Wisconsin licensed landfill.

Note#2: Category I – Non-Friable Asbestos Containing Materials may become RACM during mechanical demolition activities or maybe considered friable prior to demolition activities due to its condition at time of demolition.

Note#3: If additional materials are discovered during demolition that are not listed above they are to be assumed to be asbestos containing.

Note#4: A copy of this report should be transmitted to the demolition contractor.

Homogeneous Material Codes

| | |
|-------|------------------------|
| SPI | Plaster |
| MSS | Asphalt Shingle Siding |
| MPT | Tar Paper |
| MFB | Fiberboard |
| MPIt | Tan Paper Insulation |
| MCTMn | Brown Ceramic Tile |
| MCTMI | Yellow Ceramic Tile |
| MCTMw | White Ceramic Tile |
| MCTMc | Cream Ceramic Tile |
| MBI | Blown in Insulation |
| MDW | Drywall |
| TFP | Flue Packing |

V. EXCLUSIONS

Dwelling is fire damaged – surfaces in rooms only partially accessible. Not all areas within walls and ceilings were accessible, and these areas may contain suspect asbestos containing materials. Only visible or accessible areas were included in the scope of work.

HMG is not and shall not represent the building owner as its agent or representative for the purpose of the US EPA/NESHAP and/or the WDNR/NR447 regulations, as owner/operator.

This report represents the condition of the building and its visible/accessible suspect asbestos containing materials at the date and the times of the onsite inspection. Hidden materials or inaccessible materials, or those materials that could be present at the point of inspection, over and above those stated in the inspection report, are the responsibility of the building owner and the demolition contractor.

VI. LIMITATIONS

The care and skill given to our procedures insures the most reliable test results possible. HMG utilizes Schneider Laboratories Global, Inc., for our asbestos testing. The findings and conclusions of HMG represent our professional opinions extrapolated from limited data. Significant limited data is gathered during the course of the preliminary asbestos specific site assessment. No other warranty is expressed or implied. Prior to any abatement or renovation activities, it is recommended that HMG be provided the opportunity to review such plans in order that the inspection and assessments contained herein are properly interpreted and implemented.

This report and the information contained herein are prepared for the sole and exclusive use and possession of the City of Milwaukee Department of Neighborhood Services. No other person or entity may rely on this report or any information contained herein. Any dissemination of the

Report or any information contained herein is strictly prohibited without prior written authorization from Harenda Management Group.

VII. PRE-DEMOLITION ENVIRONMENTAL CHECKLIST

This guide lists materials and products commonly found in buildings with examples. It is not intended as a substitute for reading the rules and statutes and making your own independent determination of their applicability to your demolition project. These examples presented here do not represent an exhaustive listing of types of materials that may be required to be removed from the building prior to demolition.

ASBESTOS

Persons conducting inspections for asbestos must hold a valid asbestos inspector certification card issued by the State of Wisconsin, Dept. of Health Services. **Please follow the Asbestos Inspection and Sampling Protocol for Buildings to be Demolished or Renovated.**

CFCs and HALONS

Equipment that may contain CFCs and Halons:

| | |
|------------|--|
| <u>N/A</u> | Air Conditioners (roof top, room, and central) |
| <u>N/A</u> | Dehumidifiers |
| <u>N/A</u> | Heat Pumps |
| <u>N/A</u> | Refrigerators, Freezers, Chillers |
| <u>N/A</u> | Vending Machines, Food Display Cases |
| <u>N/A</u> | Walk-in Coolers |
| <u>N/A</u> | Water Fountains (bubblers) |
| <u>N/A</u> | Fire Extinguishers (both portable and installed HALON suppression systems) |
| <u>N/A</u> | Water Coolers |

LEAD

Lead or Lead Based Paint (LBP) is common in many older buildings. When recycling construction and demolition debris, be aware that wood containing lead paint may not be chipped and spread for landscaping. State law also prohibits the sale or transfer of any fixture or other object containing LBP that might be placed upon any surface of a dwelling, which is ordinarily accessible to children.

MERCURY

Products that may contain mercury:

LIGHTING

| | |
|------------|--|
| <u>3</u> | Fluorescent Lights – 1 st Floor Kitchen |
| <u>N/A</u> | High Intensity Discharge -Metal Halide -High Pressure Sodium -Mercury Vapor |
| <u>N/A</u> | Neon |
| <u>N/A</u> | Switches for lighting using mercury relays -Look for any control associated with exterior or automated lighting systems such as "Silent" wall switches. |

HVAC

Check thermostats and any control associated with air handling units for switches containing mercury.

HEATING, VENTILATING AND AIR CONDITIONING SYSTEMS

| | |
|------------|-----------------|
| <u>N/A</u> | Old Thermostats |
| <u>N/A</u> | Aquastats |
| <u>N/A</u> | Firestats |
| <u>N/A</u> | Manometers |
| <u>N/A</u> | Thermometers |

BOILERS, FURNACES, HEATERS AND TANKS

| | |
|------------|---------------------------------------|
| <u>N/A</u> | Mercury Flame Sensors by pilot lights |
| <u>N/A</u> | Manometers, Thermometers, Gauges |
| <u>N/A</u> | Pressure-trol |
| <u>N/A</u> | Float or Level Controls |
| <u>N/A</u> | Space Heaters |

ELECTRICAL SYSTEMS – 1 Electrical Box in Basement

| | |
|------------|-------------------------------|
| <u>N/A</u> | Load Meters and Supply Relays |
| <u>N/A</u> | Phase Splitters |
| <u>N/A</u> | Microwave Relays |
| <u>N/A</u> | Mercury Displacement Relays |

PCBs

For electrical devices manufactured prior to 1987, it is safe to assume that they contain PCBs and should be managed accordingly. Most equipment manufactured after this time will say "PCB Free". The following is a list of areas in a building were PCBs may be found:

| | |
|------------|--|
| <u>N/A</u> | Transformers |
| <u>N/A</u> | Capacitors (appliances, electronic equipment) |
| <u>N/A</u> | Heat Transfer Equipment |
| <u>N/A</u> | Ballasts |
| <u>N/A</u> | Specialty Paints (such as for swimming pools or other industrial applications) |
| <u>N/A</u> | Sumps or Oil Traps (in maintenance and industrial facilities) |

OTHER ENVIRONMENTAL ISSUES

| | |
|------------|--------------------------------------|
| <u>N/A</u> | Hazardous Waste |
| <u>N/A</u> | Oil Tanks |
| <u>N/A</u> | Well Abandonment |
| <u>1</u> | Junk Auto Tires – Exterior Back Yard |
| <u>N/A</u> | Junk Vehicles |

* 1 Gas Meter on Exterior

* 2 Gallons Paint 1st Floor Kitchen & Basement

VIII. ASBESTOS LABORATORY RESULTS



Customer: Harenda Management Group (5065)
Address: 1237 West Bruce Street
Milwaukee, WI 53204

| | |
|-----------------|---------------|
| Order #: | 365217 |
|-----------------|---------------|

Received 03/17/20
Analyzed 03/20/20
Reported 03/24/20

Attn:

Project:

Location: Wisconsin
Number: 20-400-020.1951

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|--|----------------------------|----------|-----------|-----------------|--------------------------|
| 365217-001 | 03/13/20 | 1 | Wisconsin | | |
| Layer 1: | Shingle | | | None Detected | 5% CELLULOSE FIBER |
| | Black, Bituminous/Granular | | | | 5% MINERAL/GLASS WOOL |
| | | | | | 90% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| Layer 2: | Felt | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| Layer 3: | Fibrous Material | | | None Detected | 70% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 30% NON FIBROUS MATERIAL |
| 365217-002 | 03/13/20 | 2 | Wisconsin | | |
| Layer 1: | Shingle | | | None Detected | 5% CELLULOSE FIBER |
| | Black, Bituminous/Granular | | | | 5% MINERAL/GLASS WOOL |
| | | | | | 90% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| Layer 2: | Felt | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| Layer 3: | Fibrous Material | | | None Detected | 70% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 30% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.1951

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|--|----------------------------|----------|-----------|-----------------|---------------------------|
| 365217-003 | 03/13/20 | 3 | Wisconsin | | |
| Layer 1: | Shingle | | | None Detected | 5% CELLULOSE FIBER |
| | Black, Bituminous/Granular | | | | 5% MINERAL/GLASS WOOL |
| | | | | | 90% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| Layer 2: | Felt | | | None Detected | 65% CELLULOSE FIBER |
| | Black, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| Layer 3: | Fibrous Material | | | None Detected | 70% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 30% NON FIBROUS MATERIAL |
| 365217-004 | 03/13/20 | 4 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365217-005 | 03/13/20 | 5 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365217-006 | 03/13/20 | 6 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365217-007 | 03/13/20 | 7 | Wisconsin | | |
| Layer 1: | Tile | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Brown, Hard | | | | |
| Layer 2: | Hard Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray, Hard | | | | |
| 365217-008 | 03/13/20 | 8 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |
| 365217-009 | 03/13/20 | 9 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |
| 365217-010 | 03/13/20 | 10 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.1951

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|--------------------------------------|----------|-----------|-----------------|---------------------------|
| 365217-011 | 03/13/20 | 11 | Wisconsin | | |
| Layer 1: | Plaster Gray, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365217-012 | 03/13/20 | 12 | Wisconsin | | |
| Layer 1: | Plaster Gray, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365217-013 | 03/13/20 | 13 | Wisconsin | | |
| Layer 1: | Plaster Gray, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365217-014 | 03/13/20 | 14 | Wisconsin | | |
| Layer 1: | Plaster Gray, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365217-015 | 03/13/20 | 15 | Wisconsin | | |
| Layer 1: | Plaster Gray, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365217-016 | 03/13/20 | 16 | Wisconsin | | |
| Layer 1: | Plaster Gray, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.1951

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|--------------------------------------|----------|-----------|-----------------|---------------------------|
| 365217-017 | 03/13/20 | 17 | Wisconsin | | |
| Layer 1: | Plaster Gray, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365217-018 | 03/13/20 | 18 | Wisconsin | | |
| Layer 1: | Tile Beige, Hard | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Hard Material White, Hard | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365217-019 | 03/13/20 | 19 | Wisconsin | | |
| Layer 1: | Tile Beige/Black, Hard | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Mastic Clear, Soft | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365217-020 | 03/13/20 | 20 | Wisconsin | | |
| Layer 1: | Tile Beige, Hard | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Hard Material Gray, Hard | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365217-021 | 03/13/20 | 21 | Wisconsin | | |
| Layer 1: | Tile Beige, Hard | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Hard Material Gray, Hard | | | None Detected | 100% NON FIBROUS MATERIAL |
| 365217-022 | 03/13/20 | 22 | Wisconsin | | |
| Layer 1: | Tile Beige, Hard | | | None Detected | 100% NON FIBROUS MATERIAL |
| Layer 2: | Hard Material Gray, Hard | | | None Detected | 100% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 20-400-020.1951

Method: EPA 600/R-93/116 & 40 CFR App. E Sub. E Pt. 763

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|----------------|----------|-----------|-----------------|---------------------------|
| 365217-023 | 03/13/20 | 23 | Wisconsin | | |
| Layer 1: | Soft Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Gray, Soft | | | | |
| 365217-024 | 03/13/20 | 24 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365217-025 | 03/13/20 | 25 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 365217-026 | 03/13/20 | 26 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |


EPA Regulatory Limit: 1%

Total layers analyzed on order: 45

365217-03/24/20 10:37 AM



Analyst **Mohammed Hashim**



Reviewed By: **Hind Eldanaf**
Microscopy Manager

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

365217

O 26



V:\365\365217

fghraizi

3/17/2020 9:02:58 AM

UPS

1Z2E28998463840374

| | | | |
|---|------------------------------|--|--|
| Submitting Co. Harendra Management Group | | State of Collection WI | Cert. Required <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # 5065 | Phone (414) 647-1530 |
| Milwaukee, WI 53204 | | Email dean.jacobsen@kphenvironmenmtal.com | |
| Project Name | | PO # | |
| Project Location Wisconsin | Special Instructions: | | |
| Project Number 20-400-020.1951 | | | |
| Collected By | | | |

| Turn Around Time** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|--|--|--|--|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep <hr/> Asbestos in Air <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | Metals Total <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ <hr/> Gravimetric <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | TCLP <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP (w/ organics 10 Day) <hr/> Miscellaneous <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | Microbiology <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens <hr/> Sub-Contract <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|--|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 1 | 3/13/20 | | | | | | | | |
| 2 | | | | | | | | | |
| 3 | | | | | | | | | |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen

Signature:

Date/Time: 3/16/201700

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

| | | | | | |
|-------------------------|--------------------------|------------------------------|------------------------------------|-----------------------|--|
| Submitting Co. | Harenda Management Group | State of Collection | WI | Cert. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenviromenmtal.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.1951 | | | | |
| Collected By | | | | | |

| Turn Around Time** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|---|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days * not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 11 | 3/13/20 | | | | | | | | |
| 12 | | | | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | | | | | | | | |
| 16 | | | | | | | | | |
| 17 | | | | | | | | | |
| 18 | | | | | | | | | |
| 19 | | | | | | | | | |
| 20 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: Date/Time: 3/16/20(700)

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

| | | | | | |
|------------------------|--------------------------|-----------------------|-------------------------------------|----------------|--|
| Submitting Co. | Harenda Management Group | State of Collection | WI | Cert. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmenmtal.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: | | | |
| Project Number | 20-400-020.1951 | | | | |
| Collected By | | | | | |

| Turn Around Time ** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests</small> <small>** past 3 PM the TAT will begin next business day</small> <small>Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 21 | 3/13/20 | | | | | | | | |
| 22 | | | | | | | | | |
| 23 | | | | | | | | | |
| 24 | | | | | | | | | |
| 25 | | | | | | | | | |
| 26 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min × flow in L/min]

Relinquished By: Dean Jacobsen Signature: Date/Time: 3/16/2020


! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !

IX. FLOOR PLANS


**Two Family Dwelling
1951-51A North 33rd Street
Milwaukee, Wisconsin**




Basement Floor Plan



Two Family Dwelling
1951-51A North 33rd Street
Milwaukee, Wisconsin



1st Floor Plan



**Two Family Dwelling
1951-51A North 33rd Street
Milwaukee, Wisconsin**



2nd Floor Plan



X. HMG CERTIFICATION

Company Certificate

This certifies that

HARENDA MANAGEMENT GROUP

1237 W BRUCE ST
MILWAUKEE WI 53204-1218

is certified under ch. DHS 159, Wis. Adm. Code as a

Asbestos Company -- Primary

Certificate Issue Date: 07/23/2019
Expiration Date: 08/31/2021, 12:01 a.m.
Certification #: CAP-480540

Wisconsin Department of Health Services
Division of Public Health
Bureau of Environmental and Occupational Health
Asbestos & Lead Section
PO Box 2659
Madison WI 53701-2659
Phone: (608) 261-6876



Miriam Hasan
Miriam Hasan, Unit Supervisor





ASBESTOS INSPECTOR

Issued By

STATE OF WISCONSIN

Dept. of Health Services

Cecil James Trawick Jr

5624 N 97th Street

Milwaukee WI 53227 2502

| | | | |
|------------|-----------------|------------|--------|
| | | 222 lbs | 5' 08" |
| All-104769 | Exp: 10/02/2020 | 07/09/1971 | |

Training due by: 10/02/2020

COPY



PRE-DEMOLITION INSPECTION REPORT

Job Site:

**Fire Damaged
Two Family Dwelling
2931 West Vliet Street
Milwaukee, Wisconsin**

For:

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613


**HMG Report No.: 19-400-037.2931
Inspector: Damian Rogowski
Contract No.: 360-19-0975**

Prepared by:


HARENDA MANAGEMENT GROUP
1237 West Bruce Street
Milwaukee, Wisconsin 53204
(414) 383-4800

May 2019

Signature Page
Pre-Demolition Inspection Report
Two Family Dwelling
2931 West Vliet Street
Milwaukee, Wisconsin



Dean Jacobsen
Asbestos Inspector No. AII – 14370
Expiration Date: 12/2/19
Harenda Management Group



Damian Rogowski
Asbestos Inspector No. AII – 161300
Expiration Date: 3/19/20
Harenda Management Group

May 6, 2019

City of Milwaukee
Department of Neighborhood Services
Attn: Marge Piwaron
841 North Broadway 1st Floor
Milwaukee, Wisconsin 53202-3613

RE: Pre-Demolition Inspection Report
2931 West Vliet Street
Milwaukee, WI

Harenda Management Group has completed the pre-demolition inspection of the two family dwelling at 2931 West Vliet Street, Milwaukee, Wisconsin, as per the referral from the City of Milwaukee Department of Neighborhood Services. The inspection and results are described in the following report. Please contact me at (414) 383-4800 if you have any questions.

Sincerely,

HARENDA MANAGEMENT GROUP



Dean Jacobsen
Asbestos Inspector No. AII – 14370

EXECUTIVE SUMMARY

Harenda Management Group was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection of the two family dwelling at 2931 West Vliet Street, Milwaukee, Wisconsin, prior to demolition. HMG conducted a visual inspection for asbestos and universal wastes. HMG collected asbestos bulk samples for laboratory analysis.

Asbestos was detected above 1% in exterior caulk, duct wrap, and bathroom transite panel sampled during the inspection. Asbestos was detected at less than 1% in window glazing compound as verified by point counting. Asbestos was assumed to be in the asphalt roofing. Results are in Section IV of this report.

TABLE OF CONTENTS
Pre-Demolition Inspection Report

| | | |
|-------|---|----|
| I. | Introduction..... | 1 |
| II. | Asbestos Inspection | 1 |
| III. | Asbestos Laboratory | 2 |
| | A. Method of Analysis | |
| IV. | Asbestos Findings and Observations | 2 |
| V. | Exclusions | 5 |
| VI. | Limitations | 5 |
| VII. | Pre-Demolition Environmental Checklist..... | 6 |
| VIII. | Asbestos Laboratory Results..... | 10 |
| IX. | Floor Plans | 11 |
| X. | HMG Certifications | 12 |

I. INTRODUCTION

Harenda Management Group (HMG) was retained by the City of Milwaukee Department of Neighborhood Services to conduct an inspection for suspect asbestos containing materials in the two family dwelling and garage at 2931 West Vliet Street, Milwaukee, Wisconsin. The dwelling is a two story wood framed structure with vinyl, asphalt, and wood walls and asphalt roofing. The garage has wood walls and asphalt roofing.

II. ASEBSTOS INSPECTION

Marge Piwaron, of the City of Milwaukee Department of Neighborhood Services, authorized HMG to conduct a building inspection and to analyze samples collected during the inspection.

On April 17, 2019, HMG conducted an asbestos inspection of a two family dwelling and garage, scheduled for mechanical demolition, located at 2931 West Vliet Street, Milwaukee, Wisconsin. The inspection was conducted by Damian Rogowski, Wisconsin License No. AII – 161300, and the report was written by Dean Jacobsen, Wisconsin License No. AII – 14370.

The inspection was comprised of these elements:

1. A visual determination as to the extent of suspect asbestos containing materials within the buildings.
2. Sampling and documentation of observable suspect asbestos containing materials.
3. Quantification of observable asbestos containing materials existing within the spaces.

The results of the inspection integrated with the Polarized Light Microscopy with Dispersion Staining (PLM/DS) analysis of bulk samples collected are outlined in this document.

The following types of suspect materials were observed and inspected to determine if asbestos containing materials were present in the building as required by US EPA NESHAP regulation 40 CFR 61 Subpart M, and NR 447 of the Wisconsin Administrative Code:

- Window glazing compound
- Ceiling tile
- Caulk
- Asphalt shingle siding
- Paper insulation
- Flue packing
- Duct wrap
- Drywall/joint compound
- Plaster
- Blown in insulation
- Texture
- Transite panel
- Asphalt roofing

- Mastics

A listing of specific homogeneous materials and homogeneous material codes are in the Findings and Observations section following the results table.

III. ASEBSTOS LABORATORY

A. METHOD OF ANALYSIS

Analysis is performed by using the bulk samples for visual observation and slide preparation(s) for microscopical examination and identification. The slides are analyzed for asbestos (chrysotile, amosite, crocidolite, anthophyllite, and actinolite/tremolite), fibrous non asbestos constituents (mineral wool, paper, etc.), and nonfibrous constituents. Asbestos is identified by refractive indices (obtained by using dispersion staining), morphology, color, pleochroism, birefringence, extinction characteristics, and signs of elongation. The same characteristics are used to identify the non asbestos constituents.

The microscopist visually estimates relative amounts of each constituent using a stereoscope if necessary. The test results are based on a visual determination of relative volume of the bulk sample components. The results are valid only for the item tested. Current US EPA NESHAP regulations state asbestos materials means material containing more than 1% asbestos as determined using the method specified in Appendix E, Subpart E, 40 CFR Part 763 Section I, Polarized Light Microscopy. Bold values below indicate that the material contains more than 1% asbestos. Refer to 29 CFR 1926.1101 (Construction) and 29 CFR 1910.1001 (General Industry) for specific OSHA requirements.

IV. ASEBSTOS FINDINGS AND OBSERVATIONS

The following are the laboratory results. The laboratory report is in Appendix A.

| Sample # | Location and Description | Results | Homogeneous Code |
|----------|---|-----------------------------------|------------------|
| 1 | Garage Exterior – on east window – glazing compound | Positive 2% Chrysotile | MPG |
| 1 | POINT COUNT RESULT | Trace 0.5% Chrysotile | MPG |
| 2 | Garage Interior – pile on floor – 2' x 4' ceiling tile | Negative | MSCT24 |
| 3 | House Exterior – on east window – white caulk | Negative | MCLKw |
| 4 | House Exterior – on north window – white caulk | Negative | MCLKw |
| 5 | House Exterior – around south window on asphalt siding – black caulk | Positive 4% Chrysotile | MCLKk |
| 6a | House Exterior – east wall under vinyl siding – asphalt shingle siding | Negative | MSS |
| 6b | House Exterior – east wall under asphalt shingle siding – fiber layer | Negative | MSS |
| 7a | House Exterior – north wall under vinyl siding – asphalt shingle siding | Negative | MSS |
| 7b | House Exterior – north wall under asphalt shingle siding – fiber layer | Negative | MSS |

| Sample # | Location and Description | Results | Homogeneous Code |
|-----------|--|--------------------------------|------------------|
| 8a | House Exterior – south wall under vinyl siding – asphalt shingle siding | Negative | MSS |
| 8b | House Exterior – south wall under asphalt shingle siding – fiber layer | Negative | MSS |
| 9 | House Exterior – east wall under wood siding – beige paper insulation | Negative | MPIe |
| 10 | House Exterior – north wall under wood siding – beige paper insulation | Negative | MPIe |
| 11 | House Exterior – south wall under wood siding – beige paper insulation | Negative | MPIe |
| 12 | Basement – on chimney – flue packing | Negative | TFP |
| 13 | Basement – on east window – glazing compound | Negative | MPG |
| 14 | Basement – on west window – glazing compound | Negative | MPG |
| 15 | Basement – on north duct – duct wrap | Positive 60% Chrysotile | TDW |
| 16 | Basement – on north duct – duct wrap | Positive 60% Chrysotile | TDW |
| 17 | Basement – on north duct – duct wrap | Positive 60% Chrysotile | TDW |
| 18a | 1 st floor – kitchen – south wall – drywall | Negative | MDW |
| 18b | 1 st floor – kitchen – south wall – joint compound | Negative | MDW |
| 19a | 1 st floor – dining room – east wall – drywall | Negative | MDW |
| 19b | 1 st floor – dining room – east wall – joint compound | Negative | MDW |
| 20a | 1 st floor – bathroom – south wall – drywall | Negative | MDW |
| 20b | 1 st floor – bathroom – south wall – joint compound | Negative | MDW |
| 21 | 1 st floor – kitchen – south wall under drywall – plaster | Negative | SPI |
| 22 | 1 st floor – dining room – east wall under drywall – plaster | Negative | SPI |
| 23 | 1 st floor – south bedroom – south wall under drywall – plaster | Negative | SPI |
| 24 | House Exterior – in north wall – blown in insulation | Negative | MBI |
| 25 | House Exterior – in east wall – blown in insulation | Negative | MBI |
| 26 | House Exterior – in west wall – blown in insulation | Negative | MBI |
| 27 | 1 st floor – bathroom – on north wall – texture | Negative | STX |
| 28 | 1 st floor – bathroom – on north wall – texture | Negative | STX |
| 29 | 1 st floor – bathroom – on north wall – texture | Negative | STX |
| 30 | 1st floor – bathroom – north wall – transite panel | Positive 20% Chrysotile | MTP |

Three (3) of the materials sampled contain greater than 1% asbestos and are asbestos containing materials (ACM):

| Material | Homogeneous Code | Location | Approximate Quantity | Condition |
|----------------|------------------|---|----------------------|-----------|
| Black Caulk | MCLKk | House Exterior Around Doors & Windows on Asphalt Siding | 13 Windows & 4 Doors | Poor |
| Duct Wrap | TDW | Basement on Ducts | 20 SF | Poor |
| Transite Panel | MTP | 1st Floor Bathroom North Wall | 40 SF | Poor |

Assumed Category I Non-Friable Asbestos Containing Material:

| Material | Location | Approximate Quantity | Condition |
|-----------------------------|----------------------|----------------------|-----------|
| Asphalt Shingles & Flashing | House & Garage Roofs | 1,700 SF | Poor |

Three (3) of the materials sampled contain less than 1% asbestos:

| Material | Homogeneous Code | Location | Condition |
|-------------------------|------------------|------------------------|-----------|
| Window Glazing Compound | MPG | House & Garage Windows | Fair |

The window glazing compound contains less than 1% asbestos as verified by the point count method, and by definition in NR 447 is not an ACM.

Note #1: The black caulk, transite panel, and duct wrap are friable and category II non-friable asbestos containing materials. NR 447.08 requires the building owner or operator to remove all regulated asbestos containing materials (RACM) from a facility being demolished or renovated before any activity begins that would break up, dislodge or similarly disturb the material. DHS 159 requires that only a certified asbestos company with certified asbestos abatement personnel may remove ACMs from a building. Harenda Management Group recommends that the black caulk, transite panel, and duct wrap be abated prior to demolition.

Note #2: Asphalt roofing and is a category I non friable asbestos containing material and was not friable. Under NR 447 it does not currently meet the definition of regulated asbestos containing material (RACM) and need not be removed before demolition if the demolition debris does not become RACM and will be disposed at a Wisconsin licensed landfill.

Note#3: Category I – Non-Friable Asbestos Containing Materials may become RACM during mechanical demolition activities or maybe considered friable prior to demolition activities due to its condition at time of demolition.

Note#4: If additional materials are discovered during demolition that are not listed above they are to be assumed to be asbestos containing.

Note#5: A copy of this report should be transmitted to the demolition contractor.

Note#6: Additional duct wrap may be within walls and ceilings.

Homogeneous Material Codes

| | |
|--------|-------------------------|
| SPI | Plaster |
| STX | Texture |
| MPG | Window Glazing Compound |
| MSCT24 | 2' x 4' Ceiling Tile |
| MCLKw | White Caulk |
| MCLKk | Black Caulk |
| MSS | Asphalt Shingle Siding |
| MPIe | Beige Paper Insulation |
| MDW | Drywall/Joint Compound |
| MBI | Blown in Insulation |
| MTP | Transite Panel |
| TFP | Flue Packing |
| TDW | Duct Wrap |

V. EXCLUSIONS

2nd floor north section and attic not accessible due to fire damage. 1st floor floors buried in fire debris and not accessible. Not all areas within walls and ceilings were accessible, and these areas may contain suspect asbestos containing materials. Only visible or accessible areas were included in the scope of work.

HMG is not and shall not represent the building owner as its agent or representative for the purpose of the US EPA/NESHAP and/or the WDNR/NR447 regulations, as owner/operator.

This report represents the condition of the building and its visible/accessible suspect asbestos containing materials at the date and the times of the onsite inspection. Hidden materials or inaccessible materials, or those materials that could be present at the point of inspection, over and above those stated in the inspection report, are the responsibility of the building owner and the demolition contractor.

VI. LIMITATIONS

The care and skill given to our procedures insures the most reliable test results possible. HMG utilizes Schneider Laboratories Global, Inc., for our asbestos testing. The findings and conclusions of HMG represent our professional opinions extrapolated from limited data. Significant limited data is gathered during the course of the preliminary asbestos specific site assessment. No other warranty is expressed or implied. Prior to any abatement or renovation activities, it is recommended that HMG be provided the opportunity to review such plans in order that the inspection and assessments contained herein are properly interpreted and implemented.

This report and the information contained herein are prepared for the sole and exclusive use and possession of the City of Milwaukee Department of Neighborhood Services. No other person or entity may rely on this report or any information contained herein. Any dissemination of the Report or any information contained herein is strictly prohibited without prior written authorization from Harenda Management Group.

VII. PRE-DEMOLITION ENVIRONMENTAL CHECKLIST

This guide lists materials and products commonly found in buildings with examples. It is not intended as a substitute for reading the rules and statutes and making your own independent determination of their applicability to your demolition project. These examples presented here do not represent an exhaustive listing of types of materials that may be required to be removed from the building prior to demolition.

ASBESTOS

Persons conducting inspections for asbestos must hold a valid asbestos inspector certification card issued by the State of Wisconsin, Dept. of Health Services. **Please follow the Asbestos Inspection and Sampling Protocol for Buildings to be Demolished or Renovated.**

CFCs and HALONS

Equipment that may contain CFCs and Halons:

| | |
|------------|--|
| <u>N/A</u> | Air Conditioners (roof top, room, and central) |
| <u>N/A</u> | Dehumidifiers |
| <u>N/A</u> | Heat Pumps |
| <u>N/A</u> | Refrigerators, Freezers, Chillers |
| <u>N/A</u> | Vending Machines, Food Display Cases |
| <u>N/A</u> | Walk-in Coolers |
| <u>N/A</u> | Water Fountains (bubblers) |
| <u>N/A</u> | Fire Extinguishers (both portable and installed HALON suppression systems) |
| <u>N/A</u> | Water Coolers |

LEAD

Lead or Lead Based Paint (LBP) is common in many older buildings. When recycling construction and demolition debris, be aware that wood containing lead paint may not be chipped and spread for landscaping. State law also prohibits the sale or transfer of any fixture or other object containing LBP that might be placed upon any surface of a dwelling, which is ordinarily accessible to children.

MERCURY

Products that may contain mercury:

LIGHTING

- | | |
|------------|--|
| <u>5</u> | Fluorescent Lights – Garage |
| <u>N/A</u> | High Intensity Discharge -Metal Halide -High Pressure Sodium -Mercury Vapor |
| <u>N/A</u> | Neon |
| <u>N/A</u> | Switches for lighting using mercury relays -Look for any control associated with exterior or automated lighting systems such as "Silent" wall switches. |

HVAC

Check thermostats and any control associated with air handling units for switches containing mercury.

HEATING, VENTILATING AND AIR CONDITIONING SYSTEMS

- | | |
|------------|-----------------|
| <u>N/A</u> | Old Thermostats |
| <u>N/A</u> | Aquastats |
| <u>N/A</u> | Firestats |
| <u>N/A</u> | Manometers |
| <u>N/A</u> | Thermometers |

BOILERS, FURNACES, HEATERS AND TANKS – 1 Furnace & 1 Water Heater in Basement

- | | |
|------------|---------------------------------------|
| <u>N/A</u> | Mercury Flame Sensors by pilot lights |
| <u>N/A</u> | Manometers, Thermometers, Gauges |
| <u>N/A</u> | Pressure-trol |
| <u>N/A</u> | Float or Level Controls |
| <u>N/A</u> | Space Heaters |

ELECTRICAL SYSTEMS – 1 Electrical Box in Basement

| | |
|------------|-------------------------------|
| <u>N/A</u> | Load Meters and Supply Relays |
| <u>N/A</u> | Phase Splitters |
| <u>N/A</u> | Microwave Relays |
| <u>N/A</u> | Mercury Displacement Relays |

PCBs

For electrical devices manufactured prior to 1987, it is safe to assume that they contain PCBs and should be managed accordingly. Most equipment manufactured after this time will say "PCB Free". The following is a list of areas in a building where PCBs may be found:

| | |
|------------|--|
| <u>N/A</u> | Transformers |
| <u>N/A</u> | Capacitors (appliances, electronic equipment) |
| <u>N/A</u> | Heat Transfer Equipment |
| <u>3</u> | Ballasts – Garage |
| <u>N/A</u> | Specialty Paints (such as for swimming pools or other industrial applications) |
| <u>N/A</u> | Sumps or Oil Traps (in maintenance and industrial facilities) |

OTHER ENVIRONMENTAL ISSUES

| | |
|------------|------------------|
| <u>N/A</u> | Hazardous Waste |
| <u>N/A</u> | Oil Tanks |
| <u>N/A</u> | Well Abandonment |
| <u>N/A</u> | Junk Auto Tires |
| <u>N/A</u> | Junk Vehicles |

* 1 Oxygen Tank, 40 Gallons Motor Oil, and 15 Gallons Paint in Garage

* 1 Gas Meter on Exterior

VIII. ASBESTOS LABORATORY RESULTS



Customer: Harenda Management Group (5065)
Address: 1237 West Bruce Street
Milwaukee, WI 53204

Order #: 311784

Received 04/22/19
Analyzed 04/26/19
Reported 04/29/19

Attn:

Project:

Location: Wisconsin
Number: 19-400-037.2931

Method: EPA 600/R-93/116 & 600/M4-82-020

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|--|----------|-----------|-----------------|---|
| 311784-001 | 04/17/19 | 1 | Wisconsin | | |
| Layer 1: | Granular Material Beige, Granular | | | 2% CHRYSOTILE | 98% NON FIBROUS MATERIAL |
| 311784-002 | 04/17/19 | 2 | Wisconsin | | |
| Layer 1: | Ceiling Tile Beige, Fibrous | | | None Detected | 40% CELLULOSE FIBER 40% MINERAL/GLASS WOOL 20% NON FIBROUS MATERIAL |
| 311784-003 | 04/17/19 | 3 | Wisconsin | | |
| Layer 1: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 311784-004 | 04/17/19 | 4 | Wisconsin | | |
| Layer 1: | Granular Material White, Granular | | | None Detected | 100% NON FIBROUS MATERIAL |
| 311784-005 | 04/17/19 | 5 | Wisconsin | | |
| Layer 1: | Bituminous Material Black, Bituminous | | | 4% CHRYSOTILE | 96% NON FIBROUS MATERIAL |
| 311784-006 | 04/17/19 | 6 | Wisconsin | | |
| Layer 1: | Shingle Black, Bituminous/Granular | | | None Detected | 5% CELLULOSE FIBER 5% MINERAL/GLASS WOOL 90% NON FIBROUS MATERIAL |
| | Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | |
| Layer 2: | Fibrous Material Beige, Fibrous | | | None Detected | 40% CELLULOSE FIBER 40% MINERAL/GLASS WOOL 20% NON FIBROUS MATERIAL |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 19-400-037.2931

Method: EPA 600/R-93/116 & 600/M4-82-020**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|--|----------------------------|----------|-----------|-----------------|---------------------------|
| 311784-007 | 04/17/19 | 7 | Wisconsin | | |
| Layer 1: | Shingle | | | None Detected | 5% CELLULOSE FIBER |
| | Black, Bituminous/Granular | | | | 5% MINERAL/GLASS WOOL |
| | | | | | 90% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| Layer 2: | Fibrous Material | | | None Detected | 40% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 40% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 311784-008 | 04/17/19 | 8 | Wisconsin | | |
| Layer 1: | Shingle | | | None Detected | 5% CELLULOSE FIBER |
| | Black, Bituminous/Granular | | | | 5% MINERAL/GLASS WOOL |
| | | | | | 90% NON FIBROUS MATERIAL |
| Sample was inhomogenous, subsamples of each component were analyzed separately. | | | | | |
| Layer 2: | Fibrous Material | | | None Detected | 40% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 40% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 311784-009 | 04/17/19 | 9 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 311784-010 | 04/17/19 | 10 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 311784-011 | 04/17/19 | 11 | Wisconsin | | |
| Layer 1: | Paper | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 311784-012 | 04/17/19 | 12 | Wisconsin | | |
| Layer 1: | Granular Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White, Granular | | | | |
| 311784-013 | 04/17/19 | 13 | Wisconsin | | |
| Layer 1: | Brittle Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Brittle | | | | |
| 311784-014 | 04/17/19 | 14 | Wisconsin | | |
| Layer 1: | Brittle Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Tan, Brittle | | | | |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 19-400-037.2931

Method: EPA 600/R-93/116 & 600/M4-82-020**PLM Analysis**

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|-------------------|---------------------|----------|-----------|-----------------|---------------------------|
| 311784-015 | 04/17/19 | 15 | Wisconsin | | |
| Layer 1: | Insulation | | | 60% CHRYSOTILE | 20% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 10% MINERAL/GLASS WOOL |
| | | | | | 10% NON FIBROUS MATERIAL |
| 311784-016 | 04/17/19 | 16 | Wisconsin | | |
| Layer 1: | Insulation | | | 60% CHRYSOTILE | 20% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 10% MINERAL/GLASS WOOL |
| | | | | | 10% NON FIBROUS MATERIAL |
| 311784-017 | 04/17/19 | 17 | Wisconsin | | |
| Layer 1: | Insulation | | | 60% CHRYSOTILE | 20% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 10% MINERAL/GLASS WOOL |
| | | | | | 10% NON FIBROUS MATERIAL |
| 311784-018 | 04/17/19 | 18 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |
| Layer 2: | Joint Compound | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White, Granular | | | | |
| 311784-019 | 04/17/19 | 19 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |
| Layer 2: | Joint Compound | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White, Granular | | | | |
| 311784-020 | 04/17/19 | 20 | Wisconsin | | |
| Layer 1: | Drywall | | | None Detected | 5% CELLULOSE FIBER |
| | White, Powdery | | | | 95% NON FIBROUS MATERIAL |
| Layer 2: | Joint Compound | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Off White, Granular | | | | |
| 311784-021 | 04/17/19 | 21 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Beige, Granular | | | | |
| 311784-022 | 04/17/19 | 22 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Beige, Granular | | | | |

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.

Project:

Location: Wisconsin
Number: 19-400-037.2931

Method: EPA 600/R-93/116 & 600/M4-82-020

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|------------|-------------------|----------|-----------|-----------------|---------------------------|
| 311784-023 | 04/17/19 | 23 | Wisconsin | | |
| Layer 1: | Plaster | | | None Detected | 100% NON FIBROUS MATERIAL |
| | Beige, Granular | | | | |
| 311784-024 | 04/17/19 | 24 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 311784-025 | 04/17/19 | 25 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 311784-026 | 04/17/19 | 26 | Wisconsin | | |
| Layer 1: | Insulation | | | None Detected | 65% CELLULOSE FIBER |
| | Beige, Fibrous | | | | 15% MINERAL/GLASS WOOL |
| | | | | | 20% NON FIBROUS MATERIAL |
| 311784-027 | 04/17/19 | 27 | Wisconsin | | |
| Layer 1: | Granular Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White, Granular | | | | |
| 311784-028 | 04/17/19 | 28 | Wisconsin | | |
| Layer 1: | Granular Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White, Granular | | | | |
| 311784-029 | 04/17/19 | 29 | Wisconsin | | |
| Layer 1: | Granular Material | | | None Detected | 100% NON FIBROUS MATERIAL |
| | White, Granular | | | | |
| 311784-030 | 04/17/19 | 30 | Wisconsin | | |
| Layer 1: | Hard Material | | | 20% CHRYSOTILE | 80% NON FIBROUS MATERIAL |
| | Light Gray, Hard | | | | |

EPA Regulatory Limit: 1%

Total layers analyzed on order: 36



Analyst **Mohammed Hashim**

311784-04/29/19 08:37 AM



Reviewed By: **Hind Eldanaf**

Microscopy Supervisor

Reporting Limit: 1% Gravimetrically Reduced Reporting Limit: 0.01% PLM analysis is based on Visual Estimation and NESHAP recommends that any asbestos content less than 10 percent be verified by PLM Point Count or TEM Analysis. The EPA recommends that any vermiculite should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the laboratory. The test results reported relate only to the samples submitted.



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabin.com • info@slabin.com

311784



30

V:\311\311784

fghraizi
 UPS

4/22/2019 9:33:24 AM
 1Z2E2899846 902951

| | | | |
|---|------------------------------|---|--|
| Submitting Co Harenda Management Group | | State of Collection WI | Cert. Required <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # 5065 | Phone (414) 647-1530 |
| Milwaukee, WI 53204 | | Email dean.jacobsen@kphenviromenmtal.com | |
| Project Name | | PO # | |
| Project Location Wisconsin | Special Instructions: | | |
| Project Number 19-400-037.2931 | | | |
| Collected By | | | |

| Turn Around Time | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|--|--|---|--|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | Metals Total <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | TCLP <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | Microbiology <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens <hr/> Sub-Contract <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |
| | | Asbestos in Air <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | Gravimetric <input checked="" type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | Miscellaneous <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 1 | 4/17/19 | | | | | | | | |
| 2 | | | | | | | | | |
| 3 | | | | | | | | | |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: [Signature] Date/Time 4/19/19 (700)

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabin.com • info@slabin.com

| | | | |
|---|-----------------------|--|---|
| Submitting Co: Harenda Management Group | | State of Collection: WI | Cert Required: <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct #: 5065 | Phone: (414) 647-1530 |
| Milwaukee, WI 53204 | | Email: dean.jacobsen@kphenvironmenmtal.com | |
| Project Name: | | PO #: | |
| Project Location: Wisconsin | Special Instructions: | | |
| Project Number: 19-400-037.2931 | | | |
| Collected By: | | | |

| Turn/Around Time* | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|--|---|--|--|---|--|
| <input type="checkbox"/> 2 Hour * <input type="checkbox"/> Same day * <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | Metals Total <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | TCLP <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | Microbiology <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens Sub-Contract <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |
| | | Asbestos in Air <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | Gravimetric <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | Miscellaneous <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 11 | 4/17/19 | | | | | | | | |
| 12 | | | | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | | | | | | | | |
| 16 | | | | | | | | | |
| 17 | | | | | | | | | |
| 18 | | | | | | | | | |
| 19 | | | | | | | | | |
| 20 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: [Signature] Date/Time: 4/19/19 1700

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabinc.com • info@slabinc.com

| | | | |
|---|-----------------------|---|--|
| Submitting Co: Harenda Management Group | | State of Collection: WI | Cert. Required: <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct.#: 5065 | Phone: (414) 647-1530 |
| Milwaukee, WI 53204 | | Email: dean.jacobsen@kphenvironmental.com | |
| Project Name: | | PO #: | |
| Project Location: Wisconsin | Special Instructions: | | |
| Project Number: 19-400-037.2931 | | | |
| Collected By: | | | |

| Turn Around Time* | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|---|---|---|---|--|---|
| <input type="checkbox"/> 2 Hour* <input type="checkbox"/> Same day* <input type="checkbox"/> 1 business day <input type="checkbox"/> 2 business days <input type="checkbox"/> 3 business days <input checked="" type="checkbox"/> 5 business days <small>* not available for all tests ** past 3 PM the TAT will begin next business day Please schedule rush tests in advance.</small> | <input type="checkbox"/> Air <input type="checkbox"/> Paint <input type="checkbox"/> Soil <input type="checkbox"/> Wipe <input checked="" type="checkbox"/> Bulk <input type="checkbox"/> Waste Water <input type="checkbox"/> Ground Water <input type="checkbox"/> Drinking Water <input type="checkbox"/> TSP / PM10 <input type="checkbox"/> _____ | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| | | <input checked="" type="checkbox"/> PLM <input type="checkbox"/> PLM Qualitative <input type="checkbox"/> 400 Point Count <input type="checkbox"/> 1000 Point Count <input type="checkbox"/> Gravimetric Prep | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Chromium VI <input type="checkbox"/> Mercury <input type="checkbox"/> _____ | <input type="checkbox"/> Lead <input type="checkbox"/> RCRA 8 Metals <input type="checkbox"/> Full TCLP <small>(w/ organics 10 Day)</small> | <input type="checkbox"/> BACT (MPN/PA) <input type="checkbox"/> Mold Direct Exam <input type="checkbox"/> Allergens |
| | | Asbestos in Air | Gravimetric | Miscellaneous | Sub-Contract |
| | | <input type="checkbox"/> PCM <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Total Dust NIOSH 0500 <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> Silica FTIR (7602) <input type="checkbox"/> _____ | <input type="checkbox"/> TEM Chatfield <input type="checkbox"/> TEM AHERA <input type="checkbox"/> TEM 7402 <input type="checkbox"/> Silica XRD (7500) |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 21 | 4/19/0 | | | | | | | | |
| 22 | | | | | | | | | |
| 23 | | | | | | | | | |
| 24 | | | | | | | | | |
| 25 | | | | | | | | | |
| 26 | | | | | | | | | |
| 27 | | | | | | | | | |
| 28 | | | | | | | | | |
| 29 | | | | | | | | | |
| 30 | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis
¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: [Signature] Date/Time: 4/19/09 1700

! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !



Customer: Harenda Management Group (5065)
Address: 1237 West Bruce Street
Milwaukee, WI 53204

| | |
|-----------------|--------|
| Order #: | 313092 |
|-----------------|--------|

Received 04/30/19
Analyzed 05/02/19
Reported 05/03/19

Attn:

Project:

Location: Wisconsin
Number: 19-400-037.2931

Method: EPA 600/R-93/116 & 600/M4-82-020 with Point Count

PLM Analysis

| Sample ID | Collected | Cust. ID | Location | Asbestos Fibers | Other Materials |
|---|-----------|----------|-----------|------------------|-----------------------------|
| 313092-001 | 04/17/19 | 1 | Wisconsin | 0.50% CHRYSOTILE | 99.50% NON FIBROUS MATERIAL |
| Layer 1: Granular Material Beige, Granular, Homogenous | | | | | |

EPA Regulatory Limit: 1%
Total layers analyzed on order: 1

313092-05/03/19 11:46 AM

Analyst **Mohammed Hashim**

Reviewed By: **Hind Eldanaf**
Microscopy Supervisor

Reporting limit: 0.25% Samples analyzed by the EPA Point Count test method. The EPA recommends that any vermiculite sample with a trace (<1) or greater amount of asbestos is a concern and should be treated as Asbestos Containing Material (ACM). This report must not be reproduced except in full with the approval of the lab, and must not be used to claim NVLAP or other government agency endorsement. The test results reported relate only to the samples submitted.



SCHNEIDER LABORATORIES GLOBAL, INC.

2512 West Cary Street, Richmond, Virginia 23220-5117
 804-353-6778 • 800-785-LABS (5227) • Fax 804-359-1475
 www.slabin.com • info@slabin.com

313092 S 1

 V:\313\313092
 vthrasher 4/30/2019 11:05:00 AM
 Hand Delivered

| | | | | | |
|------------------------|--------------------------|---------------------------------------|------------------------------------|----------------|--|
| Submitting Co. | Harenda Management Group | State of Collection | WI | Cert. Required | <input type="checkbox"/> YES <input type="checkbox"/> NO |
| 1237 West Bruce Street | | Acct # | 5065 | Phone | (414) 647-1530 |
| Milwaukee, WI 53204 | | Email | dean.jacobsen@kphenvironmental.com | | |
| Project Name | | PO # | | | |
| Project Location | Wisconsin | Special Instructions: Order 311784 | | | |
| Project Number | 19-400-037.2931 | | | | |
| Collected By | | | | | |

| Turn Around Time ** | Matrix | Tests/Analytes (Select ALL that Apply) Blank spaces are for additional analytes | | | |
|---|--|---|--|---|--|
| | | Asbestos in Bulk | Metals Total | TCLP | Microbiology |
| <input type="checkbox"/> 2 Hour * | <input type="checkbox"/> Air | <input type="checkbox"/> PLM | <input type="checkbox"/> Lead | <input type="checkbox"/> Lead | <input type="checkbox"/> BACT (MPN/PA) |
| <input type="checkbox"/> Same day * | <input type="checkbox"/> Paint | <input type="checkbox"/> PLM Qualitative | <input type="checkbox"/> RCRA 8 Metals | <input type="checkbox"/> RCRA 8 Metals | <input type="checkbox"/> Mold Direct Exam |
| <input type="checkbox"/> 1 business day | <input type="checkbox"/> Soil | <input checked="" type="checkbox"/> 400 Point Count | <input type="checkbox"/> Chromium VI | <input type="checkbox"/> Full TCLP | <input type="checkbox"/> Allergens |
| <input type="checkbox"/> 2 business days | <input type="checkbox"/> Wipe | <input type="checkbox"/> 1000 Point Count | <input type="checkbox"/> Mercury | (w/ organics 10 Day) | Sub-Contract |
| <input checked="" type="checkbox"/> 3 business days | <input checked="" type="checkbox"/> Bulk | <input type="checkbox"/> Gravimetric Prep | | | <input type="checkbox"/> TEM Chatfield |
| <input type="checkbox"/> 5 business days | <input type="checkbox"/> Waste Water | Asbestos in Air | Gravimetric | Miscellaneous | <input type="checkbox"/> TEM AHERA |
| * not available for all tests | <input type="checkbox"/> Ground Water | <input type="checkbox"/> PCM | <input type="checkbox"/> Total Dust NIOSH 0500 | <input type="checkbox"/> Silica FTIR (7602) | <input type="checkbox"/> TEM 7402 |
| ** past 3 PM the TAT will begin next business day | <input type="checkbox"/> Drinking Water | <input type="checkbox"/> PCM-B Rules | <input type="checkbox"/> Resp. Dust NIOSH 0600 | <input type="checkbox"/> | <input type="checkbox"/> Silica XRD (7500) |
| Please schedule rush tests in advance | <input type="checkbox"/> TSP / PM10 | | | | |
| | <input type="checkbox"/> | | | | |

| Sample # | Date Sampled | Time Sampled | Sample Identification (Employee, Bldg, Material, Type ¹) | Wipe Area | Time ² | | Flow Rate ³ | | Total Air ⁴ |
|----------|--------------|--------------|---|-----------|-------------------|------|------------------------|------|------------------------|
| | | | | | Start | Stop | Start | Stop | |
| 1 | 4/17/19 | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |

For Aqueous and Solid samples ensure enough sample is sent for duplicate and spike analysis

¹Type: A=Area, B=Blank, P=Personal, E=Excursion ²Beginning/End of Sample Period ³Liters/Minute ⁴Volume in Liters [time in min x flow in L/min]

Relinquished By: Dean Jacobsen Signature: *Dean Jacobsen* Date/Time: 4/29/19 1130


! ALL SHADED FIELDS MUST BE FILLED TO AVOID DELAYS !

IX. FLOOR PLANS

**Two Family Dwelling
2931 West Vliet Street
Milwaukee, Wisconsin**





Basement Floor Plan



**Two Family Dwelling
2931 West Vliet Street
Milwaukee, Wisconsin**



1st Floor Plan



X. HMG CERTIFICATION

Company Certificate

This certifies that

HARENDA MANAGEMENT GROUP

1237 W BRUCE ST.
MILWAUKEE WI 53204-1218

is certified under ch. DHS 159, Wis.Adm.Code as a

Asbestos Company - Primary

Certificate Issue Date: 06/23/2017
Expiration Date: 08/31/2019, 12:01 a.m.
Certification #: CAP-480540

Wisconsin Department of Health Services
Division of Public Health
Bureau of Environmental and Occupational Health
Asbestos & Lead Section
PO Box 2659
Madison WI 53701-2659
Phone: (608) 261-6876



Shelley A Bruce
Shelley A Bruce,
Unit Supervisor



Tony Evers
Governor

Andrea Palm
Secretary



State of Wisconsin
Department of Health Services

DIVISION OF PUBLIC HEALTH

1 WEST WILSON STREET

P O BOX 2659
MADISON WI 53701-2659

Telephone: 608 266-1251
FAX: 608 267-2832
TTY: 888-701-1253
dhs.wisconsin.gov

February 5, 2019

DAMIAN SCOTT ROGOWSKI
3536 COUNTY ROAD H
FRANKSVILLE WI 53126-9211

ID# AII-161300

Congratulations! Your new Wisconsin certification card is enclosed. Please look it over and call us right away if anything on your blue card is wrong.

Follow Wisconsin law by making sure that you:

1. Have your blue card with you when doing regulated work.
2. Work safely using the methods you learned in training.
3. Keep your mailing address up to date. We mail a reminder when it's time to renew your blue card. Update your address by emailing DHSAsbestosLead@wi.gov, by using our Lead and Asbestos Online Certification website, www.dhs.wisconsin.gov/waldo, or by mailing a note to:

Lead and Asbestos Section
1 W. Wilson St., Room 137
P.O. Box 2659
Madison WI 53701-2659
4. Take refresher training well before the "Training due by" date printed on your blue card.
 - o Asbestos-certified individuals must refresh in Wisconsin no earlier than **90 days** before the due date to keep the same expiration date.
Find asbestos training providers at www.dhs.wisconsin.gov/asbestos.
 - o Lead-certified individuals can refresh up to **1 year** before the due date.
Find lead training providers at www.dhs.wisconsin.gov/lead.
5. Apply to renew your card at least **1 month** before the "Exp." date on your blue card.
6. Be associated with a certified company when doing regulated work in Wisconsin. If you work for yourself, you must certify your own company under a name of your choosing. Otherwise, you must be employed by a certified company. Get a company application form at www.dhs.wisconsin.gov/lead or www.dhs.wisconsin.gov/asbestos.
7. **Don't** conduct regulated work after your blue card expires. This could result in an enforcement action.

By getting certified and working safely, you pro
professional responsibility. Contact us if you l
below and on the back of your blue card.

The Lead and Asbestos Certification Program
(608) 261-6876
DHSAsbestosLead@wi.gov
www.dhs.wisconsin.gov/asbestos
www.dhs.wisconsin.gov/lead

COPY





Policy Prohibiting Firearms and Dangerous Weapons in the Workplace

Department of Employee Relations

November 10, 2011

Revised February 27, 2012



Policy Statement

The City of Milwaukee has a zero tolerance policy for firearms and dangerous weapons in the workplace. Accordingly, the City of Milwaukee prohibits employees from carrying or possessing a firearm or dangerous weapon while acting in the course and scope of their employment for and on behalf of the City of Milwaukee. This policy applies to all general city employees, including students, volunteers, staffing agency workers or contractors working in the course and scope of their employment with the City of Milwaukee.

Definitions

Employee - Employee includes any person, excluding law enforcement personnel, who performs services for the City of Milwaukee, either compensated or uncompensated.

Firearm or dangerous weapon - for purposes of this policy a firearm or dangerous weapon includes, but is not limited to, the following:

- (1) A firearm, whether loaded or unloaded, from which a shot may be discharged including but not limited to handguns, pistols, revolvers, shotguns, rifles, and bb guns;
- (2) A gun that can discharge a shot or a projectile by means of an explosive or gas, or compressed air;
- (3) A device designed to be used as a weapon, from which can be expelled a projectile by the force of any explosion or force of combustion;
- (4) Any weapon (including a starter gun) which will or is designed to or may readily be converted to expel a projectile by the action of an explosive;
- (5) Any destructive device;
- (6) Any device designed as a weapon and capable of producing great bodily harm, including but not limited to, stun guns, stun batons;
- (7) An electric weapon such as a taser gun;
- (8) Any combustible or flammable liquid, or other substance, device, or instrumentality that, in a manner it is used or intended to be used, is calculated or likely to produce death or great bodily harm, or any fire that is used to produce death or great bodily harm; and,
- (9) Any knife *that is carried with intention or calculation to produce death or great bodily harm. Switchblades are specifically prohibited. (A Leatherman or other small pocket knife is permissible, as long as the blade is 3 inches or less in length. Knives intended to be used as eating utensils, and stored or maintained in office kitchens or lunchrooms do not represent a violation of this policy.)*

Prohibitions

Regardless of whether a city employee possesses a concealed weapons license or is allowed by law to possess a weapon, all employees are prohibited from possessing, transferring, carrying, selling and storing firearms or dangerous weapons while working on city property or while acting within the course of their employment when not on City of Milwaukee property. This prohibition applies anywhere City business is conducted as summarized below:

- working on property owned, leased or controlled by the City;
- performing work for the City at any location including private residences and commercial establishments and other customer or client locations;
- driving or riding as a passenger in a city vehicle;
- attending trade shows, conferences, or training on behalf of the City;
- attending City of Milwaukee directed or sponsored activities or events (intended for city employees only and not the general public) independent of venue;
- Riding any type of mass transit while on City business;
- Working off-site on behalf of the City (excluding the employee's residence);
- performing emergency or on-call work for the City after normal business hours and on weekends;
- Attending training or conferences on behalf of the City.

City employees may possess, carry and store a firearm or dangerous weapon in their own motor vehicles if they have obtained the appropriate license as required by applicable state and federal laws. Employees who use a personal vehicle in the course and scope of their employment are required to keep the permitted firearm or dangerous weapon stored out of sight and in a secure location.

Violation of this Policy is considered a serious offense that endangers the safety of employees and others. Therefore, this any offense may result in severe disciplinary action up to and including discharge from employment. When appropriate a referral to law enforcement may be made which may result in criminal charges.

Safety First

In applying this policy, no employee shall take any action that will risk his or her own safety or the safety of other individuals. No attempt should ever be made by an employee to restrain or forcibly evict an armed person from City premises. Employees in facilities without a designated Police or security force may inform individuals carrying weapons of the law and ask for their compliance. This should be done in an informative, calm and non-confrontational manner. An individual's continued non-compliance after being properly informed of the law should result in notification to the Police Department. Employees in facilities with a designated Police or security force should make all attempts to defer intervention in concealed or open carry situations to those groups by contacting designated security personnel via established reporting mechanisms.

An employee who feels an immediate risk to his or her own safety or the safety or security of others, should avoid any interaction with the individual. Steps should be taken to secure their area

and immediately contact the Police Department by calling 9-911 and their assigned building security (where applicable).

Report of Violations

Employee Violations

Employees are required to report violations of this Policy without regard to the relationship between the individual who initiates the prohibited behavior and the individual reporting it.

An employee who believes that another employee may be in violation of this policy should report the alleged violation to the employee's manager or supervisor, the department head, or the appropriate departmental Human Resources representative.

The City will promptly investigate allegations of violations of this policy. Supervisors and managers are responsible for establishing and modifying procedures as necessary to carry out and comply with this Policy in accordance with applicable laws and City ordinances. Departments are responsible for implementing protocols for handling a prohibited weapon upon discovery.

The City reserves the right to authorize searches for prohibited weapons on its property when a violation is reported or when probable cause or reasonable suspicion is present consistent with law. Employees should be aware that there is no reasonable expectation of privacy with respect to weapons in the workplace. The City's right to conduct searches includes, but is not limited to, such areas and items as lockers, desks, workstations, purses, briefcases, bags, and toolboxes, and lunch bags. Searches of the employee's work area and belongings, as described above, *may* be conducted by the employee's supervisor and another member of management. Searches of all types, including surrounding City property, personal property and the employee may be conducted by law enforcement in accordance with law should reasonable suspicion be present. Any weapon found in violation of this Policy may be confiscated. Refusal to permit a search may result in discipline up to an including discharge.

Visitor Violations

Visitors to posted no-carry City facilities are not allowed to carry a weapon on the premises. If a visitor does bring a weapon into a City facility a determination will need to be made as to the level of risk the visitor carries.

Any visitor carrying a weapon into a posted no-carry City facility is creating an elevated risk to security and safety that warrants a response leading to compliance with the law. If the visitor poses an immediate risk to security or safety the Police Department should be notified immediately by calling 9-911. The visitor should be considered an immediate risk to safety and security if he/she is acting in an aggressive, belligerent, confrontational, suspicious or in an otherwise questionable manner while carrying a weapon.

Anti-Retaliation Provision

No employee or City official may retaliate against an employee who has reported a possible violation of this policy.

Roles and Responsibilities

Employees are responsible for understanding and complying with the Policy Prohibiting Firearms and Dangerous Weapons in the Workplace. Whenever there is a question as to whether an instrument, article or substance is considered a weapon in violation of this policy, it is the employee's responsibility to seek clarification. Employees seeking clarification should direct their questions to their Department Head or the City's Security Operations Manager at 286-2145 prior to bringing the item(s) to City work sites and events, as well as City-owned or leased facilities or vehicles.

City departments shall ensure that employees complete a statement acknowledging receipt and understanding of this policy.

175232